

Interiors Scope Baseline – Bid Set Review

Interior & Exterior Framing • Sheathing • Drywall • Interior & Exterior-Cavity Insulation • Faux Wood (Phenolic) Panel Install • Painting • Vinyl Base • Roechling Wall Bumper • McCue • ACT • Drywall Ceilings • RAM Protection (Install)

Project	Lidl 1517 Norcross, GA – 4990 Jimmy Carter Blvd, Norcross, GA 30093 (Lidl US, LLC)	Bid Package #	TBD – Interiors (assign #)
Scope	Interior and exterior metal framing and sheathing; gypsum board; interior and exterior-cavity insulation; wood-look phenolic panel install; painting; resilient/bumper base; ACT; drywall ceilings; RAM protection install	Bid Due Date	TBD
Documents Reviewed	A-DWG's Bid Set (41 sheets, A101–A803; Permit Cycle 1 11/07/2025, with Cycle 2 12/17/2025 clouds on A104, A105, A400, A401, A500). Cross-referenced G101 (general notes), G106 (wall & partition types), G107 (rated assemblies), G109 (responsibility matrix). Rev. A: exterior framing/cavity insulation and phenolic panels added from A200, A302–A306, A604–A608.	Prepared	09/29/2026 – Step 0 scope baseline (no bids received yet)

Use: This is the scope checklist each interiors bid gets leveled against. Every line traces to a sheet, schedule, detail or note.

Quantities (LF/SF/EA) are not stated on the drawings for any of these trades – room counts and a few labeled dimensions are the only explicit quantities. A scaled takeoff (Bluebeam/PlanSwift) is required before any bid quantity can be verified.

Important: A105 General Note 1 says "refer to partition types," but the A-set contains no partition-type sheet. **The types are on G106**, so any bidder who priced the A-set alone may have missed them. CCD1 later reissued the A-DWG's (*documents/drawings/CCD1/A-DWG's_CCD1.pdf*). This baseline covers the bid set only and must be re-checked against CCD1 before award.

1. Framing – Types, Sizes, Locations

General (G101 General Partition Notes): Studs are 3-5/8" at 16" o.c. unless noted, 22 ga minimum. **The stud contractor must engage a registered PE and submit signed & sealed framing shop drawings (delegated design).** Partitions run floor to structure unless detailed otherwise; the partition tag covers the full length of the wall. Deflection track, back-to-back box details and a typical interior door framing detail are on G106. HM door jambs use double studs each jamb (A702 C2). Traffic door jambs use 6" double studs plus 3-5/8" horizontals (A703 B6/C6).

Type	Assembly (G106)	Locations found (sheet)	Notes
P1	6" metal stud, 5/8" GWB both sides	Breakroom Hall 109 / Employee Changing 111 walls; bakery-side stub at Breakroom Hall (3'-6 3/8" V.I.F.); Tech Area 113 / Sprinkler Riser 114 walls (A400 E7)	
P1A	4" metal stud, 5/8" GWB both sides	Breakroom Hall 109 near stair/lockers (A400 E7)	
P1B	6" stud, 5/8" GWB both sides, 22 ga sheet-metal liner between GWB and stud on outboard side	Office 107 enclosure; Office/Produce Backstock wall; Breakroom 110 walls at casework (A400 E7)	Security liner
P1C	6" stud, 5/8" GWB both sides, batt in cavity	Restrooms 104/105 enclosure; Produce Backstock 103 west wall and gridline B wall (A400 E7; A401 C7)	Acoustic
P2	2-HR (U419): 6" stud, 2 layers 1/2" Type C each side, 22 ga liner outboard side	IT Room 112, tagged " TO 12'-0" AFF " (A400 E7)	See Flag 7
P5	6" stud; sales side: 3/4" plywood to 4'-0" AFF, 5/8" GWB above; 5/8" GWB	Sales-to-BOH demising walls (A101 at gridline 6 / cooler-staging side, gridline B)	Plywood = bumper backing
P6	6" stud, 5/8" GWB one side	Sales face of Freezer 115 (gridline C); staging enclosure at traffic door 101.1 (A400 C7/E7)	

P7	4" stud + 5/8" GWB one side, 11" air gap, 4" stud + 5/8" GWB one side	Restroom chase (A401 C7, at 105)	
F1	3-5/8" stud w/ batt, 5/8" GWB interior; glass-mat sheathing + WRB exterior	Vestibule 100 above entry & storefront (A102; A302 E4/E7)	Incl. glass-mat sheathing; WRB per Flag 9
F2	1-5/8" stud, 5/8" GWB one side	Furring at storefront (A302 E2)	
E1A	3-5/8" stud furring w/ 5/8" GWB on 8" CMU	South wall (gridline A), BOH rooms 103–116 (A101, A400)	Interior furring only
E3	Z-furring w/ 3" rigid insulation, 3/4" plywood to 4'-0", 5/8" GWB above, on 8" groundface CMU	East wall at Cooler/Staging and loading dock 117.1 (A101; A601 E5; A602 E5)	
E5A / E5B	8" groundface CMU, 2" rigid, 3-5/8" stud w/ 5/8" GWB	North sales wall (gridline E), NW corner (A101)	
E6	2-1/2" stud w/ 5/8" GWB one side on 12" CMU	West wall north of storefront (A101)	
E2 / E7 / E7A	Exterior-side framing – see Section 1A	Front facade, entry, above canopy & storefront	In scope
Soffits	Bakery soffit: cold-formed 8" soffit studs, boxed studs at millwork support points (coordinate w/ structural). Freezer/cooler top closure: 4" stud + 4" runners, 5/8" GWB, 1'-6" high, ties to ACT	A502 D5/D7; A102 E6; A501 E7	
Backing	Concealed blocking for pre-finished cabinetry (KN 44); 3/4" plywood behind restroom equipment to 5'-0" (KN 158); 3/4" fire-retardant plywood (KN 134); TV bracket blocking at columns; wood/plate backing per G106	A400/A402 (breakroom); A401 (restrooms); A400 C5 (tech area); A501 D7	

1A. Exterior Wall Framing & Sheathing (Exterior Side / Cavity) – IN SCOPE

All metal framing and sheathing on the exterior (weather) side of the building envelope is included in this package, as well as the interior furring in Section 1. Studs at exterior walls are designed "per structural" – the delegated-design PE shop drawings (Flag 12) must cover the exterior studs, clips and bridging too.

Condition	Framing / Sheathing Required	Where / Source
E2 – phenolic panel over CMU (front facade)	6" metal studs @ 16" o.c. with bridging @ 5'-0" o.c. (per structural), outboard of 8" CMU + 3" rigid; clip angle at each stud anchored to CMU w/ Hilti HAS-E rod ; 3" 16 ga Z-furring vertical @ 16" o.c. where shown; 5/8" DensGlass sheathing; metal straps for phenolic panel connection (see structural)	Front elevation, 50'-0" phenolic panel run between gridlines 4–5 (A200 B2); A305 E5; A604 B2, E2
E7 – above canopy, thin brick	8" cold-formed metal studs (per structural), 5/8" GWB interior face, plates @ 24" o.c. vertical spacing for stud connection (see structural), blocking between studs as required	Above storefront / canopy, west and north entry (A302 E7/E4; A303 E7; A608 C4, C2)
E7A – above canopy, phenolic panel	8" cold-formed stud + 6" metal stud @ 16" o.c. outboard (3" air space between), 5/8" DensGlass over studs, plates @ 24" o.c. vertical, clip angles, metal straps for panel connection	Entry fascia 32'-0" (gridlines 2–2.6, front) and 32'-0" (gridlines B–A.1, right elevation) (A200 B2, E2; A302 E2/E7; A305 E2; A607 E7; A608 E6/E4)

Parapets / fascia returns	6" and 8" metal studs, blocking between studs as required, 5/8" DensGlass both faces where shown, 3" metal furring above roof, phenolic panel return at parapet framing	A607 B7, E7; A604 E6; A305 E2; A608 C6 (6" stud, 3-5/8" stud at canopy outside edge)
Canopy fascia / soffit framing	3-5/8" metal studs, 6" metal stud, horizontal metal runners at canopy fascia and soffit; 7/8" hat channel for metal panel ceiling (typical)	A608 C6, E6, E4, E2. Hat channel for metal soffit panels may belong to the canopy/metal panel sub - confirm (Flag 9)
Z-furring on CMU (thin brick walls)	3" metal furring / 16 ga Z-furring vertical @ 16" o.c. receiving 3" XPS on exterior face of CMU	A303 E5; A305 E7/E5/E4; A604 B4, E2
Brick wall above storefront	8" metal stud per structural w/ HSS beam; fluid-applied AWB over 5/8" DensGlass	A608 C4, C2

1B. Faux Wood (Wood-Look Phenolic) Panels – INSTALL

Product	Wood-looking phenolic panels, Stonewood , custom finish, color " Lidl Oak " (A200 Exterior Finish Schedule; Key Note 22)
Supply / Install	G109 Div 06: "Siding panels and fastening system – Stonewood – NA supply." GC installs. Panels and fastening system are furnished by the national account; this package includes receiving, handling, layout and installation.
Locations (labeled on drawings)	(1) Front elevation, gridlines 4–5: 50'-0" phenolic panel , full height to top of fascia 27'-0", panel modules 7'-6" / 7'-0" (A200 B2). (2) Entry fascia above canopy, gridlines 2–2.6: 32'-0", 8'-0" modules (A200 B2). (3) Right elevation, gridlines B–A.1: 32'-0" phenolic panel , 8'-0" modules above canopy (A200 E2). (4) Returns at parapet (A604 E6).
Installation Components	Exposed stainless steel fasteners w/ grommet washers; vertical aluminum Z/hat channel; high-performance prefinished extruded aluminum vertical furring; perforated closure flashing (top/bottom); metal straps for phenolic panel connection (see structural); 1" air space behind panel; 3/8" joints; panel returns at parapet; transition/trim at siding-to-brick (movement joint, scribe to brick) (A604 B2, E2, E6; A608 E6, E4; A305 E5)
Base condition	Stone veneer base below panels (A200; A605 E6 "Foundation at Wood Veneer")
Quantity	Run lengths are labeled (50'-0" + 32'-0" + 32'-0"), heights are from datums (top of fascia 27'-0", T.O. storefront 12'-0"). Panel SF isn't stated – verify by takeoff and the Stonewood panel layout.

2. Gypsum Board

- 5/8" GWB per partition types above; P2 uses 2 layers 1/2" Type C each side (G106).
- **Control joints:** "GWB EJ" is tagged throughout A105/A101 at about 28'-0" spacing along long walls. Include them.
- **Corners:** metal corner bead at all exposed corners and edges (A105 GN 5); Fry Reglet DMCT-375 corner trim where shown (G106 typ. GWB corner).
- Stagger horizontal joints; no vertical joints directly above/below openings (A403 / G106 Gypsum Board General Notes). Level of finish isn't stated on the drawings – see Spec 092900.
- Cement board substrate, min 8" above slab, behind FRP and Silikal cove (A501 B2).
- **FRP-1** (Marlite Symmetrix, C100-G63 White) is the wall finish in Restrooms 104/105 and a secondary finish in Bakery 102 (A105). FRP isn't on your scope list, so decide who carries it (Flag 10).

3. Insulation

Type	Location	Source / Size
Batt in stud cavity	P1C walls (restrooms, produce backstock); F1 vestibule furring; 8" stud cavities above storefront / parapet	G106; A302; A607 E7; A608 C2/C4. Thickness/R-value not stated
3" XPS rigid w/ Z-furring (interior side of CMU)	E3 walls: east wall at Cooler/Staging/loading dock	G106 E3; A601 E5; A602 E5
2" rigid (between CMU and stud furring)	E5A/E5B north sales wall	G106
Exterior side / exterior cavity – IN SCOPE		
3" XPS rigid w/ metal furring, exterior face of CMU	All thin-brick walls (E1, E1A, E2A, E5B, E6) and behind phenolic panels (E2) – front, back, left and right elevations; run to top of roof insulation at parapets	G106; A303 E5; A304; A305 E7/E5/E4; A604 B2/B4/E2; A607 B7 "3" rigid insulation with metal furring up to roof insulation"
3" XPS between CMU and E7/E7A studs	Above canopy / storefront walls	G106 E7, E7A; A302
3" XPS continuous between studs/beams to underside of deck at canopy connection	Canopy to CMU/brick connections	A608 E6, E2; A305 E2
2" rigid, exterior cavity	E5A/E5B groundface walls	G106
Batt insulation in 8" stud cavity	Brick wall above storefront, E7 walls, parapet at gridline 2/2.1	A608 C4, C2, E4; A607 B7; A302 E7
Closed-cell spray foam / foam-in-place	Base of brick above storefront over HSS; canopy connections; parapet; roof edge @ CMU (match thickness of wall insulation)	A608 C4, C2, E4; A607 B7, E7; A302 E7 (B2 roof edge @ CMU)
XPS rigid "extend down to top of footing" / 2" perimeter	Below-grade face of foundation walls and 2'-0" slab perimeter	A605 all; A303; A304. Usually carried by concrete - confirm (Flag 9)
Acoustic / smoke sealing	Sealant at bottom runners, penetrations, putty pads at outlets	G101 Acoustical Construction Notes

4. Painting

Key	Product / Color (A105 Materials Sch.)	Where (A105 Room Finish Schedule / notes)
P-0	Unpainted	Technical Area 113
P-1	PPG Eggshell, 1022-2 Intuitive	Vestibule 100, Sales 101 (materials note also lists "amenity hallway" - Flag 5)
P-2	SW Eggshell, SW 7004 Snowbound White	Hallway 106, Office 107, Breakroom Hall 109, Breakroom 110, Changing 111, IT 112; restroom walls above FRP
P-3	SW Semigloss, SW 7075 Web Gray	Doors, frames, structural steel at storefront; HM doors/frames scheduled P3 on A702

P-4	SW Epoxy, SW 7004	Bakery 102, Produce Backstock 103, Sprinkler Riser 114, Staging 117, Backstock 116 (secondary). Note: "paint up to 8'-0" if required by local code" (Flag 6)
P-5	SW Flat, SW 7004	Drywall ceilings (GB/SGB)
P-6	SW Epoxy, SW 7073 Network Gray, w/ block filler/sealer	CMU in Backstock 116 and scrubber station
P-7	SW Semigloss, SW 7004	Sales floor steel columns above stainless steel column protection (KN 179)
ES-1	SW Flat, SW 7004 (exposed structure painted)	Sales 101 and Vestibule 100: all deck, joists, conduit, j-boxes, sprinklers, misc. steel, ductwork and return grilles (A105)
ES-2	Unpainted, shop-primed	Produce Backstock 103, Tech 113, Riser 114, Backstock 116, Staging 117 (no field paint)
Other	Yellow	RAM Type 2 steel tube "paint yellow" (A501 E2). Freezer soffit vent to match SW 7004 (A501 B5). Exposed deck in IT room is galvanized, no paint (A105 Steel Finish Notes).

5. Base – Vinyl, Metal, Roechling Bumper

Item	Spec	Locations
B-1 Vinyl	Tarkett 4" EG cove base, Charcoal. Stop 6" behind refrigerated cases (A105)	Sales 101, Hallway 106, Office 107, Breakroom Hall 109, Breakroom 110, Changing 111, IT 112; casework toe kicks (4" straight base to match, A502)
B-2 Metal	Schluter Dilex-AHKA, satin anodized aluminum	Floor to stainless steel wall panel junction, Bakery 102 (A105 plan tag SS/B-2)
B-3	Not defined in Materials Schedule	Bakery 102, Restrooms 104/105. Appears to be the Silikal integral cove over cement board (A501 B2), which usually belongs to the flooring sub (Flag 4)
Roechling wall bumper	Roechling Polystone G HD, Graphite Gray; 8" high x 78.74" pieces; 1/4" lag/connector bolts at 15.27" o.c.; continuous sealant + backer rod at floor; top at 3'-4" AFF. BOH gets two rows (bottom and 3'-6") ; sales floor gets a floor-level row only where noted (A500 E7)	Key Note 04 on A105/A400: Produce Backstock 103 (west and east walls), Staging 117 (east wall, gridline 6 wall, dock 117.1 jambs), Backstock 116 (south and east walls), cooler vestibule. Base finish "BUMPER" in 116 and 117. G109: "Plastic Bumper Rail - Roechling - NA supply," GC install

6. ACT and Drywall Ceilings

Key	Product	Rooms / Height (A102 RCP)	Details
ACT-1	Armstrong Optima Tegular #3251, 24x24, White; 9/16" Interlude XL grid	Hallway 106, Breakroom Hall 109, Breakroom 110, Changing 111 – 10'-0" AFF	A501 B4, C2
ACT-2	Armstrong Kitchen Zone, 24x24, White; 15/16" Prelude grid	Bakery 102 – 9'-6" AFF; ties to freezer top closure (A501 E7)	A102 E4
SGB	Armstrong suspended drywall grid, GWB, P-5	Restrooms 104/105 – 8'-10"; Office 107 – 10'-0"	
GB	Drywall, 2-HR rated , P-5	IT Room 112 – 10'-0"	G107 rated assembly

Soffit	Drywall bakery soffit (curved)	Bakery 102 / sales edge	A102 E6; A502 D5/D7
--------	--------------------------------	-------------------------	---------------------

RCP notes: fixtures and devices centered in tile; radius GWB per manufacturer (G101 General Ceiling Notes). Hanger wire to steel (A501 B4). Freezer 115 and Cooler 118 ceilings are IMP by the cold-room vendor (not in this scope).

7. RAM Protection, McCue, Stainless – Install Scope

You listed RAM protection as **install only**. G109 matches that for the McCue and Roechling items (NA supply, GC install). For the rows marked "GC supply," it doesn't – see Flag 8.

Item	Detail / Spec	Locations	G109 Supply
RAM Type 1 (KN 01)	Low pipe rail, 2" high at 7" AFF, 2" off wall, 6" radius returns, cored into slab (A501 C4)	Vestibule 100 and sales-floor storefront (A105; A401 C7)	McCue - NA supply
RAM Type 2 (KN 02)	4"x4"x1/4" galv. tube, 1/2" expansion bolts at 4'-0" o.c., clear sealant before freezer cycle, 4" end plugs, welded closure at outside corners, paint yellow (A501 E5/E4/E2)	Cooler 118 and Freezer 115 perimeters (inside and out), Staging 117, Backstock 116 at fence/gate S2 and freezer doors, Produce Backstock 103, Bakery at freezer wall, door 103.1 area (cloud Rev 1)	"Interior bumpers for cold rooms and RAM protection" = GC supply + install
Interior bollard	5.5" dia. FlexPost 55, 1'-2" high, 13 mm holes, 89 mm (3.5") depth; install per McCue guide (A501 D4)	Traffic door 101.1 (A702 C5), dock door 117.1 (A702 D5)	McCue - NA supply
McCue Systems Protector	RAM legend symbol (A105)	No placements found on A105 at bid-set resolution (Flag 11)	McCue - NA supply
SS column protection (KN 179)	22 ga 430 SS, #4 satin, to 40" AFF	All sales floor columns (A105 "TYP.")	SS bumper rail - McCue NA
SS corner guard (KN 181)	Brushed SS, to 4'-1 1/2"	Breakroom Hall / Office / Changing corners (A105, A400)	-
SS bent plate (KN 187)	16-18 ga SS bent plate, recessed flathead screws both sides at jamb	Door 103.1 / Hallway 106 (A105, A401; Rev 1 cloud)	-
Roechling bumper	See Section 5	See Section 5	Roechling - NA supply

8. Flags – Gaps, Conflicts, Scope Splits

#	Issue	Source
1	Partition types exist only on G106. Confirm every bidder had the G-sheets.	A105 GN 1; G106
2	CCD1 reissued A-DWG's after the bid set. Re-verify this baseline against CCD1 before leveling.	documents/drawings/CCD1
3	Meeting Room 108 has no floor/base/wall/ceiling finishes scheduled.	A105 Room Finish Schedule
4	Base B-3 (Bakery, Restrooms) isn't defined. It's likely the Silikal cove (flooring). The Restroom floor is F-3 in the schedule, but the F-4 note says "bakery and restrooms."	A105; A501 B2

5	Hallway 106 wall is P-2 in the schedule, but the P-1 note includes "amenity hallway."	A105
6	GN 10: "BOH painted only when required by health department," yet P-4/P-6 are scheduled in BOH, and the P-4 note says "up to 8'-0" if required by local code." Carry full height or 8'-0"? Clarify.	A105 GN 10; Materials Sch.
7	IT Room P2 (2-HR) is tagged "to 12'-0" AFF," but partitions are to run floor to structure and the ceiling is a 2-HR GB lid. Confirm rated wall/lid continuity.	A400 E7; G101; G107
8	"RAM protection install only" conflicts with G109 for 4x4 tube / cold-room bumpers (GC supply + install). Decide whether the sub or the GC supplies them.	G109 Div 05/06
9	Exterior framing, DensGlass, cavity insulation, spray foam and phenolic panel install are now in this package (Sections 1A, 1B, 3). Items still to assign: (a) fluid-applied air/water barrier over DensGlass/CMU; (b) thin brick support panel system (typically masonry); (c) hat channel for metal soffit panels at canopy; (d) below-grade/perimeter XPS to top of footing (typically concrete). Name each in the bid form as included or excluded so bids level.	A604; A605; A607; A608
15	Phenolic panel attachment "metal straps... see structural" – the S-sheets weren't reviewed. Confirm with Stonewood whether straps/clips are in the NA fastening-system supply or GC-furnished.	A604 B2/E2/E6; A607 E7; G109
10	FRP-1 install and cement board substrate – assign.	A105; A501 B2
11	McCue Protector appears in the legend with no placements found; the NA supply list and quantity are needed from Lidl/McCue.	A105 RAM Legend; G109
12	Framing is delegated design – bids must include PE-sealed shop drawings.	G101
13	The RCP shows drywall hatch at the restroom lobby/sink area (10'-0"), but the Hallway 106 tag says ACT-1. Verify.	A102
14	No LF/SF quantities are stated for any item. Quantity checks need a scaled takeoff. Stated dims: Freezer 54'-0" x 17'-0" (A400); Cooler 32'-11" x 24'-1" (A101); Staging 36'-1" (A400); bumper piece 78.74" (A500).	-

Drafting support for bid leveling. Not a takeoff. Verify all items against the specifications (Project Manual Cycle 1/2) and CCD1 before award.