

SUBMITTAL RECORD

Norcross, GA — Lidl #1517 | Job 15170000GR
4990 Jimmy Carter Blvd, Norcross, GA 30093



Submittal Information

PSI Log #	SUB-005 (Rev 0)	Procore #	33 1000-1.0 — Domestic Water & Irrigation
Fieldwire #	PSI-0001 — Site Utility Submittal Package	Type	Product Data (Cutsheet)
Spec Section	33 10 00 — Exterior Water System	Status	Pending — no response. OVERDUE (Fieldwire response due 09/11/2026)
Subcontractor	Coles Construction (Clay Hotchkiss, Precon Mgr, 470-495-7547); supplier Core & Main (bid 5166172)	Submitted By	Luis Marcelino (Place Services Inc.) — PSI stamp No Exception Taken 08/26/2026
Procore Package	#1: Site Utilities Submittal Package	Ball in Court	Christopher Manes (CHA Consulting, Inc.)
Issue Date	Aug 26, 2026	Final Due Date	None set in Procore
Procore Received	Aug 31, 2026	Note	Same PSI-0001 attachment as SUB-003 (33 4100-1.0). Procore splits Package #1 into one item per spec section; domestic water = pkg Section 3, export pp. 20–53
Distribution	Christopher Manes, JaWanna English-Neal, Jeff Belyea (CHA Consulting); Jens Byer (Lidl US); Bobby McTeague, Tim Mauldin, Tucker Teague (Place Services Inc.)		

Package Contents (per sub's Table of Contents)

1. Storm	HDPE pipe — ADS N-12 ST IB (ASTM F2648) — reviewed under SUB-003
2. Sanitary	Pipe & fittings (Diamond Sani-21 PVC), cleanouts, heavy-duty covers (Star Pipe), marking tape — reviewed under SUB-004
3. Domestic Water & Irrigation (THIS ITEM)	PVC pressure pipe & DI fittings, 2" tap assemblies (Smith-Blair 313 saddle, Ford Meter Box), 2" DCV (Wilkins 950XLT), irrigation, 2" RPZ (Wilkins 975XL2)
4. Fire Main	U.S. Pipe Tyton DI pipe & fittings, tapping sleeve (Smith-Blair 622), M&H 129 hydrant, 8" DCDA BFP vault (Wilkins 350ASTDA), 8" PIV (Lansdale), 8" gate valve assembly

Submittal Workflow / Revision History

Rev	Name	Sent	Due	Returned	Response	Attachment
0	Christopher Manes (CHA Consulting)	Aug 26, 2026	Sep 11, 2026*	—	None — OVERDUE 20 days	Lidl-1517-Norcross-GA-Ground-Up-submittal-PSI-0001-Site-Utility-Submittal-Package-08-26-26.pdf

* No Final Due Date in Procore; due date taken from Fieldwire PSI-0001 "Response due 09/11/2026".

Reviewer Comments

None — no engineer review stamp or markups in the package as of Oct 1, 2026. (Highlights on cut sheets are Core & Main product-selection marks, identical in SUB-003/004; manufacturer "Approval Stamp" boxes are blank vendor forms.)

Enclosed (merged behind this sheet, unaltered)

Full Procore export as received Oct 1, 2026 — 91 pages: p1 Procore cover; p2 Fieldwire PSI-0001 cover; p3 Coles Construction package cover/TOC with PSI review stamp; p4–91 Core & Main product data.

Prepared by Luis Marcelino, Place Services, Inc. — Oct 1, 2026



Lidl US, LLC
3500 S. Clark St.
Arlington , Virginia 22202
P: (571) 398-5435

Project: 1517 Norcross GA - Jimmy Carter Blvd
4990 Jimmy Carter Blvd
Norcross, Georgia 30093

Submittal #33 1000-1.0 - Domestic Water & Irrigation 33 1000 - Exterior Water System

Revision	0	Submittal Manager	Christopher Manes (21327198 CHA Consulting, INC.)
Status	Open	Date Created	Aug 26, 2026
Issue Date	Aug 26, 2026	Spec Section	33 1000 - Exterior Water System
Responsible Contractor	Place Services Inc.	Received From	Luis Marcelino (Place Services Inc.)
Received Date	Aug 31, 2026	Submit By	Aug 26, 2026
Final Due Date		Lead Time	
		Cost Code	
Location		Type	Cutsheet
Submittal Package	#1: Site Utilities Submittal Package		
Approvers			
Ball in Court	Christopher Manes (21327198 CHA Consulting, INC.)		
Distribution	Bobby McTeague (Place Services Inc.), Christopher Manes (21327198 CHA Consulting, INC.), JaWanna English-Neal (21327198 CHA Consulting, INC.), Jeff Belyea (21327198 CHA Consulting, INC.), Jens Byer (28101155 Lidl US, LLC), Tim Mauldin (Place Services Inc.), Tucker Teague (Place Services Inc.)		
Description			

Submittal Workflow

Name	Sent Date	Due Date	Returned Date	Response	Attachments
General Information Attachments					Lidl-1517-Norcross-GA-Ground-Up-submittal-PSI-0001-Site-Utility-Submittal-Package-08-26-26-3-36-PM.pdf

Lidl 1517 Norcross, GA - Ground Up

4990 Jimmy Carter Blvd. Norcorss, GA 30093

Report generated by Luis Marcelino (Place Services, Inc.)



Submittal #PSI-0001 - Site Utility Submittal Package

Creator	Luis Marcelino (Place Services, Inc.)	Submission due	-
Assignee	Tucker Teague (Place Services, Inc.)	Response due	09/11/2026
Reviewers	-	Closed on	-
Status	Pending approval	Reference number	-
Type	Other	Specification	-
Description	-		

Approval (rev. 0)

Responded by	-	Responded on	-
Response	-		
Notes	-		
Attachments	-		

Submission (rev. 0)

Submitted by	Luis Marcelino (Place Services, Inc.)	Submitted on	08/26/2026
Notes	-		
Attachments	PDF attachments are included in this export. Lidl #1517 - Submittals Water, Fire, Sanitary, Storm - Coles Construction.pdf (Page 2)		

SUBMITTAL PACKAGE

Lidl Grocery Store #1517

4990 Jimmy Carter Blvd, Norcross, GA 30093 — Gwinnett County

Prepared By: Coles Construction
Contact: Clay Hotchkiss, Preconstruction Manager | 470-495-7547
Submitted To: GC Grocery Construction (Place Services Inc.)
Attn: Luis Marcelino / Tucker Teague
Scope: Site Utility Submittals – Storm, Sanitary Sewer, Domestic Water & Fire Main (Core & Main)

Table of Contents

Section	Pages
1. Storm – HDPE Pipe	2–5
2. Sanitary Sewer – Pipe & Fittings, Cleanouts, Heavy Duty Covers	6–17
3. Domestic Water & Irrigation – Pipe & Fittings, Tap Assemblies, DCV Assembly, Irrigation, RPZ Assembly	18–51
4. Fire Main – Pipe & Fittings, Tap Assembly, Fire Hydrant, DCDA BFP Vault, Post Indicator Valve, Gate Valve Assembly	52–89

Coles Construction | Civil Site Development & General Contracting

Total Pages in Package: 89

SHOP DRAWING / SUBMITTAL REVIEW

- ☒ NO EXCEPTION TAKEN
☐ REVISE AND RESUBMIT
☐ MAKE CORRECTIONS NOTED
☐ REJECTED

SUBMITTAL WAS REVIEWED FOR DESIGN CONFORMITY AND GENERAL CONFORMANCE TO CONTRACT DOCUMENTS ONLY. THE CONTRACTOR IS RESPONSABLE FOR CONFIRMING AND CORRELATING DIMENSIONS AT JOBSITE FOR TOLERANCE, CLEARANCE, QUANTITIES, FABRICATION PROCESSES AND TECHNIQUES OF CONSTRUCTION, COORDINATION OF HIS WORK WITH OTHER TRADES AND FULL COMPLIANCE WITH CONTRACT DOCUMENTS.

By: Luis Marcelino

Date: 08/26/2026

Place Services, Inc
Canton, GA 30115

Submittal Documents

LIDL 1517



Overview	Bid Date: 08-25-2026 Bid Number: 5166172
Section	STORM

Submittal Documents

LIDL 1517



Overview

Bid Date: 08-25-2026
Bid Number: 5166172

Section

HDPE PIPE

N-12[®] ST IB Pipe

(per ASTM F2648)

N-12 ST IB pipe (per ASTM F2648) has recycled content and provides material properties to meet or exceed the demands of the market.

N-12 ST IB contains a superior built-in bell-and-spigot joint. The joints are sealed by high-quality, factory-installed rubber gaskets that meet all the requirements of ASTM F477. A polyethylene bell minimizes joint distortion. The chipping and cracking that is common to concrete bells is eliminated.

Applications

- Storm drains
- Retention/Detention
- Golf, Turf & Recreation
- Culverts/Cross drains
- Mining/Forestry/Industrial
- Grain aeration
- Waterways
- Ditch enclosures
- Slope/Edge drains
- Downspouts/roof drainage
- Foundation drains
- Land reclamation
- Terracing

Features

- 4"-30" (100-750 mm) diameters available
- Nominal 20' (6 m) and 13' (4 m) lengths available
- In-line bell and spigot joint design
- Exceptional joint strength
- Light weight
- Fast installation times
- Structural strength will support H-25 live loads with 12" (300 mm) minimum cover

Benefits

- Variety of diameters and lengths that will fit any project
- Joint only requires lube for fitting - ends are pushed together for easy field installation
- Pipe requires no additional gasket materials, grout or sealing bands to transport and apply
- Installation cost savings from lower shipping costs, reduced labor and less heavy equipment
- Hydraulic efficiency from smooth interior



N-12 ST IB Pipe (per ASTM F2648) Specification

Scope

This specification describes 4" through 30" (100 to 750 mm) ADS N-12 ST IB pipe (per ASTM F2648) for use in gravity-flow land drainage applications.

Pipe Requirements

ADS N-12 ST IB pipe (per ASTM F2648) shall have a smooth interior and annular exterior corrugations.

- 4" through 30" (100 to 750 mm) shall meet ASTM F2648
- Manning's "n" value for use in design shall be 0.012.

Joint Performance

Pipe shall be joined using a bell & spigot joint meeting ASTM F2648. The joint shall be soil-tight and gaskets, when applicable, shall meet the requirements of ASTM F477. Gaskets shall be installed by the pipe manufacturer and covered with a removable wrap to ensure the gasket is free from debris. A joint lubricant supplied by the manufacturer shall be used on the gasket and bell during assembly.

Fittings

Fittings shall conform to ASTM F2306. Bell and spigot connections shall utilize a spun-on or welded bell and valley or saddle gasket meeting the soil-tight joint performance requirements of ASTM F2306.

Material Properties

Material for pipe production shall be an engineered compound of virgin and recycled high-density polyethylene conforming with the minimum requirements of cell classification 424420C (ESCR Test Condition B) for 4" through 10" (100 to 250 mm) diameters, and 435420C (ESCR Test Condition B) for 12" through 30" (300 to 750 mm) diameters, as defined and described in the latest version of ASTM D3350, except that carbon black content should not exceed 4%. The design engineer shall verify compatibility with overall system including structural, hydraulic, material and installation requirements for a given application.

Installation

Installation shall be in accordance with ASTM D2321 and ADS' published installation guidelines, with the exception that minimum cover in trafficked areas for 4" through 30" (100 to 750 mm) diameters shall be one foot (0.3 m) in single run applications. Backfill for minimum cover situations shall consist of Class 1 (compacted) or Class 2 (minimum 90% SPD) material. Maximum fill heights depend on embedment material and compaction level; please refer to Technical Note 2.02. Contact your local ADS representative or visit our website adspipe.com for a copy of the latest installation guidelines.

Pipe Dimensions*

Pipe I.D. in (mm)	4 (100)	6 (150)	8(200)	10 (250)	12 (300)	15 (375)	18 (450)	24 (600)	30 (750)
Pipe O.D. in (mm)	4.8 (122)	6.9 (175)	9.1 (231)	11.4 (290)	14.5 (368)	18 (457)	22 (559)	28 (711)	36 (914)

*Check with sales representative for availability by region. **Pipe O.D. values are provided for reference purposes only, values stated for 12" through 30" (300-750 mm) are ±1 inch (25 mm).
Contact a sales representative for exact values.



Submittal Documents

LIDL 1517



Overview

Bid Date: 08-25-2026
Bid Number: 5166172

Section

SEWER

Submittal Documents

LIDL 1517



Overview

Bid Date: 08-25-2026
Bid Number: 5166172

Section

PIPE & FITTINGS

D3034 & F679 SEWER SPECIFICATION DATA

Diamond gravity sewer pipe 4 inches through 60 inches shall be made of compounds conforming to material requirements of ASTM D3034 and ASTM F679 in accordance with ASTM D1784. Diamond PVC Sewer Pipe meets all the dimensional, chemical, and physical requirements as outlined in ASTM D3034 and ASTM F679. A listing to CSA B182.2 is available for most of these sizes. A complete listing by manufacturing plant is available upon request.

The pipe sizes 4 inches through 60 inches are made with an integral bell "water-tight" joint that meets the requirements of ASTM D3212 and that utilizes a Rieber gasket system for sealing that meets the requirements of ASTM F477.

Each male end shall be beveled to facilitate joining and referencing marked for proper insertion depth. Diamond furnished lubricant is to be used in the joining process.

SANI-21™



PHYSICAL PROPERTIES OF ASTM D3034 & F679

Property	ASTM TEST	Minimum 12454/12364
PIPE MATERIALS: PIPE SHALL BE MADE OF PVC PLASTIC HAVING A MINIMUM CELL CLASSIFICATION OF 12454 OR 12364 AS DEFINED IN SPECIFICATION D1784.		
Specific Gravity	D792	1.40/1.40
Tensile Strength, psi	D638	7,000/6,000
Tensile Modulus, psi	D638	400,000/500,000
IZOD Impact Strength,	D256	.65ft., lb./in.

SHORT FORM Specification for Diamond PVC Solid-Wall Sewer Pipe SDR 26 or SDR 35 or PS 46 or PS 115

All PVC Solid-Wall Sewer Pipe shall be made of compounds conforming to ASTM D1784 manufactured in accordance with the material requirements of ASTM D3034 or ASTM F679. All PVC Sewer Pipe must meet dimensional, chemical, and physical requirements as outlined in ASTM D3034 or ASTM F679. Joints shall meet the requirements of ASTM D3212 and shall be formed using Rieber Technology. PVC Sewer Pipe shall be installed according to the requirements of ASTM D2321, Uni-Bell's Uni-Pub 6 and the manufacturer's recommendations.

RIEBER JOINT ILLUSTRATION



ASTM D3034 SEWER SPECIFICATION DATA


Diamond gravity sewer pipe 4 inches through 60 inches shall be made of compounds conforming to material requirements of ASTM D3034 in accordance with ASTM D1784. Diamond PVC Sewer Pipe meets all the dimensional, chemical, and physical requirements as outlined in ASTM D3034.

A listing to CSA B182.2 is available for most of these sizes. A complete listing by manufacturing plant is available upon request.

Pipe sizes 4 inches through 60 inches are made with an integral bell "water-tight" joint that meets the requirements of ASTM D3212 and that utilizes a Rieber gasket system for sealing that meets the requirements of ASTM F477.

Each male end shall be beveled to facilitate joining and reference marked for proper insertion depth. Diamond furnished lubricant is to be used in the joining process.

RIEBER JOINT ILLUSTRATION



SANI-21™

D3034 SEWER SPECIFICATION DATA

Nominal Pipe Size in. (mm)	A Outside Diameter Inches	B Bell Socket Diameter Inches	D Insert Mark Inches	t Min. Wall Thickness SDR26/PS115 Inches	t Min. Wall Thickness PS75 Inches	t Min. Wall Thickness SDR35/PS46 Inches	t Min. Wall Thickness PS28 Inches
4" THROUGH 15" DIAMETERS							
4" (100)	4.215	5-1/4	4"	0.162		0.120	
6" (150)	6.275	7-1/2	4-1/8"	0.241		0.180	
8" (200)	8.400	9-7/8	4-7/8"	0.323		0.240	
10" (250)	10.500	12-3/8	5-1/4"	0.404		0.300	
12" (300)	12.500	14-5/8	5-1/2"	0.481		0.360	
15" (375)	15.300	18	6"	0.588		0.437	
18" THROUGH 60" DIAMETERS							
18" (450)	18.701	21-3/4"	7-3/4"	0.671	0.584	0.499	0.456
21" (525)	22.047	25-1/2"	8-1/2"	0.791	0.689	0.588	0.538
24" (600)	24.803	28-3/4"	8 1/2"	0.889	0.775	0.661	0.605
27" (675)	27.953	32-1/2"	11-1/8"	1.002	0.874	0.745	0.682
30" ciod (750)	32.000	37-1/4"	13-5/8"	1.148	1.000	0.853	0.780
36" ciod (900)	38.300	43-1/4"	13-7/8"	1.373	1.197	1.021	0.934
42" ciod (1050)	44.500	53"	16-3/4"	1.596	1.391	1.187	1.085
48" ciod (1200)	50.800	60"	16-7/8"	1.822	1.588	1.355	1.239
54" ciod (1350)	57.560	67"	17"	2.064	1.799	1.535	1.404
60" ciod (1500)	61.610	72"	18-1/2"	2.210	1.926	1.643	1.503

Prices are subject to a firm policy of "Price in effect at time of shipment on regular purchases" "Possession of this page does not constitute an offer of sale" *Tolerance of +/- 1/4" allowed"

SANI-21™

PHYSICAL PROPERTIES OF ASTM D3034

Property	ASTM TEST	Minimum 12454/12364
PIPE MATERIALS: PIPE SHALL BE MADE OF PVC PLASTIC HAVING A MINIMUM CELL CLASSIFICATION OF 12454 OR 12364 AS DEFINED IN SPECIFICATION D1784.		
Specific Gravity	D792	1.40/1.40
Tensile Strength, psi	D638	7,000/6,000
Tensile Modulus, psi	D638	400,000/440,000
IZOD Impact Strength,	D256	.65ft., lb./in.

SHORT FORM Specification for Diamond PVC Solid-Wall Sewer Pipe SDR26 or SDR35 or PS 28, PS 46, PS 75, or PS115. All PVC Solid-Wall Sewer pipe shall be made of compounds conforming to ASTM D1784 manufactured in accordance with the material requirements of ASTM D3034. All PVC Sewer Pipe must meet dimensional, chemical, and physical requirements as outlined in ASTM D3034. Joints shall meet the requirements of ASTM D3212 and shall be formed using Rieber Technology. PVC Sewer Pipe shall be installed according to the requirements of ASTM D2321, Uni-Bell's Uni-Pub 6 and the manufacturer's recommendations.



SANI-21™

ASTM D3034 LOADING CHART

Nominal Pipe Size in. (mm)	Outside Diameter Inches	Bundle Quantity	*Feet Per Truckload	
			14'	20'
4" (100)	4.215	60/69/84	20,160 / 21,168 / 23,184	20,160 / 24,288
6" (150)	6.275	24/32	10,080 / 10,752	10,240 / 11,264
8" (200)	8.400	18/24	5544 / 6048	5280 / 5760
10" (250)	10.500	12/15	3402	3240
12" (300)	12.500	8/16	2688	2560
15" (375)	15.300	6	1512	1440
18" (450)	18.701	2/3/4/6	1050	1000
21" (525)	22.047	4	672	640
24" (600)	24.803	4	504E / 672W	480E / 640W
27" (675)	27.953	3	378	360
30" (750)	32.000	3	252E / 378W	240E / 360W
36" (900)	38.300	2	168	160
42" (1050)	44.500	2	168	
48" (1200)	50.800	1	84	
54" (1350)	57.560	1	42E / 84W	
60" (1500)	61.610	1	42	

Prices are subject to a firm policy of "Price in effect at time of shipment on regular purchases" *Current loading chart from the plant closest to your location can be found by visiting our website, dpcpipe.com * Possession of this page does not constitute an offer of sale"

PIPE MARKING TAPE

MODELS LVPMTD - LVPMTND

(DETECTABLE) (NON-DETECTABLE)

UNIFORM COLOR CODE

	WHITE - Proposed excavation
	PINK - Temporary survey markings
	RED - Electric power lines, cables, conduit and lighting cables
	YELLOW - Gas, oil, steam, petroleum or gaseous materials
	ORANGE - Communication, alarm or signal lines, cables or conduit
	BLUE - Potable water
	PURPLE - Reclaimed water, irrigation and slurry lines
	GREEN - Sewers and drain lines

DESCRIPTION:

Lansdale's Pipe Tape provides easy detection and identification of buried pipe and our LVPMTND tape provides identification of non buried pipe. Custom tapes are available if needed and include custom colors, logos, wording, symbols, phone numbers etc.

Biaxially Oriented Polypropylene (BOPP) Resistance to Acids and Alkalis

Biaxially oriented polypropylene (BOPP) films are generally chemically inert and exhibit good resistance to most acids and alkalis, especially at room temperature and moderate concentrations. This is due to the non-polar, hydrophobic nature of polypropylene and its high chemical stability.

DATA SHEET

	DETECTABLE TAPE		NON- DETECTABLE TAPE
COLOR & LEGEND	APWA		APWA
Length (Ft)	1000 FT		1000 FT
Tolerance	± 5%		± 5%
Width (In)	2", 3", 4", 6", 12"		2", 3", 4", 6", 12"
Width Tolerance	± 2%		± 2%
Thickness (Mil)	5 mil - D2103		4 mil - D2103
Thickness Tolerance	± 5%		± 5%
Core Inside Diameter (mm)	76 mm		76 mm
Material	.35 Mil Aluminum Foil + 8 Mil Clear Bopp Film + 3.75 Mil Clear PE* Film		PE*
Yield Strength	MD	52lbf -D882	N/A
	TD	49lbf-D882	N/A
Break Strength	MD	66lbf-D882	N/A
	PSI	7800 PSI-D882	N/A
	TD	50lbf-D882	N/A
	PSI	7800 PSI-D882	N/A
Elongation	MD	80%-D882	803% - D882**
	TD	140%-D882	>1080% - D882**
Tongue Tear	MD	2lb-D1938	ISO 6383-1:2015 196 N/mm
	TD	6lb-D1938	ISO 6383-1:2015 196 N/mm
Tensile Strength	MD	50.8 lbs/in-D882	ASTM D882 52.3
	TD	50.0 lbs/10-D882	ASTM D882 52.3

NON-DETECTABLE

DETECTABLE



PROJECT	APPROVAL STAMP
PROJECT:	☐ APPROVED
ADDRESS:	☐ APPROVED AS NOTED
ENGINEER:	☐ NOT APPROVED
SUBMITTAL DATA:	REMARKS:
NOTES 1:	
NOTES 2:	

TABLE 1: CONDUCTOR (Physical, Mechanical and Electrical Properties)

PROPERTY	14 AWG	12 AWG	10 AWG	8 AWG
Conductor Type	HF-CCS	HF-CCS	HF-CCS	HF-CCS
Conductor Temper	Annealed	Annealed	Annealed	Annealed
Steel Grade	AISI 1006	AISI 1006	AISI 1006	AISI 1006
Copper Grade	UNS C10200	UNS C10200	UNS C10200	UNS C10200
Rated Break Load	177 lbs	282 lbs	448 lbs	713 lbs
Rated Tensile Strength	55,000 psi	55,000 psi	55,000 psi	55,000 psi
Elongation	20.0%	21.0%	21.0%	22.0%
Nominal Copper Thickness (% of Diameter)	3.0%	3.0%	3.0%	3.0%
Nominal Copper Weight (Per 1,000')	13.0%	13.0%	13.0%	13.0%
Nominal DC Resistance	12.024 ohms	7.562 ohms	4.756 ohms	2.991 ohms

TABLE 2: INSULATION (Physical, Mechanical and Electrical Properties)

TEST DESCRIPTION	ASTM STANDARD	TYPICAL VALUES
Density @ 23°C	ASTM D1505	0.945 g/cm ³
Melt Flow Rate	ASTM D1238	0.70 g/10 min
Tensile Strength	ASTM D638	3,400 psi
Tensile Strength Retention	ASTM D638	90% after 48 hours @ 100°C
Tensile Elongation	ASTM D638	500%
Tensile Elongation Retention	ASTM D638	90% after 48 hours @ 100°C
Environmental Stress Cracking	ASTM D1693	0 failures @ 48 hours
Thermal Stress Cracking	ASTM D2951	0 failures @ 96 hours
Brittleness Temperature	ASTM D746	-76°C
Melting Temperature	ASTM D3418	260°C
Oxidative Induction Time	ASTM D3895	170 min @ 200°C
Dielectric Constant	ASTM D1531	2.32 @ 1 MHz
Dissipation Factor	ASTM D1531	0.00006 @ 1 MHz
DC Volume Resistivity @ 23°C	ASTM D257	> 1 x 10 ¹⁵ ohm-cm

PRODUCT PART NO.	PRODUCT DESCRIPTION	RATED BREAK LOAD	RATED TENSILE STRENGTH	HDPE INSULATION THICKNESS	NOMINAL O.D.	APPROX. WEIGHT PER 1,000 FT		STANDARD PACKAGES
						COPPER WEIGHT	FINISHED WEIGHT	
WEIGHTS, MEASUREMENTS AND PACKAGING								
74411XXXX	14 SOL HF-CCS PE30	177 lbs	55,000 psi	0.030"	0.124"	1.4479	16.00	500' / 2500'
74412XXXX	12 SOL HF-CCS PE30	282 lbs	55,000 psi	0.030"	0.141"	2.3007	24.00	500' / 1000' / 2500'
74413XXXX	10 SOL HF-CCS PE30	448 lbs	55,000 psi	0.030"	0.162"	3.6592	36.00	500' / 1000' / 2500'
74414XXXX	8 SOL HF-CCS PE30	713 lbs	55,000 psi	0.030"	0.189"	5.8189	54.00	CUSTOM ORDER

INSULATION COLOR & REEL LENGTH			
COLOR	500' REEL	1000' REEL	2500' REEL
BLACK	0132	0141	0147
BLUE	0232	0241	0247
GREEN	0532	0541	0547
ORANGE	0632	0641	0647
PURPLE	0832	0841	0847
RED	0932	0941	0947
WHITE	1132	1141	1147
YELLOW	1232	1241	1247
SOME PART NUMBERS MAY BE SUBJECT TO MINS			

REEL & PACKAGING INFORMATION					
SIZE	LENGTH	MATERIAL	REEL DIMENSION	ARBOR HOLE	PALLET QUANTITY
14 AWG	500	PLYWOOD (TREATED)	8" x 4"	1.625"	162,000 FT
	1000	PLYWOOD (TREATED)	8" x 9"	1.625"	144,000 FT
	2500	PLYWOOD (TREATED)	12" x 9"	1.625"	160,000 FT
12 AWG	500	PLYWOOD (TREATED)	8" x 6"	1.625"	108,000 FT
	1000	PLYWOOD (TREATED)	8" x 9"	1.625"	108,000 FT
	2500	PLYWOOD (TREATED)	12" x 12"	1.625"	120,000 FT
10 AWG	500	PLYWOOD (TREATED)	8" x 9"	1.625"	72,000 FT
	1000	PLYWOOD (TREATED)	12" x 6"	1.625"	80,000 FT
	2500	PLYWOOD (TREATED)	14" x 10"	2.5"	67,500 FT
8 AWG	500	PLYWOOD (TREATED)	8" x 9"	1.625"	54,000 FT
	1000	PLYWOOD (TREATED)	12" x 6"	1.625"	48,000 FT
	2500	PLYWOOD (TREATED)	16" x 10"	2.5"	45,000 FT



Specification Updated: 4.15.2011 08:32:00 CST

PRO-LINE
SAFETY PRODUCTS
A DIVISION OF PRO-PAK IND. INC.

PRO-LINE SAFETY PRODUCTS COMPANY
1099 ATLANTIC DRIVE, UNIT 1 • WEST CHICAGO, IL 60185
TOLL FREE: 800.554.3424



Submittal Documents

LIDL 1517



Overview

Bid Date: 08-25-2026
Bid Number: 5166172

Section

CLEANOUTS



TRENCH TOUGH PLUS™

SDR35 Gasketed Sewer Fittings

APPLICATIONS:

- Gravity Sewer Systems
- Stormwater and Drainage

SIZE RANGE:

Molded: 4" – 18" Fabricated: 18" – 60"

FEATURES:

- The widest size range of molded fittings (up to 18" diameter) available in the industry.
- Locked in gaskets on molded fittings.
- Third party certified joints to withstand a minimum of 15 psi hydrostatic pressure and a -10.8 psi vacuum.
- Molded fittings are structurally reinforced to a heavier wall thickness at key areas to ensure maximum durability during installation and for the long term.
- Unsurpassed strength while maintaining flexibility and toughness.
- Proven track record of performance for over 60 years.

STANDARDS:



CSA B182.2: PSM type Polyvinyl Chloride (PVC) sewer pipe and fittings



ASTM F1336: Standard Specification for Polyvinyl Chloride (PVC) Gasketed Sewer Fittings
ASTM D3034: Type PSM Polyvinyl Chloride (PVC) Sewer Pipe and Fittings



NQ 3624-135: Unplasticized Polyvinyl Chloride (PVC-U) Pipe and Fittings
— Pipes of 200mm to 600mm in Diameter for Underground Sewage and Soil Drainage



SOLVENT WELD **SDR35 Sewer Fittings**

APPLICATIONS:

- Gravity Sewer Systems
- Stormwater and Drainage

SIZE RANGE:

Molded: 3" – 8" Fabricated: 8" – 15"

FEATURES:

- Compatibility with SDR35 and SDR26 sewer pipe.
- Solvent welded joints that have the ability to resist large tensile loads without pulling apart.
- The same high quality design as our gasketed sewer fittings.
- Advanced material compounds formulated and blended in our manufacturing facility.

STANDARDS:



D3034



B182.1
B182.2



NSF-14
(6" & 8")

Submittal Documents

LIDL 1517



Overview


Bid Date: 08-25-2026
Bid Number: 5166172

Section

HEAVY DUTY COVERS


7621 HANDHOLE RING & COVER "S"

MB-0040



Notes:


- Material - Cast Iron
Per ASTM A48 Class 30B
- Dimensions in Inches



ITEM CODE	DETAILS
CO7621S	COMPLETE


8"x4" NON-LOCKING CLEANOUT RING "CO" COVER

MB-0041



Notes:


- Material - Cast Iron
Per ASTM A48 Class 30B
- Dimensions in Inches



ITEM CODE	DETAILS
COSP45	COMPLETE


8"x4" LOCKING CLEANOUT RING "CO" COVER

MB-0042



Notes:

- Material - Cast Iron
Per ASTM A48 Class 30B
- Dimensions in Inches
- (2) 3/8" x 1" SS Socket Head Cap Screw



ITEM CODE	DETAILS
COSP45L	COMPLETE

Submittal Documents

LIDL 1517



Overview

Bid Date: 08-25-2026
Bid Number: 5166172

Section

DOMESTIC WATER

Submittal Documents

LIDL 1517



Overview

Bid Date: 08-25-2026
Bid Number: 5166172

Section

PIPE & FITTINGS

D2241

IPS PVC PRESSURE PIPE SPECIFICATION DATA

ASTM D2241 IPS SPECIFICATION DATA

Diamond IPS pressure-rated PVC pipe is made of compounds conforming to material requirements of ASTM D2241 in accordance with ASTM D1784. Pipe sizes (1 ½" through 12") are made with an integral bell to utilize the Rieber gasket system for sealing, and meeting specifications defined in ASTM F477 which conforms to the requirements of ASTM D3139.

Diamond IPS pressure-rated PVC pipe meets all the dimensional, chemical, and physical requirements as outlined in ASTM D2241. Potable water pipe carries the mark of NSF, International in accordance with Standard 61. Some factory locations produce IPS pressure pipe bearing the mark of NSF-14.

Each male end shall be beveled to facilitate joining and reference marked to insure proper insertion depth. Diamond furnished lubricant is to be used in the joining process.

D2241


PHYSICAL PROPERTIES OF PVC 12454:

Property	ASTM Test	Minimum
Specific Gravity	D792	1.40
Tensile Strength, psi	D638	7,000
Tensile Modulus, psi	D638	400,000
IZOD Impact Strength	D256	.65ft., lb./in.

SHORT FORM Specification for Diamond PVC Water Pipe

Diamond PVC Water Pipe shall be made of compounds conforming to ASTM D1784 with a cell classification of 12454. Diamond PVC Water Pipe must meet all the dimensional, chemical, and physical requirements as outlined in ASTM D2241 and will be supplied in 20 and 22 foot laying lengths. Joints shall be formed using Rieber Technology. Potable water pipe shall be manufactured from NSF listed ingredients.

RIEBER JOINT ILLUSTRATION



ASTM D2241

SPECIFICATION DATA. DIAMOND IPS PRESSURE-RATED PIPE IS SUPPLIED IN 20 AND 22 FOOT LAYING LENGTHS.

Nominal Pipe Size in. (mm)	B Bell Socket Diameter Inches	D Insert Mark 1 Inches *	E Insert Mark 2 Inches *
2" (50)	3-1/8"	2-3/4"	3-3/4"
2.5" (62.5)	4-3/8"	2"	3"
3" (75)	4-7/16"	3-5/8"	4-5/8"
4" (100)	5-1/2"	4-1/4"	5-1/4"
6" (150)	8-1/4"	4-3/4"	5-3/4"
8" (200)	10-1/4"	4-7/8"	5-7/8"
10" (250)	12-7/8"	5-1/2"	6-1/2"
12" (300)	15-1/8"	5-7/8"	6-7/8"

Prices are subject to a firm policy of "Price in effect at time of shipment on regular purchases"

*Possession of this page does not constitute an offer of sale

*Tolerance of +/- 1/4" allowed



ASTM D2241 SPECIFICATION DATA

Nominal Pipe Size in. (mm)	A Outside Diameter Inches	t SDR 13.5 315 psi Inches	t SDR 17 250 psi Inches	t SDR 21 200 psi Inches	t SDR 26 160 psi Inches	t SDR 32.5 125 psi Inches	t SDR 41 100 psi Inches
MINIMUM WALL THICKNESS = (t)							
1.5" (37.5)	1.900	0.141	0.112	0.090			
2" (50)	2.375	0.176	0.140	0.113	0.091		
2.5" (62.5)	2.875	0.213	0.169	0.137	0.110		
3" (75)	3.500	0.259	0.206	0.167	0.135		
4" (100)	4.500	0.333	0.265	0.214	0.173	0.138	0.110
6" (150)	6.625	0.491	0.390	0.316	0.255	0.204	0.162
8" (200)	8.625		0.508	0.410	0.332	0.265	0.210
10" (250)	10.750		0.632	0.511	0.413	0.331	0.262
12" (300)	12.750		0.750	0.606	0.490	0.392	0.311

ASTM D2241 ASTM D2241 LOADING CHART

Nominal Pipe Size in. (mm)	Outside Diameter	Joints Per Bundle	Feet Per Bundle 20' laying lengths	*Feet Per Truckload 20' laying lengths	Feet Per Bundle 22' laying lengths	*Feet Per Truckload 22' laying lengths
SDR-41 PRESSURE RATING 100 PSI						
4" (100)	4.500	63	1,260	20,160	1,386	22,176
6" (150)	6.625	35\40	560/640/700/800	8,400	770\880	9,240
8" (200)	8.625	20\24	300/360/400/480	4,840	440\528	5,324
10" (250)	10.750	12\15	240/300	3,240	264\330	3,564
12" (300)	12.750	9\12	120/160/180/240	1,960	198\264	2,156
SDR-32.5 PRESSURE RATING 125 PSI						
4" (100)	4.500	63	1,260	20,160	1,386	22,176
6" (150)	6.625	35\40	560/640/700/800	8,400	770\880	9,240
8" (200)	8.625	20\24	300/360/400/480	4,840	440\528	5,324
10" (250)	10.750	12\15	240/300	3,240	264\330	3,564
12" (300)	12.750	9\12	120/160/180/240	1,960	198\264	2,156
SDR-26 PRESSURE RATING 160 PSI						
2" (50)	2.375	215			4,730	75,680
2.5" (62.5)	2.875	131			2,882	46,112
3" (75)	3.500	88\95			1,936\2,090	32,208
4" (100)	4.500	63	1,260	20,160	1,386	22,176
6" (150)	6.625	35\40	560/640/700/800	8,400	770\880	9,240
8" (200)	8.625	20\24	300/360/400/480	4,840	440\528	5,324
10" (250)	10.750	12\15	240/300	3,240	264\330	3,564
12" (300)	12.750	9\12	120/160/180/240	1,960	198\264	2,156

Prices are subject to a firm policy of "Price in effect at time of shipment on regular purchases"

"Possession of this page does not constitute an offer of sale"

CONTINUED NEXT PAGE

PIPE MARKING TAPE

MODELS LVPMTD - LVPMTND

(DETECTABLE) (NON-DETECTABLE)

UNIFORM COLOR CODE

	WHITE - Proposed excavation
	PINK - Temporary survey markings
	RED - Electric power lines, cables, conduit and lighting cables
	YELLOW - Gas, oil, steam, petroleum or gaseous materials
	ORANGE - Communication, alarm or signal lines, cables or conduit
	BLUE - Potable water
	PURPLE - Reclaimed water, irrigation and slurry lines
	GREEN - Sewers and drain lines

DESCRIPTION:

Lansdale's Pipe Tape provides easy detection and identification of buried pipe and our LVPMTND tape provides identification of non buried pipe. Custom tapes are available if needed and include custom colors, logos, wording, symbols, phone numbers etc.

Biaxially Oriented Polypropylene (BOPP) Resistance to Acids and Alkalis

Biaxially oriented polypropylene (BOPP) films are generally chemically inert and exhibit good resistance to most acids and alkalis, especially at room temperature and moderate concentrations. This is due to the non-polar, hydrophobic nature of polypropylene and its high chemical stability.

DATA SHEET

	DETECTABLE TAPE		NON- DETECTABLE TAPE
COLOR & LEGEND	APWA		APWA
Length (Ft)	1000 FT		1000 FT
Tolerance	± 5%		± 5%
Width (In)	2", 3", 4", 6", 12"		2", 3", 4", 6", 12"
Width Tolerance	± 2%		± 2%
Thickness (Mil)	5 mil - D2103		4 mil - D2103
Thickness Tolerance	± 5%		± 5%
Core Inside Diameter (mm)	76 mm		76 mm
Material	.35 Mil Aluminum Foil + 8 Mil Clear Bopp Film + 3.75 Mil Clear PE* Film		PE*
Yield Strength	MD	52lbf -D882	N/A
	TD	49lbf-D882	N/A
Break Strength	MD	66lbf-D882	N/A
	PSI	7800 PSI-D882	N/A
	TD	50lbf-D882	N/A
	PSI	7800 PSI-D882	N/A
Elongation	MD	80%-D882	803% - D882**
	TD	140%-D882	>1080% - D882**
Tongue Tear	MD	2lb-D1938	ISO 6383-1:2015 196 N/mm
	TD	6lb-D1938	ISO 6383-1:2015 196 N/mm
Tensile Strength	MD	50.8 lbs/in-D882	ASTM D882 52.3
	TD	50.0 lbs/10-D882	ASTM D882 52.3

NON-DETECTABLE

DETECTABLE



PROJECT	APPROVAL STAMP
PROJECT:	☐ APPROVED
ADDRESS:	☐ APPROVED AS NOTED
ENGINEER:	☐ NOT APPROVED
SUBMITTAL DATA:	REMARKS:
NOTES 1:	
NOTES 2:	



C153 DUCTILE IRON MECHANICAL JOINT FITTINGS

C153 DUCTILE IRON MECHANICAL JOINT FITTINGS

BASIC SPECIFICATIONS

- SIZES:**
- 2" - 64"
- MATERIAL:**
- Ductile Iron ASTM A536, Grade 65-45-12, 60-42-10 or 70-50-05.
- PRESSURE:**
- 350 PSI Water Working Pressure 2" - 24".
 - 250 PSI Water Working Pressure 30" - 48".
 - 150 PSI Water Working Pressure 54" - 64".
- TESTING:**
- In accordance with ANSI/AWWA C153/A21.53.
 - In accordance with UL - FM requirements.
 - All fittings are hydrostatically tested in accordance with SIGMA Quality Management Standard.
 - All fittings are heat coded to ensure traceability and verification of metallurgical properties in accordance with the prevailing standards and SIGMA Quality Management Standards.
- LAYING LENGTH:**
- Short body design - straight section of body deleted to provide a compact and lighter fitting without reducing strength or flow characteristics.
 - In accordance with ANSI/AWWA C153/A21.53.
- DEFLECTION:**
- Maximum allowable deflection for MJ Joint on a full length pipe is as mentioned below:
 1. 3" - 4" = 8 Degrees
 2. 6" = 7 Degrees
 3. 8" - 12" = 5 Degrees
 4. 14" - 48" = 3 Degrees
- CEMENT LINING:**
- Maximum Double cement lined in accordance with ANSI/AWWA C104/A21.4.
- COATING:**
- Interior of fitting is seal coated (asphaltic material) in accordance with ANSI/AWWA C104/A21.4 and NSF61 approved.
 - Exterior of fitting is seal coated (asphaltic material) in accordance with ANSI/AWWA C153/A21.53 and NSF61 approved.
- GASKETS:**
- SBR in accordance with ANSI/AWWA C111/A21.11.
 - Also available in EPDM, NBR and CR.
- T-BOLTS:**
- Low Alloy corrosion resistant high strength steel in accordance with ANSI/AWWA C111/A21.11.
- APPROVALS:**
- 3"-16" Underwriters Laboratories listed and Factory Mutual Approved.
- STANDARDS:**
- Certified to NSF61 Standard including Annex G & 372.
 - ANSI/AWWA C153/A21.53 for Compact Ductile Iron Fittings 2"-64" for water and other liquids.
- INSTALLATION:**
- Per ANSI/AWWA C600 and C111 using DIP conforming to C150/C151 and PVC pipe conforming to C900/C905.

For sewer applications that require mandrel passage after installation, SIGMA recommends the end user check the fitting with the respective size mandrel BEFORE installing the fitting. SIGMA Corporation will NOT take responsibility for any back charges incurred due to the fitting not being checked with a mandrel prior to installation.





Mechanical Joint Details

Plain End Details

Size	A	B	C	D	F	J	K1	K2	L	M	P	S	X	Bolts			PE Ls
														No.	Size	Len	
3	3.96	2.50	4.84	4.94	4.06	6.19	7.62	7.69	0.58	0.62	0.63	0.39	3/4	4	5/8	3.0	5.5
4	4.80	2.50	5.92	6.02	4.90	7.50	9.06	9.12	0.60	0.75	0.75	0.39	7/8	4	3/4	3.5	5.5
6	6.90	2.50	8.02	8.12	7.00	9.50	11.06	11.12	0.63	0.88	0.75	0.43	7/8	6	3/4	3.5	5.5
8	9.05	2.50	10.17	10.27	9.15	11.75	13.31	13.37	0.66	1.00	0.75	0.45	7/8	6	3/4	3.5	5.5
10	11.10	2.50	12.22	12.34	11.20	14.00	15.62	15.62	0.70	1.00	0.75	0.47	7/8	8	3/4	3.5	5.5
12	13.20	2.50	14.32	14.44	13.30	16.25	17.88	17.88	0.73	1.00	0.75	0.49	7/8	8	3/4	3.5	5.5
14	15.30	3.50	16.40	16.54	15.44	18.75	20.25	20.25	0.79	1.25	0.75	0.55	7/8	10	3/4	4.0	8.0
16	17.40	3.50	18.50	18.64	17.54	21.00	22.50	22.50	0.85	1.31	0.75	0.58	7/8	12	3/4	4.0	8.0
18	19.50	3.50	20.60	20.74	19.64	23.25	24.83	24.75	1.00	1.38	0.75	0.68	7/8	12	3/4	4.0	8.0
20	21.60	3.50	22.70	22.84	21.74	25.50	27.08	27.00	1.02	1.44	0.75	0.69	7/8	14	3/4	4.0	8.0
24	25.80	3.50	26.90	27.04	25.94	30.00	31.58	31.50	1.02	1.56	0.75	0.75	7/8	16	3/4	4.5	8.0
30	32.00	4.00	33.29	33.46	32.17	36.88	39.12	39.12	1.31	2.00	1.00	0.82	1 1/8	20	1	5.5	8.0
36	38.30	4.00	39.59	39.76	38.47	43.75	46.00	46.00	1.45	2.00	1.00	1.00	1 1/8	24	1	5.5	8.0
42	44.50	4.00	45.79	45.96	44.67	50.62	53.12	53.12	1.45	2.00	1.00	1.25	1 3/8	28	1 1/4	6.0	8.0
48	50.80	4.00	52.09	52.26	50.97	57.50	60.00	60.00	1.45	2.00	1.00	1.35	1 3/8	32	1 1/4	6.0	8.0
54	57.56	4.00	58.85	59.02	57.73	63.20	65.70	65.70	1.55	2.50	1.00	1.45	1 3/8	36	1 1/4		
60	61.61	4.00	62.90	63.07	61.78	67.72	70.22	70.22	1.75	2.50	1.00	1.50	1 3/8	36	1 1/4		
64	65.67	4.00	66.96	67.13	65.84	71.86	74.36	74.36	1.75	2.50	1.00	1.57	1 3/8	38	1 1/4		



ONE-LOK™ MODEL SLCE WEDGE RESTRAINT FOR PVC PIPE



PRODUCT SPECIFICATIONS

- MATERIAL:**
- Gland body, wedge inserts and break-off top actuating bolts are manufactured of high strength ductile iron in accordance with ASTM A536, Grade 65-45-12.
- SIZE RANGE:**
- 3" - 60"
- DIMENSION:**
- Conform to ANSI/AWWA C111/A21.11 & ANSI/AWWA C153/A21.53 standards
- PRESSURE RATING:**
- Equal to the water working pressure rating of the pipe upon which it is installed with a minimum 2:1 factor of safety.
- COATING:**
- Red Alkyd paint
 - Electro-deposition "CORRSafe™" available upon request. For further information, please refer to our CORRSafe Product Information sheet at <http://www.sigmaco.com/pipe-restraint-product-coatings-linings/>
- APPROVALS:**
- Underwriters Laboratories' listed in sizes 4"-12" to ASTM F1674 (latest revision) and Factory Mutual approved in sizes 4"-12".
- DEFLECTION:**
- 5° on 3"-12", 2° on 14"-16", 1.5° on 18"-30" and 1° on 36", 42", 48", 54" and 60"
- TRACEABILITY:**
- Gland body, wedge inserts and break-off top actuating bolts are individually cast with exact heat code information.
- INSTALLATION:**
- In accordance with manufacturer's recommendation and applicable AWWA standards.

ONE-LOK™ Series SLCE for PVC Pipe



Features & Advantages:

1) The SIGMA ONE-LOK Series SLCE is a mechanical joint restraining gland that implements a series of individually activated wedges into the mechanical joint follower gland. When the wedge segment is engaged by the actuating bolt, the primary contact edges of each wedge segment lock onto the pipe wall. This action causes the primary contact edges to grip the pipe and effectively restrain all classifications of both AWWA C900 and ASTM D2241 IPS size PVC pipe.


2) ONE-LOK SLCE's precision contoured wedges provide proper contact and support of the PVC pipe wall. Each wedge is manufactured with an elongated contour that evenly matches the outside circumference of each nominal diameter of PVC pipe.

3) ONE-LOK SLCE's wedge actuating bolt provides the installer with two visual torque indicators. The breakaway top and secondary shoulder stop ensure proper engagement of the wedge segment at the time of installation. Unlike other actuating bolts, the ONE-LOK SLCE is manufactured with a proprietary quality control system that ensures the breakaway tops will activate at the correct torque. The breakaway top is sized to match the same dimensions of the bolts and nuts used to assemble the mechanical joint fitting and follower gland, eliminating the need for special installation tools. Once engaged, the actuating bolt leaves a residual hex-head shank, allowing post-installation disassembly of the restrained joint, if necessary.

4) ONE-LOK SLCE also features a non-corrosive, two-piece ABS plastic spacer that is removed when using the product to restrain IPS sized pipes meeting ASTM D2241. The two-piece design of this spacer allows it to be removed without requiring disassembly of the product. When the ONE-LOK SLCE is used to restrain pipes meeting AWWA C900, the spacer is left intact on the actuating bolt.

5) ONE-LOK SLCE's unique wedge segment and actuating bolt design allows the two components to interface using a cam action principle, allowing the wedge segments to rock and increase their grip on the pipe wall as thrust on the assembled joint increases. This also allows improved resistance to subsidence, seismic forces, and other movement within the maximum deflection limitations of the mechanical joint under applicable AWWA standards.


SIGMA ONE-LOK SLCE's can be used on all pressure classes and thicknesses of PVC pipe.



ONE-LOK's unique **CAM ACTION** allows the restraining lugs to "rock" and grip the PVC pipe wall more securely as thrust force increases, and allows for subsidence, seismic or other forces after installation, up to the maximum allowed deflection.



ONE-LOK™ Series SLCE for PVC Pipe




Sample Specification:

Restraint for standard mechanical joint fittings shall be incorporated in the design of the follower gland and shall utilize multiple wedge segments that act against the pipe, increasing their resistance as the line pressure increases. The assembled joint shall maintain the maximum flexibility and deflection of all nominal pipe sizes after burial. Restraining gland, wedge segments, and actuating bolts shall be manufactured of high strength ductile iron conforming to the requirements of ASTM A536, Grade 65-45-12. Dimensions shall be compatible with standardized mechanical joints conforming to the requirements AWWA C111/ANSI A21.11 and AWWA C153/ANSI 21.53 through 24" (latest revision). Breakaway tops shall be incorporated in the design of the actuating bolts to visually ensure proper torque. The manufacturing of the actuating bolt must incorporate a quality control procedure that is deemed acceptable by the specifier and positively assures precise and consistent operating torque of the breakaway top. The mechanical joint restraining devices shall have a working pressure rating of 235 psi and provide no less than a safety factor of 2:1. Restraint shall be FM approved in applicable sizes. Restraining device shall be SIGMA ONE-LOK™ or approved equal.

Material:

- Gland body, brackets, wedge segments & actuating bolts ASTM A536 65-45-12 ductile iron.
- Restraining Rods & Nuts: High strength, low alloy steel meeting AWWA/ANSI C111/A21.11 with minimum 65,000 psi tensile strength and 45,000 psi yield strength.



Dimensions in Inches, Weights in Pounds

Size	Item #	Wgt	PVC Pipe DI OD	IPS Pipe OD	Dimensions										Bolts and Inserts			Pressure Rating (PSI)	T-bolts			Gasket	
					C	F	K2	T	P	P*	X	J	Bell Joint BCD	Bell Joint Hole Size	No	Size	Torque		No	Size	Torque	No	Item #
3	SLCE3	6.21	---	3.50	4.76	3.60	7.18	0.60	9.42	8.50	0.750	6.14	---	---	2	7/8	45-55	235	4	5/8 x 3.0	45-60	1	TG3
4	SLCE4	6.78	4.80	4.50	5.92	4.90	7.92	0.60	10.22	9.30	0.875	7.50	---	---	2	7/8	50-60	235	4	3/4 x 3.5	75 - 90	1	MG4
6	SLCE6	10.28	6.90	6.63	8.01	7.00	10.00	0.60	12.87	11.95	0.875	9.50	---	---	3	7/8	50-60	235	6	3/4 x 3.5	75 - 90	1	MG6
8	SLCE8	14.48	9.05	8.63	10.17	9.15	12.18	0.75	14.37	13.45	0.875	11.75	---	---	4	7/8	50-60	235	6	3/4 x 4.0	75 - 90	1	MG8
10	SLCE10	21.40	11.10	10.75	12.22	11.20	14.60	0.85	16.68	15.76	0.875	14.00	---	---	6	7/8	50-60	235	8	3/4 x 4.0	75 - 90	1	MG10
12	SLCE12	26.96	13.20	12.75	14.32	13.30	16.64	0.85	18.58	17.66	0.875	16.25	---	---	8	7/8	50-60	235	8	3/4 x 4.0	75 - 90	1	MG12
14	SLCE14	33.67	15.30	---	16.40	15.44	20.25	1.20	21.68	19.98	0.875	18.75	---	---	10	7/8	55-65	235	10	3/4 x 4.5	75 - 90	1	MG14
16	SLCE16	41.67	17.40	---	18.50	17.54	22.45	1.21	23.65	21.95	0.875	21.00	---	---	12	7/8	55-65	235	12	3/4 x 4.5	75 - 90	1	MG16
18	SLCE18	49.50	19.50	---	20.60	19.64	24.75	1.25	25.79	24.09	0.875	23.25	---	---	12	7/8	55-65	235	12	3/4 x 4.5	75 - 90	1	MG18
20	SLCE20	61.17	21.60	---	22.70	21.74	27.00	1.34	28.16	26.46	0.875	25.50	---	---	14	7/8	55-65	235	14	3/4 x 5.0	75 - 90	1	MG20
24	SLCE24	79.33	25.80	---	26.90	25.94	31.50	1.46	32.70	31.00	0.875	30.00	---	---	16	7/8	55-65	235	16	3/4 x 5.0	75 - 90	1	MG24
30	SLCE30	198.00	32.00	---	33.29	32.17	38.42	2.00	41.92	39.92	1.125	36.88	---	---	20	1.00	65-75	165	20	1 x 6.5	100-120	1	MGS30
36	SLCE36	248.00	38.30	---	39.59	38.47	46.00	2.00	48.78	46.78	1.125	43.75	---	---	24	1.00	65-75	165	24	1 x 6.5	100-120	1	MGS36
42	SLCE42	660.00	44.50	---	45.76	44.80	58.80	3.15	59.59	57.93	1.375	50.62	54.50	1.375	14	1.00	65 - 75	235	28	1 1/4 x 8.0	120 - 150	1	MGS42
48	SLCE48	751.00	50.80	---	52.09	50.97	65.74	3.15	66.63	63.5	1.375	57.50	61.44	1.375	16	1.00	65 - 75	200	32	1 1/4 x 8.0	120 - 150	1	MGS48
54	SLCE54	1022.00	57.56	---	58.85	57.73	67.50	4.50	72.1	70.5	1.375	63.2	---	---	18	1 1/4	105 - 115	250	36	1 1/4 x 11	120 - 150	1	MGS54
60	SLCE60	1115.00	61.61	---	62.90	61.78	72.00	4.50	77.4	75.75	1.375	67.72	---	---	18	1 1/4	105 - 115	250	36	1 1/4 x 11	120 - 150	1	MGS60

Note: P* With break off bolts broken head

Weight does not include any accessories like T-bolt + Gasket. There could be +/- 5% variation in the weight.



Sizes 4" - 12" are UL listed and have been tested in accordance with ASTM F1674.

Sizes 4" - 12" are FM approved on AWWA C900 pipe.

Pressure Rating Chart


Nominal Pipe Size	Item #	Pressure Rating													
		C900									ASTM D2241				
		DR14	DR17	DR18	DR21	DR25	DR27.5	DR32.5	DR41	DR51	SDR17	SDR21	SDR26	SDR32.5	SDR41
3	SLCE3	-	-	-	-	-	-	-	-	-	250	200	160	125	100
4	SLCE4	305	250	235	200	165	150	-	-	-	250	200	160	125	100
6	SLCE6	305	250	235	200	165	150	-	-	-	250	200	160	125	100
8	SLCE8	305	250	235	200	165	150	-	-	-	250	200	160	125	100
10	SLCE10	305	250	235	200	165	150	-	-	-	250	200	160	125	100
12	SLCE12	305	250	235	200	165	150	-	-	-	250	200	160	125	100
14	SLCE14	305	250	235	200	165	150	125	100	-	-	-	-	-	-
16	SLCE16	305	250	235	200	165	150	125	100	-	-	-	-	-	-
18	SLCE18	305	250	235	200	165	150	125	100	80	-	-	-	-	-
20	SLCE20	305	250	235	200	165	150	125	100	80	-	-	-	-	-
24	SLCE24	305	250	235	200	165	150	125	100	80	-	-	-	-	-
30	SLCE30	-	250	235	200	165	150	125	100	80	-	-	-	-	-
36	SLCE36	-	-	235	200	165	150	125	100	80	-	-	-	-	-
42	SLCE42	-	-	-	200	165	150	125	100	80	-	-	-	-	-
48	SLCE48	-	-	-	-	165	150	125	100	80	-	-	-	-	-
54	SLCE54	-	-	-	-	165	150	125	100	80	-	-	-	-	-
60	SLCE60	-	-	-	-	165	150	125	100	80	-	-	-	-	-



NOTE: All packs come with ONE-LOK SLCE Gland, MJ or SIGMA Seal Gaskets & required # of T-Bolts

SIGMA Corporation One-Lok Models SLCE and SLCEH, sizes 42", 48", 54" & 60" have been successfully tested on a variety of dimension ratio (DR) pipes as manufactured by Diamond Plastics and Ipex Canada. For any questions or additional information, please contact Satheesh Chandrasekaran (Pipe Restraint Engineer) at mcs@sigmaco.com or Stephen McDonald (Pipe Restraint manager) at smd@sigmaco.com.

Installation Instructions for Wedge Action Restraint with PVC Pipe & Mechanical Joint Fitting

One Lok SLCE Wedge Action Restraint



1. Clean the fitting socket & pipe end. Lubricate mechanical joint gasket & pipe end with soapy water or approved lubricant meeting AWWA C111/A21.11. (A transition gasket is required if using on "IPS" PVC pipe)	
2. Install the One Lok SLCE Wedge Restraint on the pipe with the lip extension facing the pipe end followed by the gasket, tapered side toward end of the pipe.	

Submittal Documents

LIDL 1517



Overview


Bid Date: 08-25-2026
Bid Number: 5166172

Section

2" TAP ASSEMBLY

SPECIFICATION


SERVICE SADDLE DOUBLE BALE MODEL 313



APPLICATIONS

- **Typical Uses**
 - Tapping branch connections on new or existing pipe
 - Installing air/vacuum valves, pitot tubes, drain valves, or other miscellaneous service equipment
 - Installing pipe supports, hangers, or sign mounting brackets
- **Standard Pipe Sizes**
 - 1.25" to 24" nominal
- **Standard Taps**
 - NPT: 1/2", 3/4", 1", 1-1/4", 1-1/2", 2", 3" and 4"
 - CC/AWWA: 1/2", 5/8", 3/4", 1", 1-1/4", 1-1/2" and 2"
 - BSP: 1/2", 3/4", 1", 1-1/4", 1-1/2", 2", and 3"

See Smith-Blair catalog for available pipe diameter and tap size combinations as some combinations are not available
- **Type of Pipe**
 - Carbon Steel, Stainless Steel, Ductile Iron, Asbestos Cement, Aluminum
- **Working Pressure**
 - Up to 300 psi depending on type of pipe, type of repair, pipe diameter, service conditions, and installation workmanship





SPECIFICATION

SERVICE SADDLE DOUBLE BALE


MODEL 313

MATERIALS

- **Body** (*Small (ST) and Large (LT) Tap sizes 1/2" – 2-1/2"*)
 - Cast using Ductile Iron 65-45-12 per ASTM A536
 - Flexi-Coat® fusion bonded epoxy finish which meets application methods AWWA C213
 - Closed ears holds nut and bale in place allowing the assembly to hinge for ease of installation around pipe
 - Open ears provide easy slip on installation and removal of nuts are not required preventing lost hardware
 - Canted ears for maximum tangential tightening of bale or strap
 - Wraparound design provides maximum pipe support, reinforcement, and sealing pressure
 - Wide skirt and heavy tapping boss provides excellent stability on the pipe
- **Body** (*Extra-Large (XLT) Tap sizes 3" and 4"*)
 - Cast using Ductile Iron 65-45-12 per ASTM A536
 - Flexi-Coat® fusion bonded epoxy finish which meets application methods AWWA C213
 - Open ears provide easy slip on installation and removal of nuts are not required preventing lost hardware
 - Canted ears for maximum tangential tightening of bale or strap
 - Wraparound design provides maximum pipe support, reinforcement, and sealing pressure
 - Wide skirt and heavy tapping boss provides excellent stability on the pipe
- **Gasket**
 - Nitrile (Buna-N) per ASTM D2000
 - Certified to NSF/ANSI 61-G& 372
 - Compounded to resist water, oil, natural gas, acids, alkalies, most (aliphatic) hydrocarbon fluids, and many other chemicals
 - Temperature range: -20°F to +180°F
 - TaperSeal™ hydro-mechanical lip enables the saddle to hold higher pressures with minimal nut torque
 - Gasket is fully cemented in a cavity to hold it in place
- **Bale Assembly** (*used only on 1.25" - ~14" nominal pipe size saddles with 1/2" thru 4" tap sizes*)
 - **Bale**
 - HSLA Carbon Steel per AWWA C111/A21.11
 - Fe/Zn Coated per ASTM F1941-10
 - Size:
 - 1.25" – 3" nominal pipe size = 1/2"-13UNC
 - 4" – 14" nominal pipe size = 5/8"-11UNC
 - Extra-Large (XLT) Taps < 14.73" O.D. = 5/8"-11UNC
 - Pipe contact surface flattened to provide a wider bearing surface against pipe
 - Rolled threads for improved physical characteristics, greater thread accuracy, and smooth surface finish
 - **Nut**
 - Carbon Steel per ASTM A307
 - Fe/Zn Coated per ASTM F1941-10
 - Size:
 - 1.25" – 3" nominal pipe size = 1/2"-13UNC Heavy Hex Semi-Finished
 - 4" – 14" nominal pipe size = 5/8"-11UNC Heavy Hex Semi-Finished
 - Extra-Large (XLT) Taps < 14.73" O.D. = 5/8"-11UNC Heavy Hex Semi-Finished
 - **Flat Washer**
 - Carbon Steel per ASTM F844
 - Fe/Zn Coated per ASTM F1941-10
 - Size:
 - 1.25" – 3" nominal pipe size = 1/2" Type A Plain
 - 4" – 14" nominal pipe size = 5/8" Type A Plain
 - Extra-Large (XLT) Taps < 14.73" O.D. = 5/8" Type A Plain
 - Fe/Zn Coated per ASTM F1941-10

SUBMITTAL INFORMATION

Ballcorp Corporation Stops - (FB1000-xx-G-NL style)



AWWA/CC TAPER THREAD INLET BY GRIP JOINT COMPRESSION FOR COPPER OR PLASTIC TUBING (CTS) OUTLET




Image shown above is an FB1000-4-G-NL.

VALVE SIZE	INLET SIZE	OUTLET SIZE	VALVE LENGTH	BODY OUTLET THREADS	APPROX. WT. LBS	PART NUMBER	✓ SUBMITTED ITEM(S)
3/4"	3/4"	3/4"	4-19/64"	3/4" Flare Copper	1.5	FB1000-3-G-NL	
3/4"	3/4"	1"	4-7/16"	1" Flare Copper	2.1	FB1000-34-G-NL	
1"	1"	1"	4-1/2"	1" Flare Copper	2.6	FB1000-4-G-NL	
1"	1"	1-1/4"	4-5/16"	1-1/4" Flare Copper	3.0	FB1000-45-G-NL	
1-1/4"	1-1/4"	1-1/4"	5-25/32"	1-1/4" Flare Copper	4.8	FB1000-5-G-NL	
1-1/2"	1-1/2"	1-1/2"	6-13/32"	1-1/2" Flare Copper	5.7	FB1000-6-G-NL	
1-1/2"	1-1/2"	2"	6-29/64"	2" Flare Copper	7.4	FB1000-67-G-NL	
2"	2"	2"	7-1/2"	2" Flare Copper	9.8	FB1000-7-G-NL	

Note: Ford recommends using insert stiffeners with plastic pipe or tubing.

FEATURES

- All brass that comes in contact with potable water conforms to AWWA Standard C800 (ASTM B584, UNS C89833)
- The product has the letters "NL" cast into the main body for lead-free identification
- Certified to NSF/ANSI Standard 61 and NSF/ANSI Standard 372 where applicable
- Brass components that do not come in contact with potable water conform to AWWA Standard C800 (ASTM B62 and ASTM B584, UNS C83600, 85-5-5-5)
- Ends are integral or secured with adhesive to prevent unintentional disassembly
- 300 PSI working pressure

The Ford Meter Box Company considers the information in this submittal form to be correct at the time of publication. Item and option availability, including specifications, are subject to change without notice. Please verify that your product information is current.




The Ford Meter Box Company, Inc.
P.O. Box 443, Wabash, Indiana U.S.A. 46992-0443
Phone: 260-563-3171 / Fax: 800-826-3487
Overseas Fax: 260-563-0167
www.fordmeterbox.com

03/24/17

Submitted By:

SUBMITTAL INFORMATION

Ball Valve Curb Stop - (B41-xxxW-G-NL style)



GRIP JOINT FOR COPPER OR PLASTIC TUBING (CTS) INLET BY FEMALE IRON PIPE THREAD OUTLET




Image shown above is a B41-444W-G-NL

VALVE SIZE	INLET SIZE	OUTLET SIZE	LENGTH	APPROX. WT. LBS	PART NUMBER	✓ SUBMITTED ITEM(S)
5/8"	3/4"	3/4"	2-15/16"	1.2	B41-233W-G-NL	
3/4"	3/4"	3/4"	3-37/64"	1.7	B41-333W-G-NL	
3/4"	1"	3/4"	3-5/32"	2.0	B41-343W-G-NL	
3/4"	1"	1"	3-7/8"	2.2	B41-344W-G-NL	
1"	1"	1"	3-19/32"	2.4	B41-444W-G-NL	
1-1/4"	1-1/4"	1-1/4"	5-3/16"	5.0	B41-555W-G-NL	
1-1/2"	1-1/2"	1-1/2"	5-1/16"	5.9	B41-666W-G-NL	
2"	2"	2"	6-1/64"	8.7	B41-777W-G-NL	

Note: Ford recommends using insert stiffeners with plastic pipe or tubing.

Note: 5/8" ball valves do not have a reinforced seat.

FEATURES

- All brass that comes in contact with potable water conforms to AWWA Standard C800 (ASTM B584, UNS C89833)
- The product has the letters "NL" cast into the main body for lead-free identification
- Certified to NSF/ANSI Standard 61 and NSF/ANSI Standard 372 where applicable
- Brass components that do not come in contact with potable water conform to AWWA Standard C800 (ASTM B62 and ASTM B584, UNS C83600, 85-5-5-5)
- Valve is non-directional and is watertight with flow in either direction
- Ends are integral or secured with adhesive to prevent unintentional disassembly
- Hole for attaching curb box rod or handle is provided in tee-head
- 300 PSI working pressure

Optional full 360° tee-head rotation. Add "R" into the part number (Example: B41-333WR-G-NL)

The Ford Meter Box Company considers the information in this submittal form to be correct at the time of publication. Item and option availability, including specifications, are subject to change without notice. Please verify that your product information is current.



The Ford Meter Box Company, Inc.
P.O. Box 443, Wabash, Indiana U.S.A. 46992-0443
Phone: 260-563-3171 / Fax: 800-826-3487
Overseas Fax: 260-563-0167
www.fordmeterbox.com

05/17/18

Submitted By:



Your Single Source Solution

U.S. OPERATING
COMPANY OF **HAILIANG**

Copper Tube for Plumbing and Mechanical Applications

Job Name

Job Location

Engineer

PRODUCT DESCRIPTION & MATERIAL

JMF Copper Tube for use in plumbing and mechanical applications & is manufactured from UNS C12200 grade of copper.

SPECIFICATIONS

JMF Company Copper Tube (Type K, L, M) conforms to the NSF/ANSI 61 Annex G requirements and meets ASTM B88. Copper drainage tube (DWV) meets ASTM B306. Copper refrigeration coils ACR straight lengths and line sets meet the chemical, mechanical, cleanliness and eddy current testing requirements of the applicable specifications of ASTM B280.

Type K Rated Working Pressure (PSIG)

Nominal Diameter	Weight /ft. (lbs)	Feet/ Bundle	150°F	200°F	300°F	400°F
1/4	0.145	500	913	860	842	537
3/8	0.269	500	960	904	885	565
1/2	0.344	500	758	713	698	446
5/8	0.418	200	626	589	577	368
3/4	0.641	200	724	682	668	426
1	0.839	100	557	524	513	327
1 1/4	1.04	100	452	425	416	266
1 1/2	1.36	100	420	396	387	247
2	2.06	-	370	348	341	217
2 1/2	2.93	-	338	319	312	199
3	4.00	-	328	308	302	193
3 1/2	5.12	-	311	293	286	183
4	6.51	-	306	288	282	180
5	9.67	-	293	276	270	172
6	13.90	-	295	277	271	173
8	25.90	-	314	295	289	184

Type L Rated Working Pressure (PSIG)

Nominal Diameter	Weight /ft. (lbs)	Feet/ Bundle	150°F	200°F	300°F	400°F
1/4	0.126	500	775	729	714	456
3/8	0.198	500	662	623	610	389
1/2	0.285	500	613	577	565	361
5/8	0.362	200	537	505	495	316
3/4	0.455	200	495	466	456	291
1	0.655	100	420	395	387	247
1 1/4	0.884	100	373	351	344	219
1 1/2	1.14	100	347	327	320	204
2	1.75	-	309	291	285	182
2 1/2	2.48	-	285	269	263	168
3	3.33	-	270	254	248	159
3 1/2	4.29	-	258	243	238	152
4	5.38	-	249	235	230	147
5	7.61	-	229	215	211	135
6	10.2	-	213	201	196	125
8	19.3	-	230	216	212	135

Contractor

Wholesaler

JMF Rep

INSTALLATION

Installations must comply with the latest applicable building codes for the local jurisdiction. For detailed installation instructions, consult the Copper Development Association at copper.org.

REFERENCE

C12200 99.9% Pure Copper (can be used for potable water)
NSF/ANSI 61 Annex G Safe Drinking Water Act (third party certification)
ASTM B88 Seamless Copper Water and Gas Tube (Type K, L, M)
ASTM B280 Seamless Copper Tube for Air Conditioning

Type M Rated Working Pressure (PSIG)

Nominal Diameter	Weight /ft. (lbs)	Feet/ Bundle	150°F	200°F	300°F	400°F
3/8	0.145	500	485	456	447	285
1/2	0.204	500	420	395	387	247
3/4	0.328	200	346	326	319	204
1	0.465	100	286	270	264	169
1 1/4	0.682	100	287	271	265	169
1 1/2	0.94	100	282	265	259	166
2	1.46	-	254	239	234	149
2 1/2	2.03	-	233	219	215	137
3	2.68	-	215	203	199	127
3 1/2	3.58	-	214	202	197	126
4	4.66	-	213	201	197	126
5	6.66	-	198	186	182	116
6	8.92	-	186	175	171	109
8	16.5	-	195	183	180	115

Type DWV Rated Working Pressure (PSIG)

Nominal Diameter	Weight /ft. (lbs)	Feet/ Bundle	150°F	200°F	300°F	400°F
1 1/4	0.65	100	280	269	258	165
1 1/2	0.809	100	249	240	230	147
2	1.07	-	185	178	170	109
3	1.69	-	135	130	125	80
4	2.87	-	127	122	117	75
5	4.43	-	129	124	119	76
6	6.1	-	126	121	116	74
8	10.6	-	124	119	114	73

Tables give computed allowable stress for annealed copper tube at indicated temperature.

TECHNICAL DATA

All ratings listed for types K, L, M, DWV and refrigeration service tube in the preceding charts are calculated for tube in the annealed condition. These values should be used when soldering, brazing or welding is used for joining components in a system. While the ratings for hard drawn tube are higher, they should only be used for systems using properly designed flare or compression mechanical joints, since joining by any heating process might anneal (soften) the tube. In designing a system, careful consideration should also be given to joint ratings as well as those of the components.

JMF COMPANY IS YOUR CONSOLIDATING SOURCE FOR copper tubing, line sets, copper fittings, push to fit, pex, ball valves, gas valves, plumbing valves, malleable fittings, steel nipples, plastic fittings, brass threaded, brass nipples, flare & compression, gas connectors, water connectors, appliance kits, cord sets and MORE.



Submittal Documents

LIDL 1517



Overview


Bid Date: 08-25-2026
Bid Number: 5166172

Section

2" DCV ASSEMBLY

LEAD FREE BRASS NIPPLES

MODEL LVLFBN




FEATURES:

- Schedule 40
- Lead Free Brass Conforms to ASTM B43
- Dimensions and Ends Conform to ASTM B687
- Threads Conform to ASME B1.20.1
- Meets NSF/ANSI61, NSF/ANSI372 & CRN

AVAILABILITY:

- Stocked from 1/8" x Close through 4" x 12"
- Redi Cut Nipples are available from 1/2" through 3" diameter up to 60" in length



PROJECT		APPROVAL STAMP
PROJECT:		☐ APPROVED
ADDRESS:		☐ APPROVED AS NOTED
ENGINEER:		☐ NOT APPROVED
SUBMITTAL DATA:		REMARKS:
NOTES 1:		
NOTES 2:		



Model 950XLT

Top Access Double Check Valve Assembly

Application

Designed for installation on water lines to protect against both backsiphonage and backpressure of polluted water into the potable water supply. A test cock plug is provided to protect against fouling caused by insects, dirt and debris. Assembly shall provide protection where a potential non-health hazard exists. For non-potable applications only.

Standards Compliance

(Unless otherwise noted, applies to 3/4" thru 2" Horizontal)

- ASSE® Listed 1015 (Vertical flow-up: 1 1/4" thru 2")
- IAPMO® Listed
- AWWA Compliant C510
- CSA® Certified (Vertical flow-up: 1 1/2" & 2")
- NYC MEA 426-89-M VOL 3
- Approved by the Foundation for Cross Connection Control and Hydraulic Research at the University of Southern California (950XLTU: 3/4" & 1" Horizontal)

Materials

Main valve body	Cast Bronze ASTM B 584
Access covers	Cast Bronze ASTM B 584
Fasteners	Stainless Steel, 300 Series
Elastomers	Silicone
	Buna Nitrile
Polymers	Noryl™
Springs	Stainless steel, 300 series
Test cock cover	Plastic
Ball valve handles	Stainless steel

Features

Sizes:	2"
Maximum working water pressure	175 PSI
Maximum working water temperature	180°F
Hydrostatic test pressure	350 PSI
End connections Threaded	ANSI B1.20.1




Options

(Suffixes can be combined)

- ☐ L - less ball valves
- ☐ FT - with "Fast Test" test cocks
- ☒ U - with union ball valves
- ☐ S - with bronze "Y" type strainer

Accessories

- ☐ Repair kit (rubber only)
- ☐ Thermal expansion tank (Model XT)
- ☐ QT-SET Quick Test Fitting Set




Dimensions & Weights (do not include pkg.)

MODEL SIZE		DIMENSIONS (approximate)																WEIGHT			
		A		A UNION BALL VALVES		B LESS BALL VALVES		C		D		E		F		G		LESS BALL VALVES		WITH BALL VALVES	
in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	lbs.	kg	lbs.	kg
3/4	20	13	330	14 5/16	364	8 3/4	222	2 3/8	60	2 5/16	59	3 5/16	84	3/4	19	17 5/8	448	4	1.8	6	2.7
1	25	14	356	15 3/4	400	8 3/4	222	2 1/2	64	2 5/16	59	3 5/16	84	3/4	19	19 3/4	502	8	3.6	12	5.4
1 1/4	32	19 5/8	499	21 5/8	549	13 3/4	349	4	102	3 5/8	92	4 3/8	111	1 5/16	33	24 3/4	629	16	7.3	22	10
1 1/2	40	20 5/16	516	22 5/16	567	13 3/4	349	5 3/8	137	3 5/8	92	4 3/8	111	1 5/16	33	25 15/16	659	16	7.3	22	10
2	50	21 3/8	543	23 1/4	591	13 3/4	349	5 13/16	148	3 5/8	92	4 3/8	111	1 5/16	33	28 5/16	719	17	7.7	29	13.2

NDS Pro-Spec® 17 in. x 30 in. Rectangular Valve Boxes

Specifications: The NDS Pro-Spec® 17 in. x 30 in. body is tapered and has a minimum wall thickness of 0.320 in. The body has a double wall at the top cover seat area with a minimum thickness of 0.320 in. The cover seat area has 20 structural support ribs on the underside of the seat, each with a minimum thickness of 0.250 in. The bottom of the body has a 1.000 in. flange. The 17 in. x 30 in. cover has an average thickness of 0.350 in. The valve box has a 3/8 in. brass nut for the bolt-down as a standard feature.



Part No.	Description	Color (Box/Cover)	Pallet Qty.	Weight Ea. (lbs.)	Product Class
Box & Cover					
324BCB	17" x 30" x 15" Box, Overlapping Bolt-Down Cover - ICV	Green/Green	6	28	20PR
324BCB-BG	17" x 30" x 15" Box, Overlapping Bolt-Down Cover - ICV	Black/Green	6	28	20PR
324BCBS	17" x 30" x 15" Box, Overlapping Bolt-Down Cover - Sewer	Green/Green	6	28	20PR
324BCDB	17" x 30" x 15" Box, Drop-in Bolt-Down Cover - ICV	Green/Green	6	28	20PR
326BCB	17" x 30" x 18" Box, Overlapping Bolt-Down Cover - ICV	Green/Green	6	39	20PR
326BCB-BG	17" x 30" x 18" Box, Overlapping Bolt-Down Cover - ICV	Black/Green	6	41	20PR
326BCDB	17" x 30" x 18" Box, Drop-in Bolt-Down Cover - ICV	Green/Green	6	37	20PR
326BCDB ELEC	17" x 30" x 18" Box, Drop-in Cover - Electric	Gray/Gray	6	37	20PR
326BCDB-BG	17" x 30" x 18" Box, Drop-in Bolt-Down Cover - ICV	Black/Green	6	37	20ND
326BCDBW	17" x 30" x 18" Box, Drop-in Bolt-Down Cover - Water	Black/Black	6	37	20ND
326PBCBR	17" x 30" x 18" Box, Overlapping Cover - Reclaimed Water	Purple/Purple	6	38	20PR
Cover Only					
323C	17" x 30" Overlapping Cover - ICV	Green	75	11	20PR
323CD	17" x 30" Drop-in Cover - ICV	Green	75	11	20PR
323CD ELEC	17" x 30" Drop-in Cover - Electric	Gray	75	11	20PR
323CDW	17" x 30" Drop-in Cover - Water	Black	75	11	20PR
323CR	17" x 30" Overlapping Cover - Reclaimed Water	Purple	75	11	20PR
323CS	17" x 30" Overlapping Cover - Sewer	Green	75	11	20PR
Box Only					
324B	17" x 30" x 15" Box	Green	6	20	20PR
324B BLK	17" x 30" x 15" Box	Black	6	20	20PR
326B	17" x 30" x 18" Box	Green	10	23	20PR
326B BLK	17" x 30" x 18" Box	Black	10	23	20PR

Submittal Documents

LIDL 1517



Overview

Bid Date: 08-25-2026
Bid Number: 5166172

Section

IRRIGATION

Submittal Documents

LIDL 1517



Overview


Bid Date: 08-25-2026
Bid Number: 5166172

Section

2" TAP ASSEMBLY

SPECIFICATION


SERVICE SADDLE DOUBLE BALE MODEL 313



APPLICATIONS

- **Typical Uses**
 - Tapping branch connections on new or existing pipe
 - Installing air/vacuum valves, pitot tubes, drain valves, or other miscellaneous service equipment
 - Installing pipe supports, hangers, or sign mounting brackets
- **Standard Pipe Sizes**
 - 1.25" to 24" nominal
- **Standard Taps**
 - NPT: 1/2", 3/4", 1", 1-1/4", 1-1/2", 2", 3" and 4"
 - CC/AWWA: 1/2", 5/8", 3/4", 1", 1-1/4", 1-1/2" and 2"
 - BSP: 1/2", 3/4", 1", 1-1/4", 1-1/2", 2", and 3"

See Smith-Blair catalog for available pipe diameter and tap size combinations as some combinations are not available
- **Type of Pipe**
 - Carbon Steel, Stainless Steel, Ductile Iron, Asbestos Cement, Aluminum
- **Working Pressure**
 - Up to 300 psi depending on type of pipe, type of repair, pipe diameter, service conditions, and installation workmanship





SPECIFICATION

SERVICE SADDLE DOUBLE BALE


MODEL 313

MATERIALS

- **Body** (*Small (ST) and Large (LT) Tap sizes 1/2" – 2-1/2"*)
 - Cast using Ductile Iron 65-45-12 per ASTM A536
 - Flexi-Coat® fusion bonded epoxy finish which meets application methods AWWA C213
 - Closed ears holds nut and bale in place allowing the assembly to hinge for ease of installation around pipe
 - Open ears provide easy slip on installation and removal of nuts are not required preventing lost hardware
 - Canted ears for maximum tangential tightening of bale or strap
 - Wraparound design provides maximum pipe support, reinforcement, and sealing pressure
 - Wide skirt and heavy tapping boss provides excellent stability on the pipe
- **Body** (*Extra-Large (XLT) Tap sizes 3" and 4"*)
 - Cast using Ductile Iron 65-45-12 per ASTM A536
 - Flexi-Coat® fusion bonded epoxy finish which meets application methods AWWA C213
 - Open ears provide easy slip on installation and removal of nuts are not required preventing lost hardware
 - Canted ears for maximum tangential tightening of bale or strap
 - Wraparound design provides maximum pipe support, reinforcement, and sealing pressure
 - Wide skirt and heavy tapping boss provides excellent stability on the pipe
- **Gasket**
 - Nitrile (Buna-N) per ASTM D2000
 - Certified to NSF/ANSI 61-G& 372
 - Compounded to resist water, oil, natural gas, acids, alkalies, most (aliphatic) hydrocarbon fluids, and many other chemicals
 - Temperature range: -20°F to +180°F
 - TaperSeal™ hydro-mechanical lip enables the saddle to hold higher pressures with minimal nut torque
 - Gasket is fully cemented in a cavity to hold it in place
- **Bale Assembly** (*used only on 1.25" - ~14" nominal pipe size saddles with 1/2" thru 4" tap sizes*)
 - **Bale**
 - HSLA Carbon Steel per AWWA C111/A21.11
 - Fe/Zn Coated per ASTM F1941-10
 - Size:
 - 1.25" – 3" nominal pipe size = 1/2"-13UNC
 - 4" – 14" nominal pipe size = 5/8"-11UNC
 - Extra-Large (XLT) Taps < 14.73" O.D. = 5/8"-11UNC
 - Pipe contact surface flattened to provide a wider bearing surface against pipe
 - Rolled threads for improved physical characteristics, greater thread accuracy, and smooth surface finish
 - **Nut**
 - Carbon Steel per ASTM A307
 - Fe/Zn Coated per ASTM F1941-10
 - Size:
 - 1.25" – 3" nominal pipe size = 1/2"-13UNC Heavy Hex Semi-Finished
 - 4" – 14" nominal pipe size = 5/8"-11UNC Heavy Hex Semi-Finished
 - Extra-Large (XLT) Taps < 14.73" O.D. = 5/8"-11UNC Heavy Hex Semi-Finished
 - **Flat Washer**
 - Carbon Steel per ASTM F844
 - Fe/Zn Coated per ASTM F1941-10
 - Size:
 - 1.25" – 3" nominal pipe size = 1/2" Type A Plain
 - 4" – 14" nominal pipe size = 5/8" Type A Plain
 - Extra-Large (XLT) Taps < 14.73" O.D. = 5/8" Type A Plain
 - Fe/Zn Coated per ASTM F1941-10

SUBMITTAL INFORMATION

Ballcorp Corporation Stops - (FB1000-xx-G-NL style)



AWWA/CC TAPER THREAD INLET BY GRIP JOINT COMPRESSION FOR COPPER OR PLASTIC TUBING (CTS) OUTLET




Image shown above is an FB1000-4-G-NL.

VALVE SIZE	INLET SIZE	OUTLET SIZE	VALVE LENGTH	BODY OUTLET THREADS	APPROX. WT. LBS	PART NUMBER	✓ SUBMITTED ITEM(S)
3/4"	3/4"	3/4"	4-19/64"	3/4" Flare Copper	1.5	FB1000-3-G-NL	
3/4"	3/4"	1"	4-7/16"	1" Flare Copper	2.1	FB1000-34-G-NL	
1"	1"	1"	4-1/2"	1" Flare Copper	2.6	FB1000-4-G-NL	
1"	1"	1-1/4"	4-5/16"	1-1/4" Flare Copper	3.0	FB1000-45-G-NL	
1-1/4"	1-1/4"	1-1/4"	5-25/32"	1-1/4" Flare Copper	4.8	FB1000-5-G-NL	
1-1/2"	1-1/2"	1-1/2"	6-13/32"	1-1/2" Flare Copper	5.7	FB1000-6-G-NL	
1-1/2"	1-1/2"	2"	6-29/64"	2" Flare Copper	7.4	FB1000-67-G-NL	
2"	2"	2"	7-1/2"	2" Flare Copper	9.8	FB1000-7-G-NL	

Note: Ford recommends using insert stiffeners with plastic pipe or tubing.

FEATURES

- All brass that comes in contact with potable water conforms to AWWA Standard C800 (ASTM B584, UNS C89833)
- The product has the letters "NL" cast into the main body for lead-free identification
- Certified to NSF/ANSI Standard 61 and NSF/ANSI Standard 372 where applicable
- Brass components that do not come in contact with potable water conform to AWWA Standard C800 (ASTM B62 and ASTM B584, UNS C83600, 85-5-5-5)
- Ends are integral or secured with adhesive to prevent unintentional disassembly
- 300 PSI working pressure

The Ford Meter Box Company considers the information in this submittal form to be correct at the time of publication. Item and option availability, including specifications, are subject to change without notice. Please verify that your product information is current.




The Ford Meter Box Company, Inc.
P.O. Box 443, Wabash, Indiana U.S.A. 46992-0443
Phone: 260-563-3171 / Fax: 800-826-3487
Overseas Fax: 260-563-0167
www.fordmeterbox.com

03/24/17

Submitted By:

SUBMITTAL INFORMATION

Ball Valve Curb Stop - (B41-xxxW-G-NL style)



GRIP JOINT FOR COPPER OR PLASTIC TUBING (CTS) INLET BY FEMALE IRON PIPE THREAD OUTLET




Image shown above is a B41-444W-G-NL

VALVE SIZE	INLET SIZE	OUTLET SIZE	LENGTH	APPROX. WT. LBS	PART NUMBER	✓ SUBMITTED ITEM(S)
5/8"	3/4"	3/4"	2-15/16"	1.2	B41-233W-G-NL	
3/4"	3/4"	3/4"	3-37/64"	1.7	B41-333W-G-NL	
3/4"	1"	3/4"	3-5/32"	2.0	B41-343W-G-NL	
3/4"	1"	1"	3-7/8"	2.2	B41-344W-G-NL	
1"	1"	1"	3-19/32"	2.4	B41-444W-G-NL	
1-1/4"	1-1/4"	1-1/4"	5-3/16"	5.0	B41-555W-G-NL	
1-1/2"	1-1/2"	1-1/2"	5-1/16"	5.9	B41-666W-G-NL	
2"	2"	2"	6-1/64"	8.7	B41-777W-G-NL	

Note: Ford recommends using insert stiffeners with plastic pipe or tubing.

Note: 5/8" ball valves do not have a reinforced seat.

FEATURES

- All brass that comes in contact with potable water conforms to AWWA Standard C800 (ASTM B584, UNS C89833)
- The product has the letters "NL" cast into the main body for lead-free identification
- Certified to NSF/ANSI Standard 61 and NSF/ANSI Standard 372 where applicable
- Brass components that do not come in contact with potable water conform to AWWA Standard C800 (ASTM B62 and ASTM B584, UNS C83600, 85-5-5-5)
- Valve is non-directional and is watertight with flow in either direction
- Ends are integral or secured with adhesive to prevent unintentional disassembly
- Hole for attaching curb box rod or handle is provided in tee-head
- 300 PSI working pressure

Optional full 360° tee-head rotation. Add "R" into the part number (Example: B41-333WR-G-NL)

The Ford Meter Box Company considers the information in this submittal form to be correct at the time of publication. Item and option availability, including specifications, are subject to change without notice. Please verify that your product information is current.



The Ford Meter Box Company, Inc.

P.O. Box 443, Wabash, Indiana U.S.A. 46992-0443

Phone: 260-563-3171 / Fax: 800-826-3487

Overseas Fax: 260-563-0167

www.fordmeterbox.com

05/17/18

Submitted By:



Your Single Source Solution

U.S. OPERATING
COMPANY OF **HAILIANG**

Copper Tube for Plumbing and Mechanical Applications

Job Name

Job Location

Engineer

PRODUCT DESCRIPTION & MATERIAL

JMF Copper Tube for use in plumbing and mechanical applications & is manufactured from UNS C12200 grade of copper.

SPECIFICATIONS

JMF Company Copper Tube (Type K, L, M) conforms to the NSF/ANSI 61 Annex G requirements and meets ASTM B88. Copper drainage tube (DWV) meets ASTM B306. Copper refrigeration coils ACR straight lengths and line sets meet the chemical, mechanical, cleanliness and eddy current testing requirements of the applicable specifications of ASTM B280.

Type K Rated Working Pressure (PSIG)

Nominal Diameter	Weight /ft. (lbs)	Feet/ Bundle	150°F	200°F	300°F	400°F
1/4	0.145	500	913	860	842	537
3/8	0.269	500	960	904	885	565
1/2	0.344	500	758	713	698	446
5/8	0.418	200	626	589	577	368
3/4	0.641	200	724	682	668	426
1	0.839	100	557	524	513	327
1 1/4	1.04	100	452	425	416	266
1 1/2	1.36	100	420	396	387	247
2	2.06	-	370	348	341	217
2 1/2	2.93	-	338	319	312	199
3	4.00	-	328	308	302	193
3 1/2	5.12	-	311	293	286	183
4	6.51	-	306	288	282	180
5	9.67	-	293	276	270	172
6	13.90	-	295	277	271	173
8	25.90	-	314	295	289	184

Type L Rated Working Pressure (PSIG)

Nominal Diameter	Weight /ft. (lbs)	Feet/ Bundle	150°F	200°F	300°F	400°F
1/4	0.126	500	775	729	714	456
3/8	0.198	500	662	623	610	389
1/2	0.285	500	613	577	565	361
5/8	0.362	200	537	505	495	316
3/4	0.455	200	495	466	456	291
1	0.655	100	420	395	387	247
1 1/4	0.884	100	373	351	344	219
1 1/2	1.14	100	347	327	320	204
2	1.75	-	309	291	285	182
2 1/2	2.48	-	285	269	263	168
3	3.33	-	270	254	248	159
3 1/2	4.29	-	258	243	238	152
4	5.38	-	249	235	230	147
5	7.61	-	229	215	211	135
6	10.2	-	213	201	196	125
8	19.3	-	230	216	212	135

Contractor

Wholesaler

JMF Rep

INSTALLATION

Installations must comply with the latest applicable building codes for the local jurisdiction. For detailed installation instructions, consult the Copper Development Association at copper.org.

REFERENCE

C12200 99.9% Pure Copper (can be used for potable water)
NSF/ANSI 61 Annex G Safe Drinking Water Act (third party certification)
ASTM B88 Seamless Copper Water and Gas Tube (Type K, L, M)
ASTM B280 Seamless Copper Tube for Air Conditioning

Type M Rated Working Pressure (PSIG)

Nominal Diameter	Weight /ft. (lbs)	Feet/ Bundle	150°F	200°F	300°F	400°F
3/8	0.145	500	485	456	447	285
1/2	0.204	500	420	395	387	247
3/4	0.328	200	346	326	319	204
1	0.465	100	286	270	264	169
1 1/4	0.682	100	287	271	265	169
1 1/2	0.94	100	282	265	259	166
2	1.46	-	254	239	234	149
2 1/2	2.03	-	233	219	215	137
3	2.68	-	215	203	199	127
3 1/2	3.58	-	214	202	197	126
4	4.66	-	213	201	197	126
5	6.66	-	198	186	182	116
6	8.92	-	186	175	171	109
8	16.5	-	195	183	180	115

Type DWV Rated Working Pressure (PSIG)

Nominal Diameter	Weight /ft. (lbs)	Feet/ Bundle	150°F	200°F	300°F	400°F
1 1/4	0.65	100	280	269	258	165
1 1/2	0.809	100	249	240	230	147
2	1.07	-	185	178	170	109
3	1.69	-	135	130	125	80
4	2.87	-	127	122	117	75
5	4.43	-	129	124	119	76
6	6.1	-	126	121	116	74
8	10.6	-	124	119	114	73

Tables give computed allowable stress for annealed copper tube at indicated temperature.

TECHNICAL DATA

All ratings listed for types K, L, M, DWV and refrigeration service tube in the preceding charts are calculated for tube in the annealed condition. These values should be used when soldering, brazing or welding is used for joining components in a system. While the ratings for hard drawn tube are higher, they should only be used for systems using properly designed flare or compression mechanical joints, since joining by any heating process might anneal (soften) the tube. In designing a system, careful consideration should also be given to joint ratings as well as those of the components.

JMF COMPANY IS YOUR CONSOLIDATING SOURCE FOR copper tubing, line sets, copper fittings, push to fit, pex, ball valves, gas valves, plumbing valves, malleable fittings, steel nipples, plastic fittings, brass threaded, brass nipples, flare & compression, gas connectors, water connectors, appliance kits, cord sets and MORE.



Submittal Documents

LIDL 1517



Overview


Bid Date: 08-25-2026
Bid Number: 5166172

Section

2" RPZ ASSEMBLY

LEAD FREE BRASS NIPPLES

MODEL LVLFBN




FEATURES:

- Schedule 40
- Lead Free Brass Conforms to ASTM B43
- Dimensions and Ends Conform to ASTM B687
- Threads Conform to ASME B1.20.1
- Meets NSF/ANSI61, NSF/ANSI372 & CRN

AVAILABILITY:

- Stocked from 1/8" x Close through 4" x 12"
- Redi Cut Nipples are available from 1/2" through 3" diameter up to 60" in length



PROJECT		APPROVAL STAMP
PROJECT:		☐ APPROVED
ADDRESS:		☐ APPROVED AS NOTED
ENGINEER:		☐ NOT APPROVED
SUBMITTAL DATA:		REMARKS:
NOTES 1:		
NOTES 2:		

BRASS FITTINGS

CLASS 125 lbs.



FEATURES:

- Approved to ANSI/NSF 61-4 California AB 1953
- Meets Federal State Drinking Water Act, Lead Free Requirement
- Brass fittings conform to AWWA C800
- Brass castings conform to ASTM B584, UNS Alloy C89833
- Brass fittings dimensions conform to ASME B16.15
- NPT threads on all fittings conform to ASME B1.20.1
- Brass unions conform to specification A-A-59617
- Manufacturing facilities are ISO 9001:2008

Lead Free products contain less than .25% weighted average lead content on wetted surfaces.

LEAD FREE BRASS COMPOSITION				
	COPPER	TIN	LEAD	ZINC
Min.	87.00%	4.00%	0.00%	2.00%
Max.	91.00%	6.00%	0.10%	4.00%
	IRON	NICKEL	ANTIMONY	PHOSPHORUS
Min.	0.00%	0.00%	0.00%	0.00%
Max.	0.30%	1.00%	0.25%	0.05%
	SULFUR	ALUMINUM	SILICON	BISMUTH
Min.	0.00%	0.00%	0.00%	1.70%
Max.	0.08%	0.005%	0.005%	2.70%



Model 975XL2

Reduced Pressure Principle Assembly

Application

Ideal for use where Lead-Free* valves are required. Designed for installation on potable water lines to protect against both backsiphonage and backpressure of contaminated water into the potable water supply. Assembly shall provide protection where a potential health hazard exists. The assembly can be configured with a relief valve sensor that detects and signals excessive water discharge that, if left undetected, may cause property damage from flooding.

Standards Compliance

- ASSE® Listed 1013
- cUPC® Listed
- CSA® Certified B64.4
- AWWA Compliant C511
- Approved by the Foundation for Cross Connection Control and Hydraulic Research at the University of Southern California
- Meets the requirements of NSF/ANSI/CAN 61 and 372*
*(LESS THAN 0.25% WEIGHTED AVERAGE LEAD CONTENT)
- UL® Classified (less shut-off valves or with OS&Y valves)
- C-UL® Classified

Materials

Main valve body	Low Lead Cast Bronze ASTM B 584
Access covers	Low Lead Cast Bronze ASTM B 584
Fasteners	Stainless Steel, 300 Series
Elastomers	Silicone
	Buna Nitrile
Polymers	Noryl™
Springs	Stainless Steel, 300 series
Ball valve handles	Stainless Steel

Features

Sizes: 3/4", 1", 1-1/4", 1-1/2", 2"

Maximum working water pressure

Maximum working water temperature

Hydrostatic test pressure

End connections Threaded

175 PSI

180°F

350 PSI

ANSI B1.20.1

Relief Valve discharge port:

3/4" - 1" - 0.63 sq. in.

1 1/4" - 2" - 1.19 sq. in.



LEAD FREE



NSF/ANSI/CAN 61 & 372




Options

(Suffixes can be combined)

- ☐ - with full port QT ball valves (standard)
- ☐ MS - with relief valve excessive discharge sensor for flood detection and two-wire connection
- ☐ SE - with street elbows (3/4" & 1")
- ☒ U - with union ball valves
- ☐ TCU - with test cocks up
- ☐ FT - with integral male 45° flare SAE test fitting
- ☐ S - with bronze "Y" type strainer

Accessories

- ☐ Air gap (Model AG)
- ☐ Repair kits (rubber only)
- ☐ Thermal expansion tank (Mdl. XT)
- ☐ Soft seated check valve (Model 40XL2)
- ☐ Shock arrester (Model 1260XL)
- ☐ QT-SET Quick Test Fitting Set
- ☐ Relief Valve Monitoring Retrofit Kit (RFK-975XL2MS)



Dimensions & Weights (do not include pkg.)

MODEL SIZE		DIMENSIONS (approximate)														WITH BALL VALVES	
		A		B		C		D		E		F		G			
		in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	in.	mm	lbs.	kg
3/4	20	12	305	7 3/4	197	2 1/8	54	3	76	3 1/2	89	5	127	16 1/8	410	12	5.5
1	25	13	330	7 3/4	197	2 1/8	54	3	76	3 1/2	89	5	127	17 3/8	441	14	6.4
1 1/4	32	17	432	10 15/16	278	2 3/4	70	3 1/2	89	5	127	6 3/4	171	22 9/16	573	28	12.7
1 1/2	40	17 3/8	441	10 15/16	278	2 3/4	70	3 1/2	89	5	127	6 3/4	171	24 1/16	611	28	12.7
2	50	18 1/2	470	10 15/16	278	2 3/4	70	3 1/2	89	5	127	6 3/4	171	26 1/2	673	34	15.4

Zurn Water, LLC | Wilkins

1747 Commerce Way, Paso Robles, CA U.S.A. 93446 Ph. 855-663-9876, Fax 805-238-5766

In Canada | Zurn Industries Limited

7900 Goreway Drive, Unit 10, Brampton, Ontario L6T 5W6, 877-892-5216

www.zurn.com


Rev. M

Date: 12/23

Document No. BF-975XL2(LG)

Product No. Model 975XL2(LG)



Patent zurn.com/patents

MODEL 975XL2 3/4", 1", 1 1/4", 1 1/2" & 2" (STANDARD & METRIC)**Typical Installation**

Local codes shall govern installation requirements. To be installed in accordance with the manufacturers' instructions and the latest edition of the Uniform Plumbing Code. Unless otherwise specified, the assembly shall be mounted at a minimum of 12" (305mm) and a maximum of 30" (762mm) above adequate drains with sufficient side clearance for testing and maintenance. The installation shall be made so that no part of the unit can be submerged.




Capacity thru Schedule 40 Pipe

Pipe size	5 ft/sec	7.5 ft/sec	10 ft/sec	15 ft/sec
1/8"	1	1	2	3
1/4"	2	2	3	5
3/8"	3	4	6	9
1/2"	5	7	9	14
3/4"	8	12	17	25
1"	13	20	27	40
1 1/4"	23	35	47	70
1 1/2"	32	48	63	95
2"	52	78	105	167

**Specifications**

The Reduced Pressure Principle Backflow Preventer shall be certified to NSF/ANSI/CAN 61 and 372, shall be ASSE® Listed 1013, rated to 180°F, and supplied with full port ball valves. The main body and access covers shall be low lead bronze (ASTM B 584), the seat ring and all internal polymers shall be Noryl™ and the seat disc elastomers shall be silicone. The first and second checks shall be accessible for maintenance without removing the relief valve or the entire device from the line. If installed indoors, the installation shall be supplied with an air gap adapter. The assembly shall be configurable to include a sensor to monitor excessive water discharge from the relief valve for flood detection. The Reduced Pressure Principle Backflow Preventer shall be a ZURN WILKINS Model 975XL2.

ENGINEERED TO FIT 1¼" THROUGH 2" BACKFLOW PREVENTION DEVICE INSTALLATIONS



SLAB OR FOOTER
RECOMMENDED PAD/FOOTER SIZE:
LENGTH: 46" x 23"

SPECIFICATION:
BFProducts Inc. enclosures are manufactured to ASSE-1060 standards and designed to be used to help protect Backflow Prevention Devices from freezing conditions and vandalism. Factory assembled construction will include a gelcoat shell backed with chop-strand polyresin bonded fiberglass, internally insulated using polyurethane spray-foam.
WEIGHT: 26 LBS

Options:

- -H40 – Heat Source – HEAT TAPE
- - L37 – Pad lockable hasp and hinge connection for two piece assembly.
- T-1URF–Turf installationsrequire devoted discharge drain to facilitate flange ASSE-1060 bury.

BFPRODUCTS
CORPORATE OFFICE
P.O. BOX 242771
CHARLOTTE, NC 28224

PHONE: (704) 599-9407
FAX: (704) 599-0595
EMAIL: bfproducts@marketing.biz
WEBSITE: WWW.BFPRODUCTS.BIZ

BFProducts, Inc
Backflow Prevention Device Enclosures
"We've Got You Covered"

FIBERGLASS ENCLOSURE
MODEL # 322-APD
Submittal Sheet

SHEET NO.
08/22/09
322-APD

Submittal Documents

LIDL 1517



Overview

Bid Date: 08-25-2026
Bid Number: 5166172

Section

FIRE MAIN

Submittal Documents

LIDL 1517



Overview

Bid Date: 08-25-2026
Bid Number: 5166172

Section

PIPE & FITTINGS

ANSI/AWWA STANDARDS

ANSI/AWWA C151/A21.5, Ductile Iron Pipe, Centrifugally Cast for Water.

Ductile Iron Tyton Joint Pipe is centrifugally cast in metal molds in accordance with ANSI/AWWA C151/A21.5.

The asphaltic outside coating is in accordance with ANSI/AWWA C151/A21.51.

As specified in ANSI/AWWA C151/A21.51, pipe weights have been calculated using standard barrel weights and weights of bells being produced.

ANSI/AWWA C104/A21.4, Cement-Mortar Lining for Ductile-Iron Pipe and Fittings for Water.

The cement-mortar lining and inside coating are in accordance with ANSI/AWWA C104/ A21.4. Special linings and/or coatings can be furnished for specific conditions.

ANSI/AWWA C111/A21.11, Rubber-Gasket Joints for Ductile-Iron Pressure Pipe and Fittings.

Tyton Gaskets are furnished in accordance with ANSI/AWWA C111/A21.11.

ANSI/AWWA C105/A21.5, Polyethylene Encasement for Ductile Iron Pipe Systems.

If specifiers and users believe that corrosive soils will be encountered where our products are to be installed, please refer to ANSI/AWWA C105/A21.5, for proper external protection procedures.

ASTM A746-03 "Standard specification for Ductile Iron Gravity Sewer Pipe."**ASTM A716-08 "Standard Specification for Ductile Iron Culvert Pipe."****ASTM A536 "Standard Specification for Ductile Iron Castings."**

Tyton Joint is U.S. Pipe's trademark for pipe with a push-on type connection. Simplicity, sturdiness and watertightness are built into the system by design. Convincing proof of its worldwide acceptance is shown by the fact that more than 95% of the pipe now sold by U.S. Pipe is Tyton Joint.

Tyton Joint Pipe is available in sizes 3" through 64". Sizes 3" through 42" are available in nominal 18-foot laying lengths. 4" through 30" sizes, along with sizes 48" through 64", are available in nominal 20-foot laying lengths.

Tyton Joint Pipe in sizes 4" through 36" are UL listed, and sizes 4" through 16" are FM Approved.

When Tyton Joint Pipe is used for bridge crossings or other above-ground installations, each length of pipe must be supported in a manner to restrict both vertical and horizontal movement.

A Tyton Gasket is the only accessory required when installing Tyton Joint Pipe. It is a circular rubber gasket that has a modified bulb shape in cross section. Gaskets are furnished in accordance with ANSI/AWWA C111/ A21.1. Composition and dimensions of the gasket have been carefully engineered to ensure a watertight and lasting seal. The standard Tyton Gasket is manufactured of SBR — styrene butadiene rubber. Gaskets of special elastomers may be ordered for special applications. The gasket contour and bell socket contour ensure that the gasket will remain seated during proper assembly of the pipe. When joint restraint is required for push-on joint pipe, two options are available from U.S. Pipe. For joint restraint of 4" through 24", Field Lok 350 Gaskets may be used. Field Lok 350 Gaskets are rated for 350 psi in sizes 4" through 24". In addition, for 4" through 36" sizes, TR Flex Pipe and Fittings may be used, and for 30" through 64" sizes, HP Lok Pipe and Fittings may be used. TR Flex Pipe and Fittings are rated for working pressures for 350 psi in 4" through 24" sizes, 250 psi in sizes 30" through 36". For HP Lok Pipe and Fittings, the working pressure is 350 psi for 30" through 64". For higher pressure applications contact your U.S. Pipe representative. Complete details on Field Lok 350 Gaskets, TR Flex Pipe and Fittings, and HP Lok Pipe and Fittings can be found on our website, www.uspipe.com.

Tyton joint pipe is NSF/ANSI 61 Certified for drinking water system components.

NOTE: U.S. Pipe qualifies for Federal Procurement under Public Law No. 94-580, Section 6002, known as the Resource Recovery Act of 1976, since, due to modern technology, recycled iron and steel scrap are used to a large degree in our Ductile Iron Pipe production.

The plain end of the pipe is furnished beveled or with a quarter ellipse on the edge to allow assembly. More than 40 years of successful experience have proved its sealing capabilities. Hydrostatic tests have shown that the system will withstand pressures far in excess of rated pressures.

NOTE: Each of the following is a nationally recognized standards organization: American National Standards Institute (ANSI), American Water Works Association (AWWA), American Society for Testing and Materials (ASTM), Underwriters Laboratories (UL), National Fire Protection Association (NFPA), National Sanitation Foundation (NSF), Factory Mutual (FM)

SPECIFICATIONS

PRESSURE CLASS (Thickness, Dimension & Weight)

INCHES	PSI	INCHES		POUNDS		
SIZE	PRESSURE CLASS	THICKNESS	OUTSIDE DIAMETER ^a	BARREL WEIGHT PER FOOT	WEIGHT PER LAYING LENGTH ^b	
					18-FOOT	20-FOOT
3	—	—	—	—	—	—
4	350	0.25	4.80	10.9	205	230
6	350	0.25	6.90	16.0	305	335
8	350	0.25	9.05	21.1	400	445
10	350	0.26	11.10	27.1	515	570
12	350	0.28	13.20	34.8	660	730
14	250	0.28	15.30	40.4	780	865
14	300	0.30	15.30	43.3	920	1010
14	350	0.31	15.30	44.7	860	945
16	250	0.30	17.40	49.3	950	1050
16	300	0.32	17.40	52.5	1010	1115
16	350	0.34	17.40	55.8	1065	1175
18	250	0.31	19.50	57.2	1095	1210
18	300	0.34	19.50	62.6	1195	1320
18	350	0.36	19.50	66.2	1260	1390
20	250	0.33	21.60	67.5	1285	1420
20	300	0.36	21.60	73.5	1395	1540
20	350	0.38	21.60	77.5	1465	1620
24	200	0.33	25.80	80.8	1550	1710
24	250	0.37	25.80	90.5	1725	1905
24	300	0.40	25.80	97.7	1855	2050
24	350	0.43	25.80	104.9	1985	2195
30	150	0.34	32.00	103.5	2005	2210
30	200	0.38	32.00	115.5	2220	2450
30	250	0.42	32.00	127.5	2595	2690
30	300	0.45	32.00	136.5	2810	2870
30	350	0.49	32.00	148.4	2685	3110
36	150	0.38	38.30	138.5	2945	—
36	200	0.42	38.30	152.9	2940	—
36	250	0.47	38.30	170.9	3265	—
36	300	0.51	38.30	185.3	3525	—
36	350	0.56	38.30	203.2	3845	—

Table continued on next page. ►

NOTE:

Thicknesses and dimensions of 3" through 64" ductile iron pipe conform to ANSI/AWWA C151/A21.51. Weights may vary from the standard because of differences in bell weights.

^a Tolerance of O.D. of spigot end: 3–12 in., ±0.06 in.; 14–24 in., +0.05 in., -0.08 in.; 30–48 in., +0.08 in., -0.06 in.; 54–64 in., +0.04 in., -0.10 in.

^b Including bell; calculated weight of pipe rounded off to nearest 5 lbs.

PIPE MARKING TAPE

MODELS LVPMTD - LVPMTND

(DETECTABLE)

(NON-DETECTABLE)

UNIFORM COLOR CODE

	WHITE - Proposed excavation
	PINK - Temporary survey markings
	RED - Electric power lines, cables, conduit and lighting cables
	YELLOW - Gas, oil, steam, petroleum or gaseous materials
	ORANGE - Communication, alarm or signal lines, cables or conduit
	BLUE - Potable water
	PURPLE - Reclaimed water, irrigation and slurry lines
	GREEN - Sewers and drain lines

DESCRIPTION:

Lansdale's Pipe Tape provides easy detection and identification of buried pipe and our LVPMTND tape provides identification of non buried pipe. Custom tapes are available if needed and include custom colors, logos, wording, symbols, phone numbers etc.

Biaxially Oriented Polypropylene (BOPP) Resistance to Acids and Alkalis

Biaxially oriented polypropylene (BOPP) films are generally chemically inert and exhibit good resistance to most acids and alkalis, especially at room temperature and moderate concentrations. This is due to the non-polar, hydrophobic nature of polypropylene and its high chemical stability.

DATA SHEET

	DETECTABLE TAPE		NON- DETECTABLE TAPE
COLOR & LEGEND	APWA		APWA
Length (Ft)	1000 FT		1000 FT
Tolerance	± 5%		± 5%
Width (In)	2", 3", 4", 6", 12"		2", 3", 4", 6", 12"
Width Tolerance	± 2%		± 2%
Thickness (Mil)	5 mil - D2103		4 mil - D2103
Thickness Tolerance	± 5%		± 5%
Core Inside Diameter (mm)	76 mm		76 mm
Material	.35 Mil Aluminum Foil + 8 Mil Clear Bopp Film + 3.75 Mil Clear PE* Film		PE*
Yield Strength	MD	52lbf -D882	N/A
	TD	49lbf-D882	N/A
Break Strength	MD	66lbf-D882	N/A
	PSI	7800 PSI-D882	N/A
	TD	50lbf-D882	N/A
	PSI	7800 PSI-D882	N/A
Elongation	MD	80%-D882	803% - D882**
	TD	140%-D882	>1080% - D882**
Tongue Tear	MD	2lb-D1938	ISO 6383-1:2015 196 N/mm
	TD	6lb-D1938	ISO 6383-1:2015 196 N/mm
Tensile Strength	MD	50.8 lbs/in-D882	ASTM D882 52.3
	TD	50.0 lbs/10-D882	ASTM D882 52.3

NON-DETECTABLE

DETECTABLE



PROJECT	APPROVAL STAMP
PROJECT:	☐ APPROVED
ADDRESS:	☐ APPROVED AS NOTED
ENGINEER:	☐ NOT APPROVED
SUBMITTAL DATA:	REMARKS:
NOTES 1:	
NOTES 2:	

C153 DUCTILE IRON MECHANICAL JOINT FITTINGS


C153 DUCTILE IRON MECHANICAL JOINT FITTINGS

BASIC SPECIFICATIONS

- SIZES:**
- 2" - 64"
- MATERIAL:**
- Ductile Iron ASTM A536, Grade 65-45-12, 60-42-10 or 70-50-05.
- PRESSURE:**
- 350 PSI Water Working Pressure 2" - 24".
 - 250 PSI Water Working Pressure 30" - 48".
 - 150 PSI Water Working Pressure 54" - 64".
- TESTING:**
- In accordance with ANSI/AWWA C153/A21.53.
 - In accordance with UL - FM requirements.
 - All fittings are hydrostatically tested in accordance with SIGMA Quality Management Standard.
 - All fittings are heat coded to ensure traceability and verification of metallurgical properties in accordance with the prevailing standards and SIGMA Quality Management Standards.
- LAYING LENGTH:**
- Short body design - straight section of body deleted to provide a compact and lighter fitting without reducing strength or flow characteristics.
 - In accordance with ANSI/AWWA C153/A21.53.
- DEFLECTION:**
- Maximum allowable deflection for MJ Joint on a full length pipe is as mentioned below:
 1. 3" - 4" = 8 Degrees
 2. 6" = 7 Degrees
 3. 8" - 12" = 5 Degrees
 4. 14" - 48" = 3 Degrees
- CEMENT LINING:**
- Maximum Double cement lined in accordance with ANSI/AWWA C104/A21.4.
- COATING:**
- Interior of fitting is seal coated (asphaltic material) in accordance with ANSI/AWWA C104/A21.4 and NSF61 approved.
 - Exterior of fitting is seal coated (asphaltic material) in accordance with ANSI/AWWA C153/A21.53 and NSF61 approved.
- GASKETS:**
- SBR in accordance with ANSI/AWWA C111/A21.11.
 - Also available in EPDM, NBR and CR.
- T-BOLTS:**
- Low Alloy corrosion resistant high strength steel in accordance with ANSI/AWWA C111/A21.11.
- APPROVALS:**
- 3"-16" Underwriters Laboratories listed and Factory Mutual Approved.
- STANDARDS:**
- Certified to NSF61 Standard including Annex G & 372.
 - ANSI/AWWA C153/A21.53 for Compact Ductile Iron Fittings 2"-64" for water and other liquids.
- INSTALLATION:**
- Per ANSI/AWWA C600 and C111 using DIP conforming to C150/C151 and PVC pipe conforming to C900/C905.

For sewer applications that require mandrel passage after installation, SIGMA recommends the end user check the fitting with the respective size mandrel BEFORE installing the fitting. SIGMA Corporation will NOT take responsibility for any back charges incurred due to the fitting not being checked with a mandrel prior to installation.

ONE-LOK™ MODEL SLDE WEDGE RESTRAINT FOR DUCTILE IRON PIPE



PRODUCT SPECIFICATIONS

- MATERIAL:**
- Gland body, wedge inserts and break-off top actuating bolts are manufactured of high strength ductile iron in accordance with ASTM A536, Grade 65-45-12. Wedge inserts are heat-treated to a hardness of 370 BHN minimum.
- SIZE RANGE:**
- 3" through 64"
- DIMENSION:**
- Conform to ANSI/AWWA C111/A21.11 & ANSI/AWWA C153/A21.53 standards
- PRESSURE RATING:**
- Sizes 3"-16" carry a 350 psi WWP and sizes 18"- 64" carry a 250 psi WWP while providing a minimum 2:1 factor of safety.
- COATING:**
- Asphaltic black enamel
 - Electro-deposition "CORRSAFE™" available upon request. For further information, please refer to our CORRSAFE Product Information sheet at <http://www.sigmaco.com/pipe-restraint-product-coatings-linings/>
- APPROVALS:**
- Underwriters Laboratories' listed in sizes 3"-36" and Factory Mutual approved in sizes 3"-12".
- DEFLECTION:**
- 5° on 3"-12", 2° on 14"-16", 1.5° on 18"-30" and 1° on 36"- 64"
- TRACEABILITY:**
- Gland body, wedge inserts and break-off top actuating bolts are individually cast with exact heat code information.
- INSTALLATION:**
- In accordance with manufacturer's recommendation and applicable AWWA standards.

Submittal Documents

LIDL 1517



Overview

Bid Date: 08-25-2026
Bid Number: 5166172


Section

TAP ASSEMBLY

SPECIFICATION

TAPPING SLEEVE - FABRICATED STEEL

MODEL 622



APPLICATIONS

- **Typical Uses**
 - Tapping size-on-size branch connections on new or existing pipe
 - Tapping reducing branch connections on new or existing pipe
 - Installing valves and other miscellaneous service equipment
- **Standard Pipe Sizes**
 - 4" to 30" nominal
- **Outlet Type and Size**
 - 4" to 12"
- **Type of Pipe (see notes)**
 - Carbon Steel, Stainless Steel, Cast Iron, Asbestos Cement, PVC, Ductile Iron, HDPE
- **Working Pressure / Test Pressure (see notes)**
 - Up to 175 PSI / 262PSI

MATERIALS

- **Body**
 - Carbon Steel per ASTM A283 Grade C
 - Material thickness: 4" nominal pipe size(s) = 1/4" (top plate) 3/16" (bottom plate)
6"-30" nominal pipe size(s) = 3/8" (both plates)
- **Neck**
 - Carbon Steel per ASTM A53 or A513
 - Furnished with 3/4" NPT test outlet
 - Accepts full size cutters except size-on-size taps which require a 1/2" undersize shell cutter
- **Outlet Flange**
 - Carbon Steel per ASTM A36
 - Type AWWA C207 Class D steel ring flat face
 - Compatible with ANSI 125# and 150# bolt hole patterns
 - Recessed for tapping valve alignment per MSS SP-60
- **V-Lug**
 - Carbon Steel per ASTM A283 Grade C
 - Material thickness: 4"-6" nominal pipe size(s) = 3/16"
8"-30" nominal pipe size(s) = 1/4"



Smith-Blair
a xylem brand

SPECIFICATION

TAPPING SLEEVE - FABRICATED STEEL

MODEL 622

- **Gasket**
 - Nitrile (Buna-N) per ASTM D2000
 - Compounded to resist water, oil, natural gas, acids, alkalies, most (aliphatic) hydrocarbon fluids, and many other chemicals
 - Temperature range: -20°F to +180°F
 - Gasket is fully cemented in machined recess
- **Bolts**
 - High Strength Low Alloy (HSLA) Steel per AWWA C111/A21.11 – with rolled threads
 - Size:
 - 4”-6” nominal pipe size(s) = 5/8”-11UNC x 6” long, Oval Neck Track Head
 - 8”-24” nominal pipe size(s) = 3/4”-10UNC x 9” long, Oval Neck Track Head
 - 30” nominal pipe size(s) = 3/4”-10UNC x 11.25” long, Oval Neck Track Head
- **Nut**
 - HSLA Steel per AWWA C111/A21.11
 - Size:
 - 4”-6” nominal pipe size(s) = 5/8”-11UNC Heavy Hex Semi-Finished
 - 8”-30” nominal pipe size(s) = 3/4”-10UNC Heavy Hex Semi-Finished
- **Washer**
 - Carbon Steel per ASTM F844
 - Fe/Zn coated per ASTM F1941-10
 - Size:
 - 4”-6” nominal pipe size(s) = 5/8” Type A Plain
 - 8”-30” nominal pipe size(s) = 3/4” Type A Plain
- **Test Outlet**
 - Carbon Steel 3/4” FNPT half coupling per ASTM A865
 - Carbon Steel 3/4” MNPT square head test plug
- **Welding**
 - Welds accomplished using qualified welders
 - GMAW weld process utilized
- **Finish**
 - Flexi-Coat® fusion bonded epoxy

LISTINGS/STANDARDS

- Certified to NSF/ANSI 61 and NSF/ANSI 372
- Flexi-Coat® Fusion-Bonded Epoxy Coating meets requirements of AWWA C213
- Meets applicable portions of AWWA C223

08" C515 MJ X MJ

Front View Dimensions:
Overall Width: 13.50
Flange Diameter: $\phi 13.75$
Holes: 4 X $\phi 0.88$ HOLES
Slots: 2 X $\phi 0.88$ SLOTS
ON $\phi 11.75$ B.C.
MJ END:
ANSI A21.11
AWWA C111

Side View Dimensions:
Top Width: 9.00
Total Height: 10.38
Internal Height: 6.88
Bottom Width: 13.12
Offset: 0.67

08" C515 TYTON X TYTON



Front View Dimensions:
Overall Width: 13.50
Flange Diameter: $\phi 11.00$
Holes: 2 X $\phi 1.00$ HOLES
TYTON END:
AWWA C111
Bottom Width: 12.56
Overall Bottom Width: 14.19

Side View Dimensions:
Top Width: 9.00
Total Height: 10.38
Internal Height: 5.50
Bottom Width: 17.13
Offset: 2.81
Labels: TYTON 7, TYTON 7

08" C515 PVC X PVC

Front View Dimensions:
Overall Width: 13.50
Flange Diameter: $\phi 10.50$
PVC END:
AWWA C111

Side View Dimensions:
Top Width: 9.00
Total Height: 10.38
Internal Height: 5.25
Bottom Width: 16.23
Offset: 2.26
Labels: PVC, PVC



08" C515 MJ X TAP

Technical drawing showing two views of the 08" C515 MJ X TAP valve. The front view shows a circular body with a diameter of 13.50 inches. It features 8 x Ø0.88 holes on Ø11.75 B.C., 4 x Ø0.88 holes, and 2 x Ø0.88 slots on Ø11.75 B.C. The top flange has a diameter of Ø13.50 and the bottom flange has a diameter of Ø13.75. The side view shows a height of 10.38 inches, a width of 9.00 inches, and a base width of 12.56 inches. The side view also indicates a 2638 series valve with a 1.38 inch wide base.

Ø13.50
Ø13.75
Ø8.96
13.50
10.38
9.00
12.56
1.38
2638
MJ
PLG
6.75
6.88
0.67

8 X Ø0.88 HOLES ON Ø11.75 B.C.
TAP END:
ANSI B16.1
CLASS 125




4 X Ø0.88 HOLES
2 X Ø0.88 SLOTS ON Ø11.75 B.C.
MJ END:
ANSI A21.11
AWWA C111

08" C515 GRVD X GRVD


Technical drawing showing two views of the 08" C515 GRVD X GRVD valve. The front view shows a circular body with a diameter of 13.50 inches and a central hole with a diameter of Ø8.57. The side view shows a height of 10.38 inches, a width of 9.00 inches, and a base width of 11.50 inches. The side view also indicates a 2638 series valve with a 1.18 inch wide base.

13.50
Ø8.57
10.38
9.00
11.50
1.18
2638
GRV
GRV
4.29



08" C515 NRS RESILIENT WEDGE GATE VALVE
LBS.
1-5

[illegible]

OPERATING NUT WITH O-RING PLATE



THE ENGINEER'S SEAL (FOR ALL PROJECTS) (FOR ALL PROJECTS) (FOR ALL PROJECTS)		PROPERTY OF JACOBS ENGINEERING GROUP, INC. ALL RIGHTS RESERVED. NO REPRODUCTION OR TRANSMISSION OF THIS DOCUMENT OR ITS CONTENTS IS PERMITTED WITHOUT THE WRITTEN PERMISSION OF JACOBS ENGINEERING GROUP, INC.		PROJECT NO. 1222/2020 DATE 12/22/2020			
0.00 TO 0.05 0.05 TO 0.10 0.10 TO 0.15 0.15 TO 0.20 0.20 TO 0.25 0.25 TO 0.30 0.30 TO 0.35 0.35 TO 0.40 0.40 TO 0.45 0.45 TO 0.50 0.50 TO 0.55 0.55 TO 0.60 0.60 TO 0.65 0.65 TO 0.70 0.70 TO 0.75 0.75 TO 0.80 0.80 TO 0.85 0.85 TO 0.90 0.90 TO 0.95 0.95 TO 1.00 1.00 TO 1.05 1.05 TO 1.10 1.10 TO 1.15 1.15 TO 1.20 1.20 TO 1.25 1.25 TO 1.30 1.30 TO 1.35 1.35 TO 1.40 1.40 TO 1.45 1.45 TO 1.50 1.50 TO 1.55 1.55 TO 1.60 1.60 TO 1.65 1.65 TO 1.70 1.70 TO 1.75 1.75 TO 1.80 1.80 TO 1.85 1.85 TO 1.90 1.90 TO 1.95 1.95 TO 2.00 2.00 TO 2.05 2.05 TO 2.10 2.10 TO 2.15 2.15 TO 2.20 2.20 TO 2.25 2.25 TO 2.30 2.30 TO 2.35 2.35 TO 2.40 2.40 TO 2.45 2.45 TO 2.50 2.50 TO 2.55 2.55 TO 2.60 2.60 TO 2.65 2.65 TO 2.70 2.70 TO 2.75 2.75 TO 2.80 2.80 TO 2.85 2.85 TO 2.90 2.90 TO 2.95 2.95 TO 3.00 3.00 TO 3.05 3.05 TO 3.10 3.10 TO 3.15 3.15 TO 3.20 3.20 TO 3.25 3.25 TO 3.30 3.30 TO 3.35 3.35 TO 3.40 3.40 TO 3.45 3.45 TO 3.50 3.50 TO 3.55 3.55 TO 3.60 3.60 TO 3.65 3.65 TO 3.70 3.70 TO 3.75 3.75 TO 3.80 3.80 TO 3.85 3.85 TO 3.90 3.90 TO 3.95 3.95 TO 4.00 4.00 TO 4.05 4.05 TO 4.10 4.10 TO 4.15 4.15 TO 4.20 4.20 TO 4.25 4.25 TO 4.30 4.30 TO 4.35 4.35 TO 4.40 4.40 TO 4.45 4.45 TO 4.50 4.50 TO 4.55 4.55 TO 4.60 4.60 TO 4.65 4.65 TO 4.70 4.70 TO 4.75 4.75 TO 4.80 4.80 TO 4.85 4.85 TO 4.90 4.90 TO 4.95 4.95 TO 5.00 5.00 TO 5.05 5.05 TO 5.10 5.10 TO 5.15 5.15 TO 5.20 5.20 TO 5.25 5.25 TO 5.30 5.30 TO 5.35 5.35 TO 5.40 5.40 TO 5.45 5.45 TO 5.50 5.50 TO 5.55 5.55 TO 5.60 5.60 TO 5.65 5.65 TO 5.70 5.70 TO 5.75 5.75 TO 5.80 5.80 TO 5.85 5.85 TO 5.90 5.90 TO 5.95 5.95 TO 6.00 6.00 TO 6.05 6.05 TO 6.10 6.10 TO 6.15 6.15 TO 6.20 6.20 TO 6.25 6.25 TO 6.30 6.30 TO 6.35 6.35 TO 6.40 6.40 TO 6.45 6.45 TO 6.50 6.50 TO 6.55 6.55 TO 6.60 6.60 TO 6.65 6.65 TO 6.70 6.70 TO 6.75 6.75 TO 6.80 6.80 TO 6.85 6.85 TO 6.90 6.90 TO 6.95 6.95 TO 7.00 7.00 TO 7.05 7.05 TO 7.10 7.10 TO 7.15 7.15 TO 7.20 7.20 TO 7.25 7.25 TO 7.30 7.30 TO 7.35 7.35 TO 7.40 7.40 TO 7.45 7.45 TO 7.50 7.50 TO 7.55 7.55 TO 7.60 7.60 TO 7.65 7.65 TO 7.70 7.70 TO 7.75 7.75 TO 7.80 7.80 TO 7.85 7.85 TO 7.90 7.90 TO 7.95 7.95 TO 8.00 8.00 TO 8.05 8.05 TO 8.10 8.10 TO 8.15 8.15 TO 8.20 8.20 TO 8.25 8.25 TO 8.30 8.30 TO 8.35 8.35 TO 8.40 8.40 TO 8.45 8.45 TO 8.50 8.50 TO 8.55 8.55 TO 8.60 8.60 TO 8.65 8.65 TO 8.70 8.70 TO 8.75 8.75 TO 8.80 8.80 TO 8.85 8.85 TO 8.90 8.90 TO 8.95 8.95 TO 9.00 9.00 TO 9.05 9.05 TO 9.10 9.10 TO 9.15 9.15 TO 9.20 9.20 TO 9.25 9.25 TO 9.30 9.30 TO 9.35 9.35 TO 9.40 9.40 TO 9.45 9.45 TO 9.50 9.50 TO 9.55 9.55 TO 9.60 9.60 TO 9.65 9.65 TO 9.70 9.70 TO 9.75 9.75 TO 9.80 9.80 TO 9.85 9.85 TO 9.90 9.90 TO 9.95 9.95 TO 10.00 10.00 TO 10.05 10.05 TO 10.10 10.10 TO 10.15 10.15 TO 10.20 10.20 TO 10.25 10.25 TO 10.30 10.30 TO 10.35 10.35 TO 10.40 10.40 TO 10.45 10.45 TO 10.50 10.50 TO 10.55 10.55 TO 10.60 10.60 TO 10.65 10.65 TO 10.70 10.70 TO 10.75 10.75 TO 10.80 10.80 TO 10.85 10.85 TO 10.90 10.90 TO 10.95 10.95 TO 11.00 11.00 TO 11.05 11.05 TO 11.10 11.10 TO 11.15 11.15 TO 11.20 11.20 TO 11.25 11.25 TO 11.30 11.30 TO 11.35 11.35 TO 11.40 11.40 TO 11.45 11.45 TO 11.50 11.50 TO 11.55 11.55 TO 11.60 11.60 TO 11.65 11.65 TO 11.70 11.70 TO 11.75 11.75 TO 11.80 11.80 TO 11.85 11.85 TO 11.90 11.90 TO 11.95 11.95 TO 12.00 12.00 TO 12.05 12.05 TO 12.10 12.10 TO 12.15 12.15 TO 12.20 12.20 TO 12.25 12.25 TO 12.30 12.30 TO 12.35 12.35 TO 12.40 12.40 TO 12.45 12.45 TO 12.50 12.50 TO 12.55 12.55 TO 12.60 12.60 TO 12.65 12.65 TO 12.70 12.70 TO 12.75 12.75 TO 12.80 12.80 TO 12.85 12.85 TO 12.90 12.90 TO 12.95 12.95 TO 13.00 13.00 TO 13.05 13.05 TO 13.10 13.10 TO 13.15 13.15 TO 13.20 13.20 TO 13.25 13.25 TO 13.30 13.30 TO 13.35 13.35 TO 13.40 13.40 TO 13.45 13.45 TO 13.50 13.50 TO 13.55 13.55 TO 13.60 13.60 TO 13.65 13.65 TO 13.70 13.70 TO 13.75 13.75 TO 13.80 13.80 TO 13.85 13.85 TO 13.90 13.90 TO 13.95 13.95 TO 14.00 14.00 TO 14.05 14.05 TO 14.10 14.10 TO 14.15 14.15 TO 14.20 14.20 TO 14.25 14.25 TO 14.30 14.30 TO 14.35 14.35 TO 14.40 14.40 TO 14.45 14.45 TO 14.50 14.50 TO 14.55 14.55 TO 14.60 14.60 TO 14.65 14.65 TO 14.70 14.70 TO 14.75 14.75 TO 14.80 14.80 TO 14.85 14.85 TO 14.90 14.90 TO 14.95 14.95 TO 15.00 15.00 TO 15.05 15.05 TO 15.10 15.10 TO 15.15 15.15 TO 15.20 15.20 TO 15.25 15.25 TO 15.30 15.30 TO 15.35 15.35 TO 15.40 15.40 TO 15.45 15.45 TO 15.50 15.50 TO 15.55 15.55 TO 15.60 15.60 TO 15.65 15.65 TO 15.70 15.70 TO 15.75 15.75 TO 15.80 15.80 TO 15.85 15.85 TO 15.90 15.90 TO 15.95 15.95 TO 16.00 16.00 TO 16.05 16.05 TO 16.10 16.10 TO 16.15 16.15 TO 16.20 16.20 TO 16.25 16.25 TO 16.30 16.30 TO 16.35 16.35 TO 16.40 16.40 TO 16.45 16.45 TO 16.50 16.50 TO 16.55 16.55 TO 16.60 16.60 TO 16.65 16.65 TO 16.70 16.70 TO 16.75 16.75 TO 16.80 16.80 TO 16.85 16.85 TO 16.90 16.90 TO 16.95 16.95 TO 17.00 17.00 TO 17.05 17.05 TO 17.10 17.10 TO 17.15 17.15 TO 17.20 17.20 TO 17.25 17.25 TO 17.30 17.30 TO 17.35 17.35 TO 17.40 17.40 TO 17.45 17.45 TO 17.50 17.50 TO 17.55 17.55 TO 17.60 17.60 TO 17.65 17.65 TO 17.70 17.70 TO 17.75 17.75 TO 17.80 17.80 TO 17.85 17.85 TO 17.90 17.90 TO 17.95 17.95 TO 18.00 18.00 TO 18.05 18.05 TO 18.10 18.10 TO 18.15 18.15 TO 18.20 18.20 TO 18.25 18.25 TO 18.30 18.30 TO 18.35 18.35 TO 18.40 18.40 TO 18.45 18.45 TO 18.50 18.50 TO 18.55 18.55 TO 18.60 18.60 TO 18.65 18.65 TO 18.70 18.70 TO 18.75 18.75 TO 18.80 18.80 TO 18.85 18.85 TO 18.90 18.90 TO 18.95 18.95 TO 19.00 19.00 TO 19.05 19.05 TO 19.10 19.10 TO 19.15 19.15 TO 19.20 19.20 TO 19.25 19.25 TO 19.30 19.30 TO 19.35 19.35 TO 19.40 19.40 TO 19.45 19.45 TO 19.50 19.50 TO 19.55 19.55 TO 19.60 19.60 TO 19.65 19.65 TO 19.70 19.70 TO 19.75 19.75 TO 19.80 19.80 TO 19.85 19.85 TO 19.90 19.90 TO 19.95 19.95 TO 20.00 20.00 TO 20.05 20.05 TO 20.10 20.10 TO 20.15 20.15 TO 20.20 20.20 TO 20.25 20.25 TO 20.30 20.30 TO 20.35 20.35 TO 20.40 20.40 TO 20.45 20.45 TO 20.50 20.50 TO 20.55 20.55 TO 20.60 20.60 TO 20.65 20.65 TO 20.70 20.70 TO 20.75 20.75 TO 20.80 20.80 TO 20.85 20.85 TO 20.90 20.90 TO 20.95 20.95 TO 21.00 21.00 TO 21.05 21.05 TO 21.10 21.10 TO 21.15 21.15 TO 21.20 21.20 TO 21.25 21.25 TO 21.30 21.30 TO 21.35 21.35 TO 21.40 21.40 TO 21.45 21.45 TO 21.50 21.50 TO 21.55 21.55 TO 21.60 21.60 TO 21.65 21.65 TO 21.70 21.70 TO 21.75 21.75 TO 21.80 21.80 TO 21.85 21.85 TO 21.90 21.90 TO 21.95 21.95 TO 22.00 22.00 TO 22.05 22.05 TO 22.10 22.10 TO 22.15 22.15 TO 22.20 22.20 TO 22.25 22.25 TO 22.30 22.30 TO 22.35 22.35 TO 22.40 22.40 TO 22.45 22.45 TO 22.50 22.50 TO 22.55 22.55 TO 22.60 22.60 TO 22.65 22.65 TO 22.70 22.70 TO 22.75 22.75 TO 22.80 22.80 TO 22.85 22.85 TO 22.90 22.90 TO 22.95 22.95 TO 23.00 23.00 TO 23.05 23.05 TO 23.10 23.10 TO 23.15 23.15 TO 23.20 23.20 TO 23.25 23.25 TO 23.30 23.30 TO 23.35 23.35 TO 23.40 23.40 TO 23.45 23.45 TO 23.50 23.50 TO 23.55 23.55 TO 23.60 23.60 TO 23.65 23.65 TO 23.70 23.70 TO 23.75 23.75 TO 23.80 23.80 TO 23.85 23.85 TO 23.90 23.90 TO 23.95 23.95 TO 24.00 24.00 TO 24.05 24.05 TO 24.10 24.10 TO 24.15 24.15 TO 24.20 24.20 TO 24.25 24.25 TO 24.30 24.30 TO 24.35 24.35 TO 24.40 24.40 TO 24.45 24.45 TO 24.50 24.50 TO 24.55 24.55 TO 24.60 24.60 TO 24.65 24.65 TO 24.70 24.70 TO 24.75 24.75 TO 24.80 24.80 TO 24.85 24.85 TO 24.90 24.90 TO 24.95 24.95 TO 25.00 25.00 TO 25.05 25.05 TO 25.10 25.10 TO 25.15 25.15 TO 25.20 25.20 TO 25.25 25.25 TO 25.30 25.30 TO 25.35 25.35 TO 25.40 25.40 TO 25.45 25.45 TO 25.50 25.50 TO 25.55 25.55 TO 25.60 25.60 TO 25.65 25.65 TO 25.70 25.70 TO 25.75 25.75 TO 25.80 25.80 TO 25.85 25.85 TO 25.90 25.90 TO 25.95 25.95 TO 26.00 26.00 TO 26.05 26.05 TO 26.10 26.10 TO 26.15 26.15 TO 26.20 26.20 TO 26.25 26.25 TO 26.30 26.30 TO 26.35 26.35 TO 26.40 26.40 TO 26.45 26.45 TO 26.50 26.50 TO 26.55 26.55 TO 26.60 26.60 TO 26.65 26.65 TO 26.70 26.70 TO 26.75 26.75 TO 26.80 26.80 TO 26.85 26.85 TO 26.90 26.90 TO 26.95 26.95 TO 27.00 27.00 TO 27.05 27.05 TO 27.10 27.10 TO 27.15 27.15 TO 27.20 27.20 TO 27.25 27.25 TO 27.30 27.30 TO 27.35 27.35 TO 27.40 27.40 TO 27.45 27.45 TO 27.50 27.50 TO 27.55 27.55 TO 27.60 27.60 TO 27.65 27.65 TO 27.70 27.70 TO 27.75 27.75 TO 27.80 27.80 TO 27.85 27.85 TO 27.90 27.90 TO 27.95 27.95 TO 28.00 28.00 TO 28.05 28.05 TO 28.10 28.10 TO 28.15 28.15 TO 28.20 28.20 TO 28.25 28.25 TO 28.30 28.30 TO 28.35 28.35 TO 28.40 28.40 TO 28.45 28.45 TO 28.50 28.50 TO 28.55 28.55 TO 28.60 28.60 TO 28.65 28.65 TO 28.70 28.70 TO 28.75 28.75 TO 28.80 28.80 TO 28.85 28.85 TO 28.90 28.90 TO 28.95 28.95 TO 29.00 29.00 TO 29.05 29.05 TO 29.10 29.10 TO 29.15 29.15 TO 29.20 29.20 TO 29.25 29.25 TO 29.30 29.30 TO 29.35 29.35 TO 29.40 29.40 TO 29.45 29.45 TO 29.50 29.50 TO 29.55 29.55 TO 29.60 29.60 TO 29.65 29.65 TO 29.70 29.70 TO 29.75 29.75 TO 29.80 29.80 TO 29.85 29.85 TO 29.90 29.90 TO 29.95 29.95 TO 30.00 30.00 TO 30.05 30.05 TO 30.10 30.10 TO 30.15 30.15 TO 30.20 30.20 TO 30.25 30.25 TO 30.30 30.30 TO 30.35 30.35 TO 30.40 30.40 TO 30.45 30.45 TO 30.50 30.50 TO 30.55 30.55 TO 30.60 30.60 TO 30.65 30.65 TO 30.70 30.70 TO 30.75 30.75 TO 30.80 30.80 TO 30.85 30.85 TO 30.90 30.90 TO 30.95 30.95 TO 31.00 31.00 TO 31.05 31.05 TO 31.10 31.10 TO 31.15 31.15 TO 31.20 31.20 TO 31.25 31.25 TO 31.30 31.30 TO 31.35 31.35 TO 31.40 31.40 TO 31.45 31.45 TO 31.50 31.50 TO 31.55 31.55 TO 31.60 31.60 TO 31.65 31.65 TO 31.70 31.70 TO 31.75 31.75 TO 31.80 31.80 TO 31.85 31.85 TO 31.90 31.90 TO 31.95 31.95 TO 32.00 32.00 TO 32.05 32.05 TO 32.10 32.10 TO 32.15 32.15 TO 32.20 32.20 TO 32.25 32.25 TO 32.30 32.30 TO 32.35 32.35 TO 32.40 32.40 TO 32.45 32.45 TO 32.50 32.50 TO 32.55 32.55 TO 32.60 32.60 TO 32.65 32.65 TO 32.70 32.70 TO 32.75 32.75 TO 32.80 32.80 TO 32.85 32.85 TO 32.90 32.90 TO 32.95 32.95 TO 33.00 33.00 TO 33.05 33.05 TO 33.10 33.10 TO 33.15 33.15 TO 33.20 33.20 TO 33.25 33.25 TO 33.30 33.30 TO 33.35 33.35 TO 33.40 33.40 TO 33.45 33.45 TO 33.50 33.50 TO 33.55 33.55 TO 33.60 33.60 TO 33.65 33.65 TO 33.70 33.70 TO 33.75 33.75 TO 33.80 33.80 TO 33.85 33.85 TO 33.90 33.90 TO 33.95 33.95 TO 34.00 34.00 TO 34.05 34.05 TO 34.10 34.10 TO 34.15 34.15 TO 34.20 34.20 TO 34.25 34.25 TO 34.30 34.30 TO 34.35 34.35 TO 34.40 34.40 TO 34.45 34.45 TO 34.50 34.50 TO 34.55 34.55 TO 34.60 34.60 TO 34.65 34.65 TO 34.70 34.70 TO 34.75 34.75 TO 34.80 34.80 TO 34.85 34.85 TO 34.90 34.90 TO 34.95 34.95 TO 35.00 35.00 TO 35.05 35.05 TO 35.10 35.10 TO 35.15 35.15 TO 35.20 35.20 TO 35.25 35.25 TO 35.30 35.30 TO 35.35 35.35 TO 35.40 35.40 TO 35.45 35.45 TO 35.50 35.50 TO 35.55 35.55 TO 35.60 35.60 TO 35.65 35.65 TO 35.70 35.70 TO 35.75 35.75 TO 35.80 35.80 TO 35.85 35.85 TO 35.90 35.90 TO 35.95 35.95 TO 36.00 36.00 TO 36.05 36.05 TO 36.10 36.10 TO 36.15 36.15 TO 36.20 36.20 TO 36.25 36.25 TO 36.30 36.30 TO 36.35 36.35 TO 36.40 36.40 TO 36.45 36.45 TO 36.50 36.50 TO 36.55 36.55 TO 36.60 36.60 TO 36.65 36.65 TO 36.70 36.70 TO 36.75 36.75 TO 36.80 36.80 TO 36.85 36.85 TO 36.90 36.90 TO 36.95 36.95 TO 37.00 37.00 TO 37.05 37.05 TO 37.10 37.10 TO 37.15 37.15 TO 37.20 37.20 TO 37.25 37.25 TO 37.30 37.30 TO 37.35 37.35 TO 37.40 37.40 TO 37.45 37.45 TO 37.50 37.50 TO 37.55 37.55 TO 37.60 37.60 TO 37.65 37.65 TO 37.70 37.70 TO 37.75 37.75 TO 37.80 37.80 TO 37.85 37.85 TO 37.90 37.90 TO 37.95 37.95 TO 38.00 38.00 TO 38.05 38.05 TO 38.10 38.10 TO 38.15 38.15 TO 38.20 38.20 TO 38.25 38.25 TO 38.30 38.30 TO 38.35 38.35 TO 38.40 38.40 TO 38.45 38.45 TO 38.50 38.50 TO 38.55 38.55 TO 38.60 38.60 TO 38.65 38.65 TO 38.70 38.70 TO 38.75 38.75 TO 38.80 38.80 TO 38.85 38.85 TO 38.90 38.90 TO 38.95 38.95 TO 39.00 39.00 TO 39.05 39.05 TO 39.10 39.10 TO 39.15 39.15 TO 39.20 39.20 TO 39.25 39.25 TO 39.30 39.30 TO 39.35 39.35 TO 39.40 39.40 TO 39.45 39.45 TO 39.50 39.50 TO 39.55 39.55 TO 39.60 39.60 TO 39.65 39.65 TO 39.70 39.70 TO 39.75 39.75 TO 39.80 39.80 TO 39.85 39.85 TO 39.90 39.90 TO 39.95 39.95 TO 40.00 40.00 TO 40.05 40.05 TO 40.10 40.10 TO 40.15 40.15 TO 40.20 40.20 TO 40.25 40.25 TO 40.30 40.30 TO 40.35 40.35 TO 40.40 40.40 TO 40.45 40.45 TO 40.50 40.50 TO 40.55 40.55 TO 40.60 40.60 TO 40.65 40.65 TO 40.70 40.70 TO 40.75 40.75 TO 40.80 40.80 TO 40.85 40.85 TO 40.90 40.90 TO 40.95 40.95 TO 41.00 41.00 TO 41.05 41.05 TO 41.10 41.10 TO 41.15 41.15 TO 41.20 41.20 TO 41.25 41.25 TO 41.30 41.30 TO 41.35 41.35 TO 41.40 41.40 TO 41.45 41.45 TO 41.50 41.50 TO 41.55 41.55 TO 41.60 41.60 TO 41.65 41.65 TO 41.70 41.70 TO 41.75 41.75 TO 41.80 41.80 TO 41.85 41.85 TO 41.90 41.90 TO 41.95 41.95 TO 42.00 42.00 TO 42.05 42.05 TO 42.10 42.10 TO 42.15 42.15 TO 42.20 42.20 TO 42.25 42.25 TO 42.30 42.30 TO 42.35 42.35 TO 42.40 42.40 TO 42.45 42.45 TO 42.50 42.50 TO 42.55 42.55 TO 42.60 42.60 TO 42.65 42.65 TO 42.70 42.70 TO 42.75 42.75 TO 42.80 42.80 TO 42.85 42.85 TO 42.90 42.90 TO 42.95 42.95 TO 43.00 43.00 TO 43.05 43.05 TO 43.10 43.10 TO 43.15 43.15 TO 43.20 43.20 TO 43.25 43.25 TO 43.30 43.30 TO 43.35 43.35 TO 43.40 43.40 TO 43.45 43.45 TO 43.50 43.50 TO 43.55 43.55 TO 43.60 43.60 TO 43.65 43.65 TO 43.70 43.70 TO 43.75 43.75 TO 43.80 43.80 TO 43.85 43.85 TO 43.90 43.90 TO 43.95 43.95 TO 44.00 44.00 TO 44.05 44.05 TO 44.10 44.10 TO 44.15 44.15 TO 44.20 44.20 TO 44.25 44.25 TO 44.30 44.30 TO 44.35 44.35 TO 44.40 44.40 TO 44.45 44.45 TO 44.50 44.50 TO 44.55 44.55 TO 44.60 44.60 TO 44.65 44.65 TO 44.70 44.70 TO 44.75 44.75 TO 44.80 44.80 TO 44.85 44.85 TO 44.90 44.90 TO 44.95 44.95 TO 45.00 4							



COMPANY INFORMATION COMPANY NAME: AWW ADDRESS: 1000 W. 10th St. CITY: CHICAGO, IL 60607 PHONE: 312.467.1000 FAX: 312.467.1001 E-MAIL: SALES@AWW.COM WEBSITE: WWW.AWW.COM		PRODUCT INFORMATION PRODUCT NAME: 08" CS15 NRS RESILIENT WEDGE GATE VALVE SIZE: 08" MATERIAL: CS15 WEIGHT: 150 LBS PRESSURE: 150 PSI TEMPERATURE: 120°F CYCLES: 100,000 LEAKAGE: 0.1% @ 150 PSI TEST PRESSURE: 250 PSI TEST DURATION: 10 MIN TEST RESULTS: PASS DATE: 12/22/2020 BY: CW CHECKED BY: 12/22/2020 SCALE: 1:5 DRAWN BY: SoloWorks 2016 SP2 REVISION: 4 TOTAL: 6		AWW AMERICAN WATER WORKS ASSOCIATION AWWA 1000 W. 10th St. CHICAGO, IL 60607 312.467.1000 WWW.AWW.COM
---	--	--	--	--

<u>ITEM NO.</u>	<u>COMPONENT</u>	<u>QTY.</u>	<u>SIZE</u>	<u>STANDARD MATERIAL</u>	<u>MATERIAL OPTIONS</u>
1	BODY	1	-	DUCTILE IRON	-
2	WEDGE	1	-	EPDM/DUCTILE IRON	-
3	COVER	1	-	DUCTILE IRON	-
4	STEM	1	-	C99500	C86700, 304 SS, 316 SS
5	THRUST WASHER	2	-	ACETAL	C26000
6	GLAND	1	-	DUCTILE IRON	-
7	STEM NUT	1		C99500	C87850
8	O-RING	1	#335	EPDM	BUNA-N
9	O-RING	1	#447	EPDM	BUNA-N
10	HEX NUT	10	5/8"-11	18-8 S	316 SS
11	HEX HEAD CAP SCREW	2	5/8"-11 X 2 1/4	18-8 SS	316 SS
12	HEX HEAD CAP SCREW	1	1/2"-13 X 1 1/4	18-8 SS	316 SS
13	WASHER	1	1/2"	18-8 SS	316 SS
14	HEX HEAD CAP SCREW	8	5/8-11 X 2 1/2	18-8 SS	316 SS
15	O-RING	3	#216	EPDM	BUNA-N
16	OPERATING NUT	1	-	CAST IRON	DUCTILE IRON, C86700, **Ø 14" HANDWHEEL**

- VALVES CONFORM WITH THE FOLLOWING STANDARDS
 - AWWA C515
 - NSF 61
- LOW ZINC BRASS STEM AND STEM NUT AVAILABLE
- 100% DOMESTIC FASTENERS AND ORINGS OPTIONS AVAILABLE
- *OPEN LEFT* (COUNTERCLOCKWISE) AND *OPEN RIGHT* (CLOCKWISE) OPTIONS AVAILABLE
- TURNS TO OPEN FROM FULLY CLOSED: 26
- AWWA MAXIMUM ALLOWABLE CLOSING TORQUE 150 FT-LBS
- OPTIONAL HANDWHEEL CAN BE SUBSTITUTED FOR STANDARD 2" SQUARE OP. NUTS.
 - **NOTE: STANDARD HANDWHEEL SIZE LISTED OUT IN PARTS LIST.**

COMPANY: WATTS ADDRESS: 1000 W. 10TH AVE., SUITE 100, DENVER, CO 80202 PHONE: 303.733.1100 FAX: 303.733.1101 WWW: WWW.WATTSVALVE.COM		MODEL: 08" C515 NRS RESILIENT WEDGE GATE VALVE SIZE: 08" MATERIAL: DUCTILE IRON END USE: WATER DATE: 12/2/2020 DRAWN BY: SW CHECKED BY: SW APPROVED BY: SW		SHEET NO.: 5 TOTAL SHEETS: 6 PROJECT NO.: 2018-002
--	--	--	--	--

REQUIREMENT:

- ☐ Class 30B
- ☐ Class 35B
- ☐ Ductile Iron



Quality – Service – Commitment – Delivered.

MUNICIPAL VALVE AND SERVICE BOXES

SIZE RANGE:

- Adjustable Slip and Screw Type with standard assembled lengths ranging from 15" to 72" (Lengths do not include risers and/or extensions).

STANDARDS:

- Manufactured from cast iron in accordance with and meet all applicable terms and provisions as per ASTM A48 standard and will meet the minimum tensile strength requirements.
- Sigma Valve Boxes when properly installed can be used for projects related to American Association of State and Highway Officials (AASHTO) standards.

INSTALLATION:

- Per AWWA M44

COATING:

- Black Asphaltic Bituminous paint. Coating thickness of 1 to 2mil is applied on the product.

Extention Height	Components	2 Pc Screw Type	2 Pc Slip Type	Extention Height	Components	3 Pc Screw Type	Extention Height	Components	Screw Type Service Box
19-22	10T + 15B	VB261	VB461	27-37	10T + 12B	VB630AA	24-33	15T + 21B	VB791C
27-37	16T + 24B	VB262	VB462	33-42	10T + 18B	VB630A	30-39	15T + 27B	VB792C
39-50	16T + 36B	VB264	VB464	39-49	16T + 24B	VB630B	30-42	18T + 27B	VB792D
39-60	26T + 36B	VB266	VB466B / VB466N*	45-54	16T + 30B	VB630C	36-48	18T + 33B	VB793D
50-71	26T + 48B	VB267	VB467	51-60	16T + 36B	VB630CC	36-54	24T + 33B	VB793E
63-81	26T + 60B	VB268	VB468	45-66	26T + 30B	VB630D	42-60	24T + 39B	VB794E
				51-72	26T + 36B	VB630DD	41-64	30T + 39B	VB795E
				63-84	26T + 48B	VB630F			
				74-94	26T + 60B	VB630G			
			B = With Flange N = Without Flange	NOTE: Requires use of base - Above ships with VB6306 base standard - Other sizes available					

**** ADD -35 TO ITEM # FOR CLASS 35B GREY IRON REQUIREMENTS / ADD -D FOR DUCTILE IRON REQUIREMENTS**
RISERS, EXTENSIONS AND VARIOUS SPECIALLY LETTERED LIDS AVAILABLE FOR ALL ITEMS




700 Goldman Drive
 Cream Ridge, NJ 08514
 CRMCSR@sigmaco.com

5000 Askins Lane
 Houston, TX 77093
 HTNCSR@sigmaco.com

4652 E. Guasti Rd
 Ontario, CA 91761
 ONTCRSR@sigmaco.com

21699 Torrence Avenue
 Sauk Village, IL 60411
 CHICSR@sigmaco.com

Highway 22 West
 Alexander City, AL 35010
 ALXCSR@sigmaco.com



SECTION "A - A"

Masonry Supply, Inc

P.O. BOX 943

SELMA, NC 27576


PH: (919) 351-4014 (office), (919) 291-8761 (cell) FAX: (919) 351-4047

EMAIL: masonrysupply@hotmail.com

ITEM: 24" CONCRETE VALVE BOX COLLAR

PART # MSVB - 24

MATERIAL SPEC: A - 3 CONCRETE (4000 psi @28 DAYS)



Notes:

1. Made of minimum 4000 PSI Concrete
2. Height - 4', width of sides - 5"
3. 3/4" chamfers on front corners
4. Four pieces of #3 rebar
5. Two inch brass marker plate with anchor
6. Lettering stamped on marker as specified in 3" letters
 Standard Marker = MV (Main Valve) top front
 = BO (Blow-off) bottom front
 = AV (Air Release Valve)
 = LM (Line Marker)

Masonry Supply, Inc

P.O. BOX 943
 SELMA, NC 27576

PH: (919) 351-4014 (office), (919) 291-8761 (cell) FAX: (919) 351-4047
 EMAIL: masonrysupply@hotmail.com

ITEM: PRECAST CONCRETE 4 FT TALL MARKING POSTS W/BRASS

PART # MMVB 04 W/BR

MATERIAL SPEC: A - 3 CONCRETE (4000 psi @28 DAYS)

Submittal Documents

LIDL 1517




Overview

Bid Date: 08-25-2026
Bid Number: 5166172

Section

FIRE HYDRANT

PRODUCT DATA



*Nozzle height ground line

ACCESSORIES

SEAT REMOVAL WRENCH — A light-weight universal combination tool is used to remove the main valve components. The bronze alloy seat ring unthreads from the drain ring by engaging the wrench at the bottom of the break coupling.

HOLD DOWN NUT WRENCH — The wrench fits the hold down nut for easy removal.

LUBRICATION — The hydrant features a dual lubrication system. Simply add grease or oil by removing the lubrication bolt on top of the weathershield.

EXTENSION KIT — Contains everything required to extend the stem and barrel. Available in 6" increments.

SAFETY FLANGE REPAIR KIT — Includes safety flanges, stem coupling, pins and clips, flange O-rings, all bolts, nuts, and hardware to repair a hydrant damaged by a traffic accident.

MAIN VALVE SEAT REPAIR KIT — Contains drain valve facings, SS rivets, main valve seat, lock washer, and all required O-rings.

RECOMMENDED SPECIFICATIONS

1. Fire hydrant shall be manufactured in accordance with AWWA standard C502, utilizing dry barrel dry top design.
2. Fire hydrant shall be rated at 250 PSI working pressure and tested to 500 PSI hydrostatic pressure.
3. Fire hydrant shall be of dual lubrication design featuring a lubrication bolt in the top of the weathershield for oil or grease.
4. Fire hydrant shall feature o-ring seals at the bonnet, break line, and elbow.
5. The traffic break coupling shall be comprised of cast iron with the seat wrench mounting-point located on the squared bottom.
6. Break flanges shall be made of cast iron and allow 360 degrees of rotation.
7. The nozzle section and one piece bonnet shall be comprised of cast iron coated in durable polyester powder coat.
8. Nozzles shall be threaded and screwed into the nozzle section and mechanically secured with a set screw.
9. The stand pipe and elbow shall be comprised of ductile iron utilizing stainless steel bolts/nuts below ground level.
10. The upper drain valve shall consist of bronze alloy and contain rubber facings secured in place by stainless steel rivets.
11. The seat ring shall be comprised of bronze alloy and utilize a double O-ring seal.
12. Fire hydrant shall be manufactured with a one piece bottom plate that limits travel in the elbow of the hydrant and is secured in place by a lock washer on the lower stem threading.
13. Fire hydrant shall be the M&H model 129 manufactured by M&H Valve Co.

SUGGESTED SPECIFICATIONS (1 of 2)

M&H AWWA C502 FIRE HYDRANTS

- ◆ Model 129
- ◆ Traffic Model
- ◆ 250 PSI Working Pressure – 500 PSI Hydrostatic Test - AWWA
- ◆ UL / FM Approved

GENERAL	Fire hydrants shall comply in all respects with AWWA Standard C-502, latest revision. Fire hydrants shall be of the compression type, with the main valve opening against the pressure and closing with the pressure. The main valve opening shall be (4 ½" or 5 ¼") in diameter. Fire Hydrant shall be of a dry barrel, dry top design. The nozzle section shall consist of two (2) hose nozzles and one (1) pumper nozzle or other as specified.
RATING	Fire hydrants shall be rated at 250 psi water working pressure, tested at 500 pounds hydrostatic for structural soundness in the following manner: 500 pound hydrostatic test supplied from the inlet side, first with the main valve closed for the testing of the valve seat: second, with the main valve open for testing of the drain valves and the hydrant barrel. Testing to be complete in accordance with AWWA C-502 and UL & FM requirements.
END CONFIGURATION	Hydrants shall be connected to the main by a 4" or 6" fusion bonded, epoxy coated mechanical joint or flanged shoe. Mechanical joint shoes shall be fitted with strapping lugs.
DESIGN	The main valve seat of the hydrant shall be made of rubber and be supported by a one-piece bronze top plate / drain valve mechanism. Drain valve shall have replaceable rubber facings. The bottom stem threads of the main valve rod shall be fitted with an epoxy coated, cast iron bottom plate, sealing lower rod threads from the water. Changes in size or shape of the waterway (hydrant nozzles) shall be accomplished by means of easy curves. Exclusive of the main valve opening, the net area of the waterway of the barrel and the foot piece at the smallest part shall not be less than 120% of that of the net opening of the main valve. Hose and pumper nozzles shall be threaded and screwed into the nozzle section. And then mechanically locked to prevent turning. Hose and pumper caps shall be chained to the hydrant The hydrant shall be so designed that when it is in place, no excavation will be required to remove the main valve and movable parts of the drain valve. Further, the hydrant shall be of the type that can be extended without excavating. Hydrants shall be so designed that, in the event of accident, or breaking of the hydrant above or near grade level; the main valve will remain closed. The main valve rod shall be made in two parts and fitted with breakable coupling at the ground line flange. The ground line connection between nozzle section and the barrel shall incorporate the use of two traffic flange. This connection shall be so designed that the nozzle section can be rotated in any increment of 360°. The ground line connection between the barrel and nozzle sections shall have a rubber o-ring gasket to provide a seal. The operating threads of the hydrant shall be so designed as to avoid the working of any iron or steel parts against either iron or steel. The operating stem and operating nut threads shall be square or acme type.

SUGGESTED SPECIFICATIONS (2 of 2)

DESIGN

(Continued)

The operating thread shall be lubricated at factory with food grade grease. Access shall be provided to field lubricate the operating mechanism.

The operating thread shall be sealed from water at all times when the valve is either in the opened or closed position. The operating rod shall be bronze sheathed where it passes through the double "O" ring seal in the bonnet.

The bonnet shall be weather proof and utilize a weather shield integral with the external wrench operating nut.

The operating nut shall be made of bronze with a self-lubricating design.

Hydrants shall be of the dry barrel type and hydrant shoe shall have two positive acting non-corrosive drain valves that shall drain the hydrant completely by opening when the main valve is closed, and close tightly in accordance with AWWA C-502 requirements when main valve is open.

The main valve assembly shall be seated in the hydrant with a bronze-to-bronze interface to facilitate removal of the main valve, should maintenance be required. The nozzle section shall consist of two-2 1/2" hose nozzles to the specified thread designation (NST or other, as specified) and one pumper nozzle 4 1/2" in diameter to the specified thread designation (NST or other, as specified), or other combination of nozzle outlets, including independent hose gate valves, as specified.

Two O-ring seals shall be utilized where the main hydrant rod passes through the 1 piece bonnet.

Hydrant standpipe shall be ductile iron and single piece for all bury depths.

All like parts of hydrants of the same size and model produced by the same manufacturer shall be interchangeable.

Hydrant shall open by turning to the (left or right). Direction of opening to be permanently marked on hydrant bonnet.

Threads on hose and steamer nozzles shall be National Standard unless otherwise specified.

Size and shape of operating nuts cap nuts shall conform to National Standard unless otherwise specified.

Bury shall be (specify depth of bury) measuring depth from grade line to bottom of trench or connecting pipe.

Auxiliary shut-off (isolation) gate valves, when required, shall be of the same manufacture as the hydrant.

COATING

Hydrant shoes shall have an interior and exterior thermosetting epoxy coating of 5 to 6 mils meeting AWWA C550. Exterior of hydrant nozzle section shall be Fire Hydrant Red (or as specified).

MARKINGS

Hydrant shall be marked with the name of the manufacturer, size of valve opening, direction of opening and the year of manufacture all in accordance with the AWWA C-502. Country of origin to be cast on all major hydrant castings.

SOURCE

Hydrants shall be M&H Model 129 or approved equal

Submittal Documents

LIDL 1517



Overview

Bid Date: 08-25-2026
Bid Number: 5166172

Section

8"DCDA BFP VAULT

PRODUCT INFORMATION

8'x5'x6' (ID) WITH FLOOR
8" BACKFLOW VAULT

VAULT = 17,000 #
LID = 3,400 #

SPECIFICATIONS

MEETS ASTM C858 & C857

RATING: A-8 (H-10)

CONCRETE TO BE 4,000 PSI
@ 28 DAYS

REINFORCING BAR MEETS
ASTM A 615

10" STEPS ON 12" CENTERS

BUTYL SEALANT MEETING ASTM
C 990 TO BE USED ON JOINTS

ACCESS HATCH SHALL BE
FABRICATED WITH 1/4"
ALUMINUM DIAMOND PLATE
DESIGNED TO SUPPORT 300 psf
36"x36" FRAME OPENING
EQUIPPED WITH: SLAM LOCK,
MOUNT LIFT HANDLE, HOLD-
OPEN ARM, SS HARDWARE
AND HINGES

PENETRATIONS SIZE AND
LOCATION VARY PER JOB

CALL FOR ADDITIONAL SPECS






DRAWING INFORMATION

Drawn By: CTP
Checked By: JJG
Revision: 1
Date: 1/12/2022

APPROVED BY:

print: _____

sign: _____



Scale: 1/4" = 1'



**BARTOW
PRECAST**

770.382.4462
sales@bartowprecast.com
WWW.BARTOWPRECAST.COM



Model 350ASTDA

Double Check Detector Assembly

Application

Designed for installation on water lines in fire protection systems to protect against both backsiphonage and backpressure of polluted water into the potable water supply. Model 350ASTDA shall provide protection where a potential health hazard does not exist. Incorporates metered by-pass to detect leaks and unauthorized water use.

Standards Compliance (Horizontal & Vertical)

- ASSE® Listed 1048
- AWWA Compliant C510 (with gates only) and C550
- UL® Classified
- C-UL® Classified
- FM® Approved
- CSA® Certified B64.5
- Approved by the Foundation for Cross Connection Control and Hydraulic Research at the University of Southern California
- Meets the requirements of NSF/ANSI/CAN 61*
*(0.25% MAX. WEIGHTED AVERAGE LEAD CONTENT)

By-Pass Backflow Assembly 3/4" Model 950XLD

Materials

Main valve body	304L Stainless steel
Access covers	304L Stainless steel
Internals	Stainless steel, 300 Series NORYL™
Fasteners & springs	Stainless Steel, 300 Series
Elastomers	EPDM (FDA approved) Buna Nitrile (FDA approved)
Polymers	NORYL™

Features

Sizes:	2 1/2", 3", 4", 6", 8", 10"
Maximum working water pressure	175 PSI
Maximum working water temperature	140°F
Hydrostatic test pressure	350 PSI
End connections (Grooved for steel pipe)	AWWA C60C
(Flanged)	ANSI B16.42
	Class 150

Dimensions & Weights (do not include pkg.)

MODEL 350ASTDA SIZE	WEIGHT							
	WITH OS&Y GATES (GXF)		WITH OS&Y GATES (GXG)		WITH BUTTERFLY VALVES (GXG)		WITH BUTTERFLY VALVES (FXG)	
	in.	mm	lbs.	kg	lbs.	kg	lbs.	kg
2 1/2	65	126	57	116	53	93	42	103
3	80	143	65	131	60	97	44	110
4	100	218	99	198	90	101	46	123
6	150	352	160	322	147	164	74	194
8	200	667	303	613	278	350	159	373
10	250	885	401	827	375	463	210	521

MODEL 350ASTDA SIZE		DIMENSION (approximate)																	
		A		A WITH BUTTERFLY VALVES		B LESS GATE VALVES		C		D		E OS&Y OPEN		E OS&Y CLOSED		E WITH BUTTERFLY VALVES		F	
		in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm	in	mm
2 1/2	65	31 7/8	810	28 3/4	730	n/a	n/a	12	305	7 1/4	184	17 3/4	451	15 3/8	391	8 1/4	210	5	127
3	80	32 7/8	835	29 3/8	746	n/a	n/a	12	305	7 1/4	184	20 1/4	514	17	432	8 1/4	210	5	127
4	100	34 7/8	886	30 1/4	768	n/a	n/a	12	305	8	203	22 1/2	572	18 1/4	464	9	229	5	127
6	150	43 1/2	1105	36 1/2	927	n/a	n/a	10 1/2	267	10	254	30 1/2	775	24 1/4	616	10 1/4	260	6	152
8	200	52 3/4	1340	45 3/4	1162	n/a	n/a	15 1/8	384	11	279	37	940	28 1/2	724	18 1/2	470	8 3/8	213
10	250	55 3/4	1416	49 3/4	1264	n/a	n/a	15 1/8	384	12	305	45 5/8	1159	34 3/4	883	18 1/2	470	8 3/8	213



MODEL 350ASTDABF
(SHOWN WITH OPTIONAL
FLANGED END BUTTERFLY VALVES)




Options



(Suffixes can be combined)

- ☒ - with flanged end OS & Y gate valves (standard)
- ☐ LM - less water meter
- ☐ - with gallon meter (standard)
- ☐ CFM - with cu ft meter
- ☐ CMM - with cu meter meter
- ☐ G - with grooved end OS&Y gate valves
- ☐ FG - with flanged inlet gate connection and grooved outlet gate connection
- ☐ PI - with Post Indicator Gate Valves
- ☐ BG - with grooved end butterfly valves with integral supervisory switches
- ☐ BF - with flanged end butterfly valves with integral supervisory switches
- ☐ RV - with By-pass on right hand side

Accessories

- ☐ [Repair kit](#)
- ☐ Thermal expansion tank ([Model XT- Spec Sheet](#))
- ☐ OS & Y Gate valve tamper switch ([OSY-40](#))



MODEL 350ASTDA 2 1/2", 3" & 4" (STANDARD & METRIC)**MODEL 350ASTDA 6" 8" & 10" (STANDARD AND METRIC)****Suggested PRV Pairing:**

[Model ZW5000](#) Hose Valve ([Spec Sheet](#))

[Model ZW5004](#) Floor Control - Sprinkler Valve ([Spec Sheet](#))

[Model ZW209FP](#) Fire Protection Pressure R. ([Spec Sheet](#))



Typical Installation

([Installation & Maintenance Instruction Sheet](#)) 2 1/2" - 6"

([Installation & Maintenance Instruction Sheet](#)) 8" - 10"

Local codes shall govern installation requirements. Unless otherwise specified, the assembly shall be mounted at a minimum of 12" (305mm) and a maximum of 30" (762mm) above adequate drains with sufficient side clearance for testing and maintenance. The installation shall be made so that no part of the unit can be submerged.

Capacity thru Schedule 40 Pipe (GPM)				
Pipe size	5 ft/sec	7.5 ft/sec	10ft/sec	15 ft/sec
2 1/2"	75	112	149	224
3"	115	173	230	346
4"	198	298	397	595
6"	450	675	900	1351
8"	780	1169	1559	2339
10"	1229	1843	2458	3687
12"	1763	2644	3525	5288

**Specifications**

The Double Check Detector Backflow Prevention Assembly shall be certified to NSF/ANSI/CAN 61, ASSE® Listed 1048, and supplied with full port gate valves. The main body and access cover shall be 304L Stainless Steel, the seat ring and check valve shall be Noryl™, the stem shall be stainless steel (ASTM A 276) and the seat disc elastomers shall be EPDM. The first and second check valves shall be accessible for maintenance without removing the device from the line. The Double Check Detector Backflow Prevention Assembly shall be a ZURN WILKINS Model 350ASTDA.

Zurn Water, LLC | Wilkins

1747 Commerce Way, Paso Robles, CA U.S.A. 93446 Ph. 855-663-9876, Fax 805-238-5766

In Canada | **Zurn Industries Limited**

7900 Goreway Drive, Unit 10, Brampton, Ontario L6T 5W6, 877-892-5216

www.zurn.com

Submittal Documents

LIDL 1517



Overview	Bid Date: 08-25-2026 Bid Number: 5166172
Section	8" POST IND VALVE

POST INDICATOR VALVE WITH FLANGE ENDS


MODEL - LVPIVFF, LVPIVMJMJ



DESCRIPTION:

- Valves comply with AWWA C515-15 Standard
- Non-Rising Stem, resilient seated (EDPM encapsulated wedge)
- Triple O-Ring Seal
- Available with optional test plug on valve body (special order)
- Post Indicator Valves provided with universal "Indicator Post Plate"
- Mechanical Joint Ends to AWWA C153/A21.53
- Flanged Ends to ANSI B16.1, CLASS 125
- UL/Listed/FM Approved at 300 PSI water working pressure rating
- NSF/ANSI/CAN 61 certified as lead-free for use in drinking water systems
- Temperature range: 42°-180° F
- Fusion bonded epoxy coated interior and exterior to AWWA C550 standard
- Flanged Valves available with hand wheel or operating nut

*Flanged ends shown, LVPIVFF.
Available with Mechanical Joint
(MJ) ends. Model # LVPIVMJMJ



MATERIAL SPECIFICATIONS

PART	MATERIAL	ASTM SPEC.
Body	Ductile Iron	A536 65-45-12
Wedge	Ductile Iron	EPDM Encapsulated
Wedge Nut	Bronze	B62 C83600
Stem	Stainless Steel	ISI 304
Bonnet	Ductile Iron	A536 65-45-12
Gasket	Rubber	EPDM
Gland	Ductile Iron	A536 65-45-12
Thrust Collar	Bronze	B62 C83600
O-Ring	Rubber	EPDM
Post Flange	Ductile Iron	A536 65-45-12
Operating Nut	Ductile Iron	A536 65-45-12
NPT Plug	Bronze	Commercial
Post Flange	Bolt	Stainless Steel AISI 316
Bonnet Bolt	Stainless Steel	AISI 304


VALVE DIMENSIONS

Size (in.)	3	4	5	6	8	10	12
L (in.)	8	9	10	10-1/2	11-1/2	13	14
H (in.)	11-5/8	13-3/4	16-1/8	17-5/16	21-7/16	25-5/8	28-3/4
D (in.)		12	12	12	12	12	12
Weight (lbs.)	41	64	79	103	161	235	339

PROJECT		APPROVAL STAMP
PROJECT:		☐ APPROVED
ADDRESS:		☐ APPROVED AS NOTED
ENGINEER:		☐ NOT APPROVED
SUBMITTAL DATA:		REMARKS:
NOTES 1:		
NOTES 2:		

ADJUSTABLE VERTICAL INDICATOR POST

MODEL LVVIP



FEATURES:

- Meet or Exceed the Requirements of NFPA 24 Standard
- Indicates the State of the Valve OPEN or SHUT Position
- Target Nut to allow 13 to 45 Turns
- “L” Shaped Wrench Handle fitted with a Secure Padlock (provided by user).
- Protected Windows
- Telescoping Operating Rod
- Easily Adjustable Indicator OPEN and SHUT Targets
- UL/ULC 789 Listed and FM1110 Approved

CORROSION PROTECTION:


- Spray Painted Interior and Exterior meet or exceed all applicable of AWWA C550 Standard.
- Stand Barrel: Black Bitumen Coated

FIELD ADJUSTMENTS:

- Remove the post head to adjust OPEN and SHUT signs as required.
- Adjust telescoping rod and pipe to desired length.
- Re-attach the post to the post flange on the valve

ADJUSTABLE VERTICAL INDICATOR POST

MODEL LVVIP



SIZES 4" TO 14"

MATERIAL SPECIFICATIONS

PART	MATERIAL	ASTM SPECIFICATION
Post Head	Gray Cast Iron	A126 Class B
Operating Wrench	Ductile Iron	A536 Grade 65-45-12
Retaining Ring	Stainless Steel	A276 Type 304
Weather Cap	Polyethylene	Commercial
Threaded Sleeve	Stainless Steel	A276 Type 304
Pipe Plug	Malleable Iron	A47 Grade 22010
Target Plate	Aluminum Alloy	ASTM B26
Screw	Carbon Steel	A105
Target Plate	Aluminum Alloy	ASTM B26
Windows	Plexiglass	Commercial
Gasket	Rubber	D2000 NBR
Upper Barrel	Carbon Steel	A53 Type S Grade B
Lower Barrel	Carbon Steel	A53 Type S Grade B
Upper Rod	Carbon Steel	A53 Type S Grade B
Lower Rod	Carbon Steel	A53 Type S Grade B
Base Flange	Cast Iron	A126 Class B
Locking Bolts	Carbon Steel	A307 Grade B
Locking Nuts	Carbon Steel	A 105
Cotter Pin	Stainless Steel	A276 Type 304
Crane Coupling	Carbon Steel	A53 Type S Grade B

DIMENSIONS DATA FOR LANSDALE ADJUSTABLE VERTICAL INDICATOR POST (In)

SIZE	4	6	8	10	12	14
URNS TO OPEN	13	20	26	33	39	45
H0	9.92	13.97	17.48	21.06	24.29	28.62

L= ADJUSTABLE BURY DEPTH RANGE

L	A	B	C	D	E	F	G
MIN	18.25	36	57	78	99	120	148.5
MAX	39.5	60.5	81.5	102.5	123.5	144.5	168

PROJECT	APPROVAL STAMP
PROJECT:	☐ APPROVED
ADDRESS:	☐ APPROVED AS NOTED
ENGINEER:	☐ NOT APPROVED
SUBMITTAL DATA:	REMARKS:
NOTES 1:	
NOTES 2:	




P.I.V (WALL OR VERTICAL POST) TAMPER SWITCH MODEL LVPIVSS



FEATURES:

- **Weight:** .1.323 lbs
- **Temperature Rating:** -40°F - 140°F
- **Enclosure:**
 - Cover:** Die Cast
 - Finish:** Red Powder Coat
 - Base:** Die Cast
 - All parts have corrosion resistant finishes
- **Cover Tamper:**
 - Tamper Resistant Screws
 - Cover Tamper Switch Available
 - 33amps/5amps at 125/250VAC
- **Contact Ratings:**
 - Two sets of SPDT
 - 10amps at 125/250VAC. 2.5 Amps 30VDC resistive
- **Conduit Entrances:** One knockout and one hole for ½" conduit provided
- **Service Use:** NFPA 13, 13D, 13R, 72
- UL/ULC Listed/FM Approved

Dimensions/Inches



PROJECT		APPROVAL STAMP
PROJECT:		☐ APPROVED
ADDRESS:		☐ APPROVED AS NOTED
ENGINEER:		☐ NOT APPROVED
SUBMITTAL DATA:		REMARKS:
NOTES 1:		
NOTES 2:		

Submittal Documents

LIDL 1517



Overview

Bid Date: 08-25-2026
Bid Number: 5166172

Section

8" GATE VALVE ASSEMBLY

The original, and the definitive standard.

RESILIENT WEDGE GATE VALVES

**4" THROUGH 20"
STYLE 7000**



AWWA C515 250 PSI • UL/FM Approved 200 PSI • NSF 61 Certified •
Full Water Way • Fusion Bond Epoxy Coated • 10 Year Limited Warranty



M&H VALVE COMPANY

M&H Valve is a division of McWane, Inc.

www.mh-valve.com



For Generations


RESILIENT WEDGE VALVE

In 1975, M&H recognized the increased requirements and escalating maintenance cost of water systems in the United States.


M&H responded by introducing the first R/W (Resilient Wedge) Valve in America. This introduction revolutionized the valve market in the U.S.

M&H is the first to introduce, and still leads in the design and technical development, of the bubble-tight resilient seating valve.


The M&H Resilient Wedge Valve, with its unique features and benefits, is the first to be manufactured with both AWWA and UL/FM approval for all water system requirements.




7571
MECHANICAL JOINT
4" - 20"




7561
FLANGED
4" - 20"




7572
FLANGED X
MECHANICAL JOINT
4" - 20"




7597
PUSH ON FOR
SDR PVC
4" - 12"




7576
MECHANICAL
CUTTING IN JOINT
4" - 12"




7901
TYTON ENDS FOR D.I.
AND C900 PVC PIPE
4" - 16"




7902
FLANGED X TYTON
4" - 12"




7590
TAPPING X MJ
TAPPING VALVE
4" - 20"




7571-P
MECHANICAL JOINT
POST INDICATOR VALVE
4" - 16"




7068
FLANGED OS&Y
4" - 16"




BEVEL GEARING
HORIZONTAL
INSTALLATION
ALL END STYLES
14" - 20"



SPUR GEARING
VERTICAL
INSTALLATION
ALL END STYLES
14" - 20"



OS&Y BEVEL GEARING
HORIZONTAL INSTALLATION
ALL END STYLES
14" - 20"



OS&Y SPUR
GEARING VERTICAL
INSTALLATION
ALL END STYLES
14" - 20"

NOTE:

It is recommended that valves be installed with stems vertical when used in raw sewage or sludge applications or in water with excessive sediment. Flanged end connections not recommended for buried service.

VALVE SIZE																	NO. OF TURNS TO FULL OPEN				
	A	B	C	E	G	H	J	K	M	N	P	Q	R	S	U	V	NO GEAR	GEARED	W	X	Y
4"	9	4-1/2	6-3/4	14-3/4	4-5/8	6-3/4	-	-	-	-	4-1/2	22-3/4	18-1/4	10	6-3/4	9-1/4	13-1/2	-	-	-	-
6"	10-1/2	5-1/2	7-7/8	19	5-1/4	8	-	-	-	-	5	30-1/8	23-3/4	12	8	10-1/2	19-1/2	-	-	-	-
8"	11-1/2	8-1/8	8-1/2	22-1/2	5-5/8	9-3/4	-	-	-	-	5-1/2	37-3/4	29-1/4	14	10-3/4	13-1/4	25-1/2	-	-	-	-
10"	13	10-1/2	10	26-1/2	7	11-3/4	-	-	-	-	7	45-3/4	35-3/8	18	11-3/4	14-7/8	31-1/2	-	-	-	-
12"	14	10-3/4	11-1/4	30	8-1/2	12-7/8	-	-	-	-	8-1/2	53-1/8	40-3/8	18	12-3/8	15	37-3/4	-	-	-	-
14"	15	10	-	37-3/4	10-1/2	13-1/2	52-1/8	8	48-5/8	9-1/8	-	74-3/4	59-3/4	22	13-1/4	16-3/4	52	100	76	59-7/8	64-1/2
16"	16	10	-	37-3/4	10-1/2	13	51-1/8	8	47-5/8	9-1/8	-	74-3/4	59-3/4	22	12-3/4	16-1/4	52	100	76	59-7/8	64-1/2
18"	17	11-3/4	-	-	-	14-7/8	58	12	55-3/4	10-1/8	-	-	-	-	14-5/8	18-1/8	-	189	90-7/8	70-1/8	74-5/8
20"	18	11	-	-	-	14-1/2	57	12	54-3/4	10-1/8	-	-	-	-	14-1/2	18	-	189	90-7/8	70-1/8	74-5/8

ENGINEERING FEATURES

THRUST BEARINGS

Delrin thrust bearings above and below the thrust collar reduce friction and minimize operating torques.

STAINLESS STEEL HARDWARE

304 stainless steel nuts and bolts provide long-life corrosion protection.

COPPER ALLOY STEM

Long, trouble free life with high strength, non-corrosive copper alloy stem and stem nut.

100% COATED WEDGE

100% coated wedge ensures bubble-tight seal every time up to 250 PSI. With twin seal design.

ELLIPTICAL BOLT HOLES

Hole design on MJ connection eliminates the need for anti-rotation bolts (4" – 12").

EASY STORAGE

Pads on the bottom of all valves keep valve in upright position for easier storage and protection from the elements.

REPLACEABLE O-RINGS

Two O-ring seals are replaceable with the valve fully open and subjected to full-rated working pressure.

NO FLAT GASKETS


O-ring seals at stuffing box and bonnet to body flanges to ensure the best possible seal.

MINIMAL FLOW LOSS

Smooth, unobstructed waterway is free of pockets, cavities, and depressions allowing for minimal flow loss and lower pumping costs. All valves accept full size tapping cutter.

EPOXY COATING

Clow corrosion resistant fusion-bonded epoxy coating, conforming to AWWA C550 and NSF 61 Certified, protects both inside and outside of valve.



VALVE RATING: All valves are rated at 250 PSI for AWWA service and hydrostatically tested to 500 PSI. Valves through 16" are rated at 200 PSI for UL/FM service.



COMMITTED TO ENVIRONMENTAL RESPONSIBILITY

M&H VALVE COMPANY IS COMMITTED TO PROTECTING OUR NATURAL RESOURCES THROUGH ENVIRONMENTALLY RESPONSIBLE MANUFACTURING PRACTICES, INCLUDING THE USE OF 80+% RECYCLED CONTENT IN OUR HYDRANTS AND VALVES.

To learn more about our commitment to the environment, call 256-237-3521

RECOMMENDED SPECIFICATIONS

1. Valves shall conform to the latest revision of AWWA Standard C515 covering resilient seated gate valves for water supply service.
2. The valves shall have a ductile iron body, bonnet, and O-ring plate. The wedge shall be totally encapsulated with rubber.
3. The sealing rubber shall be permanently bonded to the wedge per ASTM D429.
4. Valves shall be supplied with O-ring seals at all pressure retaining joints. No flat gaskets shall be allowed.
5. The valves shall be either non-rising stem or rising stem, opening by turning left or right, and provided with 2" square operating nut or a handwheel with the word "Open" and an arrow to indicate the direction to open.
6. Stems shall be cast copper alloy with integral collars in full compliance with AWWA. All stems shall operate with copper alloy stem nuts independent of wedge and of stem (in NRS valves).
7. Stems shall have two O-rings located above thrust collar and one O-ring below. Stem O-rings shall be replaceable with valve fully opened and subjected to full pressure. The stems on 4" – 20" shall also have two low torque thrust bearings located above and below the stem collar to reduce friction during operation.
8. Waterway shall be smooth, unobstructed and free of all pockets, cavities and depressions in the seat area. Valves 4" and larger shall accept a full size tapping cutter.
9. The body, bonnet and O-ring plate shall be fusion-bond epoxy coated, both interior and exterior on body and bonnet. Epoxy shall be applied in accordance with AWWA C550 and be NSF 61 Certified.
10. Each valve shall have maker's name, pressure rating, and year in which it was manufactured cast in the body. Prior to shipment from the factory, each valve shall be tested by hydrostatic pressure equal to the requirements of AWWA C515 (and UL/FM where applicable).
11. Valves shall have all component parts cast and assembled in the USA and shall be manufactured by the M&H Valve Company.

ISO 9001



www.mh-valve.com



M&H VALVE COMPANY

605 West 23rd Street • Anniston, Alabama 36201
PHONE 256-237-3521 FAX 888-549-5309



For Generations

REQUIREMENT:

- ☐ Class 30B
☐ Class 35B
☐ Ductile Iron



Quality – Service – Commitment – Delivered.

MUNICIPAL VALVE AND SERVICE BOXES

SIZE RANGE:

- Adjustable Slip and Screw Type with standard assembled lengths ranging from 15" to 72" (Lengths do not include risers and/or extensions).

STANDARDS:

- Manufactured from cast iron in accordance with and meet all applicable terms and provisions as per ASTM A48 standard and will meet the minimum tensile strength requirements.
- Sigma Valve Boxes when properly installed can be used for projects related to American Association of State and Highway Officials (AASHTO) standards.

INSTALLATION:

- Per AWWA M44

COATING:

- Black Asphaltic Bituminous paint. Coating thickness of 1 to 2mil is applied on the product.

Extention Height	Components	2 Pc Screw Type	2 Pc Slip Type	Extention Height	Components	3 Pc Screw Type	Extention Height	Components	Screw Type Service Box
19-22	10T + 15B	VB261	VB461	27-37	10T + 12B	VB630AA	24-33	15T + 21B	VB791C
27-37	16T + 24B	VB262	VB462	33-42	10T + 18B	VB630A	30-39	15T + 27B	VB792C
39-50	16T + 36B	VB264	VB464	39-49	16T + 24B	VB630B	30-42	18T + 27B	VB792D
39-60	26T + 36B	VB266	VB466B / VB466N*	45-54	16T + 30B	VB630C	36-48	18T + 33B	VB793D
50-71	26T + 48B	VB267	VB467	51-60	16T + 36B	VB630CC	36-54	24T + 33B	VB793E
63-81	26T + 60B	VB268	VB468	45-66	26T + 30B	VB630D	42-60	24T + 39B	VB794E
				51-72	26T + 36B	VB630DD	41-64	30T + 39B	VB795E
				63-84	26T + 48B	VB630F			
				74-94	26T + 60B	VB630G			
			B = With Flange N = Without Flange	NOTE: Requires use of base - Above ships with VB6306 base standard - Other sizes available					

**** ADD -35 TO ITEM # FOR CLASS 35B GREY IRON REQUIREMENTS / ADD -D FOR DUCTILE IRON REQUIREMENTS**
RISERS, EXTENSIONS AND VARIOUS SPECIALLY LETTERED LIDS AVAILABLE FOR ALL ITEMS




700 Goldman Drive
 Cream Ridge, NJ 08514
 CRMCSR@sigmaco.com

5000 Askins Lane
 Houston, TX 77093
 HTNCSR@sigmaco.com

4652 E. Guasti Rd
 Ontario, CA 91761
 ONTCRSR@sigmaco.com

21699 Torrence Avenue
 Sauk Village, IL 60411
 CHICSR@sigmaco.com

Highway 22 West
 Alexander City, AL 35010
 ALXCSR@sigmaco.com



SECTION "A - A"


Masonry Supply, Inc

P.O. BOX 943
SELMA, NC 27576
PH: (919) 351-4014 (office), (919) 291-8761 (cell) FAX: (919) 351-4047
EMAIL: masonrysupply@hotmail.com

ITEM: 24" CONCRETE VALVE BOX COLLAR

PART # MSVB - 24

MATERIAL SPEC: A - 3 CONCRETE (4000 psi @28 DAYS)



Notes:

1. Made of minimum 4000 PSI Concrete
2. Height - 4', width of sides - 5"
3. 3/4" chamfers on front corners
4. Four pieces of #3 rebar
5. Two inch brass marker plate with anchor
6. Lettering stamped on marker as specified in 3" letters
 Standard Marker = MV (Main Valve) top front
 = BO (Blow-off) bottom front
 = AV (Air Release Valve)
 = LM (Line Marker)

Masonry Supply, Inc

P.O. BOX 943
 SELMA, NC 27576

PH: (919) 351-4014 (office), (919) 291-8761 (cell) FAX: (919) 351-4047
 EMAIL: masonrysupply@hotmail.com

ITEM: PRECAST CONCRETE 4 FT TALL MARKING POSTS W/BRASS

PART # MMVB 04 W/BR

MATERIAL SPEC: A - 3 CONCRETE (4000 psi @28 DAYS)