



Lidl US, LLC
3500 S. Clark St.
Arlington , Virginia 22202
P: (571) 398-5435

Project: 1517 Norcross GA - Jimmy Carter Blvd
4990 Jimmy Carter Blvd
Norcross, Georgia 30093

Submittal #1-3.0 - CCTV Submittal 1 - Default Section

Revision	0	Submittal Manager	Christopher Manes (21327198 CHA Consulting, INC.)
Status	Open	Date Created	Sep 18, 2026
Issue Date	Sep 18, 2026	Spec Section	1 - Default Section
Responsible Contractor	Place Services Inc.	Received From	Tucker Teague (Place Services Inc.)
Received Date	Sep 25, 2026	Submit By	Sep 18, 2026
Final Due Date		Lead Time	
		Cost Code	
Location		Type	Product Manual
Submittal Package			
Approvers			
Ball in Court	Christopher Manes (21327198 CHA Consulting, INC.)		
Distribution	Bobby McTeague (Place Services Inc.), Christopher Manes (21327198 CHA Consulting, INC.), JaWanna English-Neal (21327198 CHA Consulting, INC.), Jeff Belyea (21327198 CHA Consulting, INC.), Jens Byer (28101155 Lidl US, LLC), Luis Marcelino (Place Services Inc.), Todd Seldomridge (21327198 CHA Consulting, INC.), Tucker Teague (Place Services Inc.)		
Description	Place Services Inc. - No Exceptions Taken		

Submittal Workflow

Name	Sent Date	Due Date	Returned Date	Response	Attachments
General Information Attachments					#1517 Lidl Norcross, GA - CCTV Submittal.pdf

Lidl 1517 Norcross, GA - Ground Up

4990 Jimmy Carter Blvd. Norcorss, GA 30093

Report generated by Tucker Teague (Place Services, Inc.)



Submittal #PSI-0007 - CCTV Submittal

Creator	Tucker Teague (Place Services, Inc.)	Submission due	-
Assignee	Tucker Teague (Place Services, Inc.)	Response due	09/25/2026
Reviewers	-	Closed on	-
Status	Pending approval	Reference number	-
Type	Product data	Specification	-
Description	-		

Approval (rev. 0)

Responded by	-	Responded on	-
Response	-		
Notes	-		
Attachments	-		

Submission (rev. 0)

Submitted by	Tucker Teague (Place Services, Inc.)	Submitted on	09/18/2026
Notes	Place Services Inc. - No Exceptions Taken		
Attachments	PDF attachments are included in this export. ↓ CCTV Submittal.pdf (Page 2)		

UTILICOM

SUPPLY ASSOCIATES

CCTV SUBMITTALS

DATE	8/31/26
CUSTOMER	R.J. HAYNIE & ASSOCIATES
PROJECT	GWINNETT COUNTY - TS-082
LOCATION	JIMMY CARTER BLVD @ SHELBY DR
CUSTOMER PO#	34830817JH
USA QUOTE #	62085 (CCTV ONLY)

MFR. PART#	DESCRIPTION	MANUFACTURER	CERT #
Q6086-EUS	ICONIC PTZ CAMERA WITH 4 MEGAPIXELS, LIGHT-SENSITIVE ½" SENSOR, 34X OPTICAL ZOOM	AXIS	CUT SHEET
MOS64AP-BK-100F	CAT 6 600MHZ OUTDOOR RATED CABLE RJ45 SHIELDED CONNECTORS ON EACH END, 100FT. LENGTH	MAJOR CUSTOM CABLE	CUT SHEET
DTK-MRJPOES	POWER/VIDEO/DATA SURGE PROTECTION GIG ETHERNET FOR SHIELDED CABLE **	DITEK	CUT SHEET
TQ5001-E	CCTV WALL AND POLE MOUNT	AXIS	CUT SHEET

SHOP DRAWING / SUBMITTAL REVIEW

- ☒ NO EXCEPTION TAKEN
☐ REVISE AND RESUBMIT
☐ MAKE CORRECTIONS NOTED
☐ REJECTED

SUBMITTAL WAS REVIEWED FOR DESIGN CONFORMITY AND GENERAL CONFORMANCE TO CONTRACT DOCUMENTS ONLY. THE CONTRACTOR IS RESPONSIBLE FOR CONFIRMING AND CORRELATING DIMENSIONS AT JOBSITE FOR TOLERANCE, CLEARANCE, QUANTITIES, FABRICATION PROCESSES AND TECHNIQUES OF CONSTRUCTION, COORDINATION OF HIS WORK WITH OTHER TRADES AND FULL COMPLIANCE WITH CONTRACT DOCUMENTS.

By: Tucker Teague

Date: 9/18/2026

Place Services, Inc
Canton, GA 30115

AXIS Q6086-E PTZ Camera

Iconic PTZ with 4 MP and great light sensitivity

AXIS Q6086-E features an extremely light-sensitive 1/2" sensor, 34x optical zoom, and laser focus. Built on ARTPEC-9, it supports AV1 codec and offers accelerated performance to run impressive analytics applications on the edge. For instance, AXIS Object Analytics can detect and classify different objects. This IP66-, IK10-, NEMA 4x-, and NEMA TS2-rated camera is both impact and weather-resistant. Axis Zipstream with support for AV1, H.264, and H.265 significantly lowers bandwidth and storage requirements. Furthermore, Axis Edge Vault safeguards your device and protects sensitive information from unauthorized access.

- > **Highly light-sensitive 1/2" sensor**
- > **Lightfinder 2.0 and Forensic WDR**
- > **Next-generation AI-powered analytics**
- > **Precise laser focus and 34x optical zoom**
- > **Built-in cybersecurity with Axis Edge Vault**



AXIS Q6086-E PTZ Camera

Camera

Image sensor

1/2" progressive scan RGB CMOS
Pixel size: 2.9 µm

Lens

Varifocal, 6.64 – 225.5 mm, F1.7–5.1
Horizontal field of view: 61.5°–2.0°
Vertical field of view: 37.3°–1.1°
Minimum focus distance: 3 m (9.8 ft)
Laser focus, autofocus, P-iris

Day and night

Automatic IR-cut filter
Removable infrared-pass filter

Minimum illumination

Color: 0.07 lux at 30 IRE, F1.7
B/W: 0.005 lux at 30 IRE, F1.7
Color: 0.1 lux at 50 IRE, F1.7
B/W: 0.009 lux at 50 IRE, F1.7

Shutter speed

1/49500 s to 2 s

Pan/Tilt/Zoom

Pan: 360° endless, 0.05°–500°/s
Tilt: 0 to -90°, 0.05°–500°/s
Zoom: 34x optical, 12x digital, total 408x zoom
Preset accuracy: 0.10°
Nadir flip, 300 preset positions, tour recording (max 10, max duration 16 minutes each), guard tour (max 100), control queue, on-screen directional indicator, orientation aid PTZ, set new pan 0°, adjustable zoom speed

System on chip (SoC)

Model

ARTPEC-9

Memory

4096 MB RAM, 8192 MB Flash

Compute capabilities

Deep learning processing unit (DLPU)

Video

Video compression

H.264 (MPEG-4 Part 10/AVC) Baseline, Main and High Profiles
H.265 (MPEG-H Part 2/HEVC) Main Profile
AV1
Motion JPEG

Resolution

2688x1512 (4MP) to 640x360

Frame rate

Up to 50/60 fps (50/60 Hz) in all resolutions
Automatic switching

Video streaming

Up to 20 unique and configurable video streams¹
Axis Zipstream technology in H.264, H.265 and AV1
Controllable frame rate and bandwidth
VBR/ABR/MBR H.264/H.265/AV1
Low latency mode
Video streaming indicator

Signal-to-noise ratio

>55 dB

WDR

Forensic WDR: Up to 120 dB depending on scene

Noise reduction

Spatial filter (2D noise reduction)
Temporal filter (3D noise reduction)

Image settings

Saturation, contrast, brightness, sharpness, white balance, day/night threshold, local contrast, tone mapping, exposure mode, exposure zones, defog, compression, rotation: 0°, 180°, text and image overlay, overlay widget, 100 individual polygon privacy masks including mosaic and chameleon privacy masks, lock aperture, target aperture, image stabilization (EIS), image freeze on PTZ
Scene profiles: outdoor, indoor, forensic, traffic overview, license plate

Image processing

Axis Zipstream, Forensic WDR, Lightfinder 2.0

1. We recommend a maximum of 3 unique video streams per camera or channel, for optimized user experience, network bandwidth, and storage utilization. A unique video stream can be served to many video clients in the network using multicast or unicast transport method via built-in stream reuse functionality.

Audio

Input and output through portcast technology accessories or edge-to-edge pairing. For more information, see *Optional accessories* and *Edge-to-edge*.

Network

Network protocols

IPv4, IPv6 USGv6, ICMPv4/ICMPv6, HTTP, HTTPS², HTTP/2, TLS², QoS Layer 3 DiffServ, FTP, SFTP, CIFS/SMB, SMTP, mDNS (Bonjour), UPnP®, SNMP v1/v2c/v3 (MIB-II), DNS/DNSv6, DDNS, NTP, PTP, NTS, RTSP, RTP, SRTP/RTSPS, TCP, UDP, IGMPv1/v2/v3, RTCP, ICMP, DHCPv4/v6, ARP, SSH, NTCIP, LLDP, CDP, MQTT v3.1.1, Secure syslog (RFC 3164/5424, UDP/TCP/TLS), Link-Local address (ZeroConf)

System integration

Application Programming Interface

Open API for software integration, including VAPIX®, metadata and AXIS Camera Application Platform (ACAP); specifications at axis.com/developer-community.

One-click cloud connection

ONVIF® Profile G, ONVIF® Profile M, ONVIF® Profile S, and ONVIF® Profile T, specifications at onvif.org

Video management systems

Compatible with AXIS Camera Station Edge, AXIS Camera Station Pro, AXIS Camera Station 5, and video management software from Axis' partners available at axis.com/vms.

Onscreen controls

Privacy masks
Day/night shift
Quick zoom
Autotracking
Defog
Heater
Orientation aid
Media clip

Edge-to-edge

Speaker pairing
Radar pairing

Event conditions

Device status: above/below/within operating temperature, fan failure, IP address blocked/removed, live stream active, network lost, new IP address, shock detected, system ready

Edge storage: recording ongoing, storage disruption, storage health issues detected

I/O: manual trigger, virtual input is active

MQTT: MQTT client connected

PTZ: PTZ control queue, PTZ malfunctioning, PTZ movement, PTZ preset position reached, PTZ ready

Scheduled and recurring: schedule

Video: average bitrate degradation, day-night mode

Event actions

Day-night mode

Defog

Guard tour: run guard tour while the rule is active, start guard tour

Guard tour (recorded): run recorded guard tour while the rule is active

MQTT: send MQTT publish message

Notification: HTTP, HTTPS, TCP and email

Overlay text

Preset positions: go to preset position, go to preset position while the rule is active

Recordings: record video, record video while the rule is active

Security: erase configuration

SNMP trap messages: send, send while the rule is active

Tracking: start temporary detection, toggle autotracking/autotracking profile, toggle autotracking/autotracking profile while the rule is active

Images or video clips: FTP, SFTP, HTTP, HTTPS, network share and email

WDR mode

Built-in installation aids

Pixel counter, level grid

Analytics

Applications

Included

AXIS Object Analytics, AXIS Image Health Analytics, AXIS Scene Metadata, AXIS Live Privacy Shield³, AXIS Video Motion Detection, autotracking, active gatekeeper

Supported

AXIS People Counter

Support for AXIS Camera Application Platform enabling installation of third-party applications, see axis.com/acap

2. This product includes software developed by the OpenSSL Project for use in the OpenSSL Toolkit. (openssl.org), and cryptographic software written by Eric Young (ey@cryptsoft.com).

3. Available for download

AXIS Object Analytics

Object classes: humans, vehicles (types: cars, buses, trucks, bikes, other)

Scenarios: line crossing, object in area, time in area, crossline counting, occupancy in area, tailgating detection, PPE monitoring^{BETA}, motion in area, motion line crossing

Up to 10 scenarios

Other features: triggered objects visualized with trajectories, color-coded bounding boxes and tables

Polygon include/exclude areas

Perspective configuration

ONVIF Motion Alarm event

AXIS Image Health Analytics

Detection settings:

Tampering: blocked image, redirected image

Image degradation: blurred image, underexposed image

Other features: sensitivity, validation period

AXIS Scene Metadata

Object classes: humans, faces, vehicles (types: cars, buses, trucks, bikes), license plates

Object attributes: vehicle color, upper/lower clothing color, confidence, position

Approvals

Product markings

CE, FCC, ICES, KC, VCCI

Supply chain

TAA compliant

EMC

CISPR 35, CISPR 32 Class A, EN 55035,

EN 55032 Class A, EN 50121-4, EN 61000-3-2,

EN 61000-3-3, EN 61000-6-1, EN 61000-6-2

Australia/New Zealand: RCM AS/NZS CISPR 32 Class A

Canada: ICES-3(A)/NMB-3(A)

Japan: VCCI Class A

Korea: KS C 9835, KS C 9832 Class A

USA: FCC Part 15 Subpart B Class A

Railway: IEC 62236-4

Safety

CAN/CSA C22.2 No. 62368-1 ed. 3,

IEC/EN/ 60825-1 Class 1, IEC/EN/UL 62368-1 ed. 3,

RCM AS/NZS 62368.1:2022

Environment

IEC 60068-2-1, IEC 60068-2-2, IEC 60068-2-6,

IEC 60068-2-14, IEC 60068-2-27, IEC 60068-2-78,

IEC/EN 60529 IP66/IP67, IEC/EN 62262 IK10,

ISO 21207 (Method B), ISO 12944-6: C5, NEMA 250

Type 4X, NEMA TS 2 (2.2.7-2.2.9), MIL-STD-810H

(Method 501.7, 502.7, 505.7, 506.6, 507.6, 509.7, 510.7, 512.6, 521.4)

Network

NIST SP500-267

Cybersecurity

ETSI EN 303 645, BSI IT Security Label, FIPS 140

Cybersecurity

Edge security

Software: Signed OS, brute force delay protection, digest authentication and OAuth 2.0 RFC6749 Client Credential Flow/OpenID Authorization Code Flow for centralized ADFS account management, password protection, Axis Cryptographic Module (FIPS 140-3 level 3)

Hardware: Axis Edge Vault cybersecurity platform
Secure keystore: secure element (CC EAL 6+, FIPS 140-3 Level 3), system-on-chip security (TEE)
Axis device ID, signed video, secure boot, encrypted filesystem (AES-XTS-Plain64 256bit)

Network security

IEEE 802.1X (EAP-TLS, PEAP-MSCHAPv2)⁴,

IEEE 802.1AE (MACsec PSK/EAP-TLS), IEEE 802.1AR,

HTTPS/HSTS⁴, TLS v1.2/v1.3⁴, Network Time Security

(NTS), X.509 Certificate PKI, host-based firewall

Documentation

AXIS OS Hardening Guide

Axis Vulnerability Management Policy

Axis Security Development Model

AXIS OS Software Bill of Material (SBOM)

To download documents, go to axis.com/support/cybersecurity/resources

To read more about Axis cybersecurity support, go to axis.com/cybersecurity

4. This product includes software developed by the OpenSSL Project for use in the OpenSSL Toolkit. (openssl.org), and cryptographic software written by Eric Young (eay@cryptsoft.com).

General

Casing

IP66-, IP67-, NEMA 4X- and IK10-rated
Polycarbonate hard-coated dome
Aluminum casing
Color: white NCS S 1002-B
For repainting instructions, go to the product's support page. For information about the impact on warranty, go to axis.com/warranty-implication-when-repainting.

Power

Power over Ethernet (PoE) IEEE 802.3bt, Class 6
Typical 10 W, max 51 W
Features: dynamic power mode, power profiles, power meter

Connectors

Network: RJ45 10BASE-T/100BASE-TX/1000BASE-T PoE
RJ45 Push-pull Connector (IP66/IP67)

Storage

Support for SD/SDHC/SDXC card
Support for SD card encryption (AES-XTS-Plain64 256bit)
Recording to network-attached storage (NAS)
For SD card and NAS recommendations see axis.com

Operating conditions

Full power with 60 W midspan: -50 °C to 55 °C (-58 °F to 131 °F)
Maximum temperature according to NEMA TS 2 (2.2.7): 74 °C (165 °F)
Arctic temperature control: Start-up as low as -40 °C (-40 °F)
Humidity: 10–100% RH (condensing)

Storage conditions

-40 °C to 65 °C (-40 °F to 149 °F)
Humidity 5-95% RH (non-condensing)

Dimensions

For the overall product dimensions, see the dimension drawing in this datasheet.
Effective Projected Area (EPA): 0.046 m² (0.5 ft²)

Weight

4100 g (9 lb)

Box content

Camera, weathershield, installation guide, 90 W Midspan (including power cable)⁵, RJ45 Push-pull Connector (IP66), owner authentication key

System tools

AXIS Site Designer, AXIS Device Manager, product selector, accessory selector, lens calculator
Available at axis.com

Languages

English, German, French, Spanish, Italian, Russian, Simplified Chinese, Japanese, Korean, Portuguese, Polish, Traditional Chinese, Dutch, Czech, Swedish, Finnish, Turkish, Thai, Vietnamese

Warranty

5-year warranty, see axis.com/warranty

Software support

New feature development until 2030 (AXIS OS 12, 13 and 14)
Support until 2035-12-31 (AXIS OS LTS 2030–2035)
Read more about the AXIS OS lifecycle at help.axis.com/axis-os

Part numbers

Available at axis.com/products/axis-q6086-e#part-numbers

Optional accessories

Portcast

AXIS TU8003 90 W Connectivity Midspan

Installation

AXIS T8415 Wireless Installation Tool

Mounting

AXIS T91/T94/TQ Mounting Accessories

Storage

AXIS Surveillance Cards

Smoked dome

For more accessories, go to axis.com/products/axis-q6086-e#compatible-products

Sustainability

Substance control

PVC free, BFR/CFR free in accordance with JEDEC/ECA Standard JS709
RoHS in accordance with EU RoHS Directive 2011/65/EU and 2015/863, and standard EN IEC 63000:2018
REACH in accordance with (EC) No 1907/2006. For SCIP UUID, see echa.europa.eu

5. Not included for AXIS Q6086-E NM

Materials

Renewable carbon-based plastic content: 71%

(recycled: 1%, bio-based: 70%)

Screened for conflict minerals in accordance with OECD guidelines

To read more about sustainability at Axis, go to axis.com/about-axis/sustainability

Environmental responsibility

axis.com/environmental-responsibility

Axis Communications is a signatory of the UN Global Compact, read more at unglobalcompact.org

Power-optimized performance

Power

PoE, IEEE 802.3bt, Class 6

Low power profile: typical 10 W, max 25.5 W

PoE, IEEE 802.3at, Class 4

Full power profile: typical 10 W, max 25.5 W

Low power profile: typical 10 W, max 25.5 W

Operating conditions


Full power profile with 30 W midspan: -20 °C to 55 °C (-4 °F to 131 °F)

Low power profile with 30 W or 60 W midspan: -20 °C to 55 °C (-4 °F to 131 °F)

Detect, Observe, Recognize, Identify (DORI)

	DORI definition	Distance (wide)	Distance (tele)
Detect	25 px/m (8 px/ft)	92.6 m (303.7 ft)	3118.4 m (10228.4 ft)
Observe	63 px/m (19 px/ft)	36.7 m (120.4 ft)	1237.5 m (4059.0 ft)
Recognize	125 px/m (38 px/ft)	18.5 m (60.7 ft)	623.6 m (2045.4 ft)
Identify	250 px/m (76 px/ft)	9.3 m (30.5 ft)	311.8 m (1022.7 ft)

The DORI values are calculated using pixel densities for different use cases as recommended by the EN-62676-4 standard. The calculations use the center of the image as the reference point and consider lens distortion. The possibility to recognize or identify a person or object depends on factors such as object motion, video compression, lighting conditions, and camera focus. Use margins when planning. The pixel density varies across the image, and the calculated values can differ from the distances in the real world.



Dimensions in mm [inch]			
Year	Version	Scale	Notes
2025 Apr-11	M1.3	1:5	
Drawn/Updated	Axis	Axis	
3199327	A3	1(1)	

SCALE 1:5

Q608X PTZ Camera

Highlighted capabilities

AV1

AV1 is a modern video encoding standard optimized for video transmission over the internet by Alliance for Open Media (AoM). It was designed to provide better compression efficiency than older codecs including H.264 (also known as AVC) and H.265 (HEVC), while being royalty-free and open-source.

AXIS Object Analytics

AXIS Object Analytics is a preinstalled, multifeatured video analytics that detects and classifies humans, vehicles, and types of vehicles. Thanks to AI-based algorithms and behavioral conditions, it analyzes the scene and their spatial behavior within – all tailored to your specific needs. Scalable and edge-based, it requires minimum effort to set up and supports various scenarios running simultaneously.

Laser focus

Laser focus helps cameras find focus even faster than cameras with autofocus only. It finds focus in challenging lighting conditions, such as scenes with low light or contrast. The out-of-the-box-ready feature is a fully automatic solution, requiring neither setting nor programming to work. As soon as the camera is turned on, the laser focus starts working. The laser focus feature includes a laser that assists focusing by providing a reference point. The laser module has a transmitter and a receiver. The transmitter sends out a laser ray that bounces off an object and returns to the receiver, providing the camera with a focus reference point. The IR light of the laser focus is neither visible nor harmful, and has a wavelength of 905 nm. The laser focus feature verifies focus continuously when the scene changes. Since the camera already knows the distance to the object, it knows where to start searching, and the entire process is performed automatically within a fraction of a second.

For more information, see axis.com/glossary

4

3

2

1

D

D

C


C

B

B

A

A



PRODUCT INFORMATION:

- 1.) CAT 6 600MHz OUTDOOR RATED DIRECT BURIAL
- 2.) 23AWG SOLID BARE COPPER CONDUCTORS
- 3.) ALUMINUM FOIL SHIELD WITH A DRAIN WIRE
- 4.) OUTER JACKET MATERIAL: LDPE
- 5.) OPERATING TEMP RANGE -40°C TO $+60^{\circ}\text{C}$
- 6.) STRAIN RELIEF BOOTS INSTALLED ON EACH END



FILE NAME	
CONTRACT NO	N/A
DRAWN	10/19/16 JOELH
CHECK	10/19/16 JOSHWA
APPR.	10/19/16 JOSHWA
ISSUED	10/19/16 JOELH

CUSTOMER SPEC			
MOS64AP-BK			
RJ45S/45S CAT 6 SHIELDED OSP			
SIZE	FSCM NO	DWG NO	REV
C		MOS64AP-BK	A

PINOUT		
RJ45S	DRAIN	RJ45S
CASE		CASE
1	WH/OR	1
2	OR/WH	2
3	WH/GN	3
4	BL/WH	4
5	WH/BL	5
6	GN/WH	6
7	WH/BR	7
8	BR/WH	8



DTK-MRJPOES

Power over Ethernet Surge Protector

DITEK's DTK-MRJPOES protects circuits that use state-of-the-art Power over Ethernet connections. This point of use surge protector is compatible with CAT5e, CAT6 and CAT6A cabling infrastructure; and can be installed either at the equipment end, or ahead of injectors or network switches. Its multi-stage, hybrid design provides superior protection for PoE applications. When used with shielded twisted pair (STP) cabling, the DTK-MRJPOES does not require a separate earth ground.



Product Features

- Hybrid design utilizing SAD and GDT technologies for optimal protection
- Supports data speeds up to 10GbE without signal degradation
- RJ45 female connections with external grounding screw
- Complies with all IEEE Power over Ethernet standards
- UL497B Listed

Applications

- PoE IP Camera, NVR's
- Wireless Access Points
- Audio/Video Touch Pads and Screens
- Access Control
- PoE Lighting

Accessories

- DIN Rail Mounting Kit, p/n DTK-DRK

Technical Specifications

Service Voltage:	<60V
Protection Modes:	Common (All), Differential (All)
Clamping Voltage:	Common Mode: 75V Differential Mode: 7.22V
Surge Current Rating:	20kA / Pair
Power Handling:	Up to 144 Watts
Data Rate:	Up to 10GbE

Mechanical Specifications

Connection Method:	Shielded RJ45 Female In/Out
Housing:	ABS
Operating Temperature:	-40°F – 158°F (-40°C – 70°C)
Maximum Humidity:	95% non-condensing
Dimensions:	3.0" L X 1.7" W x 1.2" H (76 mm x 43 mm x 30 mm)
Weight:	4 oz (113 g)

Quality Standards & Approvals

Certifications:	UL497B
Standards Compliance:	CAT5e, EIA/TIA 568A, EIA/TIA 568B
Certifications:	FDOT APL# 620-004-009
Warranty:	10 Year Limited Warranty

IEEE PoE Standard	Wattage	Compatible
802.3af	15.4 W	Yes
802.3at	30 W	Yes
802.3bt Type 3	60 W	Yes
802.3bt Type 4	100 W	Yes

Find us in
MasterSpec
a product of The American Institute of Architects



AXIS TQ5001-E Wall-and-Pole Mount

Robust mount for PTZ cameras

With this wall-and-pole mount, installers can choose between using an RJ45 or IDC (insulation-displacement contact) connector for the installation. It features a built-in cable with an Ethernet IP66-rated RJ45 connector to facilitate installation and prevent water and dust from entering the camera. Made from impact-resistant, outdoor-ready material, AXIS TQ5001-E is suited for both indoor and outdoor environments. Flipping the mounting bracket makes it possible to turn AXIS TQ5001-E from a wall mount to a pole mount (AXIS Steel Straps TX30 are required). The mount is also suitable for corner mounting with an optional accessory.

- > **Robust, IK10-rated**
- > **For indoor and outdoor use**
- > **Versatile connection with IDC connector**
- > **Built-in IP66-rated RJ45 connector**
- > **5-year warranty**



AXIS TQ5001-E Wall-and-Pole Mount

Approvals

Product markings	CSA, UL/cUL, UKCA, CE, KC, VCCI, RCM
Supply chain	TAA compliant
EMC	CISPR 35, CISPR 32 Class A, EN 55035, EN 55032 Class A, EN 50121-4, EN 61000-6-1, EN 61000-6-2 Australia/New Zealand: RCM AS/NZS CISPR 32 Class A Canada: ICES-3(A)/NMB-3(A) Japan: VCCI Class A Korea: KS C 9835, KS C 9832 Class A USA: FCC Part 15 Subpart B Class A Railway: IEC 62236-4
Safety	CAN/CSA C22.2 No. 62368-1 ed. 3, IEC/EN/UL 62368-1 ed. 3
Environment	IEC 60068-2-1, IEC 60068-2-2, IEC 60068-2-6, IEC 60068-2-27, IEC/EN 60529 IP66, IEC/EN 62262 IK10, NEMA 250 Type 4X, MIL-STD 810G 509.5


General

Supported products	AXIS P55 Series AXIS P56 Series AXIS Q37 Series AXIS Q60 Series AXIS Q61 Series For a complete list of compatible cameras, go to axis.com/products/axis-tq5001-e-wall-and-pole-mount#compatible-products
Casing	IP66-, NEMA 4X- and IK10-rated Aluminum casing Color: white NCS S 1002-B
Mounting	Back: Cable hole Bottom: 3/4" (M25) conduit side entries
Connectors	Output: IP66, RJ45 Ethernet (male) Input: RJ45 Ethernet (female), IDC
Operating conditions	-50 °C to 65 °C (-58 °F to 149 °F) Humidity 10–100% RH (non-condensing)
Storage conditions	-40 °C to 65 °C (-40 °F to 149 °F) Humidity 10–100% RH (non-condensing)
Dimensions	For the overall product dimensions, see the dimension drawing in this datasheet.
Weight	1960 g (4.3 lb) Maximum load: 40 kg (88.2 lb)
Box content	Mount, wall bracket, installation guide, cable ties, RJ45 mounting tool
Optional accessories	AXIS ACI Conduit Adapters AXIS T91A64 Corner Bracket AXIS Steel Straps TX30 570 mm AXIS Steel Straps TX30 1450 mm For more accessories, go to axis.com/products
Warranty	5-year warranty, see axis.com/warranty
Part numbers	Available at axis.com/products/axis-tq5001-e-wall-and-pole-mount#part-numbers

Sustainability

Substance control	PVC free
Materials	Screened for conflict minerals in accordance with OECD guidelines To read more about sustainability at Axis, go to axis.com/about-axis/sustainability
Environmental responsibility	axis.com/environmental-responsibility Axis Communications is a signatory of the UN Global Compact, read more at unglobalcompact.org

Dimension drawing



AXIS TQ5001-E Wall-and-Pole Mount

www.axis.com

Revision	v.01	Revision date	2023-09-11
Paper size	A4	Release date	2023-09-11
Created by	MS	Scale	1:6

© 2023 Axis Communications